

A project of Volunteers in Asia

The Co-composting of Domestic Solid and Human Wastes

By: Letitia A. Obeng and Frederick W. Wright  
WB TP#7/UNDP PMR#7

Published by: IBRD  
1818 H Street, N.W.  
Washington, DC 20433

Available from: Publications Sales Unit  
The World Bank  
1818 H Street, N.W.  
Washington, DC 20433

Reproduced with permission.

Reproduction of this microfiche document in any form is subject to the same restrictions as those of the original document.

# **Integrated Resource Recovery**

**UNDP Project Management Report Number 7**

INTEGRATED RESOURCE RECOVERY SERIES  
GLO/80/004, GLO/80/007  
NUMBER 7

This is the seventh in a series of reports being prepared by the Resource Recovery Project as part of a global effort to realize the goal of the United Nations International Drinking Water Supply and Sanitation Decade, which is to extend domestic and community water supply and sanitation services throughout the developing world during 1981 to 1990. The project objective is to encourage resource recovery as a means of offsetting some of the costs of community sanitation.

Other volumes published to date include:

1. Recycling from Municipal Refuse: A State-of-the Art Review and Annotated Bibliography (Technical Paper No. 30) by S. Cointreau et al.
2. Remanufacturing: The Experience of the United States and Implications for Developing Countries (Technical Paper No. 31) by R. T. Lund.
3. Aquaculture: A Component of Low Cost Sanitation Technology (Technical Paper No. 36) by P. Edwards.
4. Municipal Waste Processing in Europe: A Status Report on Selected Materials and Energy Recovery Projects (Technical Note No. 37) by J. G. Abert.
5. Anaerobic Digestion: Principles and Practices for Biogas Systems (Technical Paper No. 49) by C. G. Gunnerson and D. C. Stuckey et al.
6. Wastewater Irrigation in Developing Countries: Health Effects and Technical Solutions (Technical Paper No. 51) by H. Shuval et al.

Photographs (from top to bottom, left to right): Workers show how compost can be used to improve the quality of soil for agricultural purposes. A range of different waste materials can be efficiently composted if the right mix of carbon and nitrogen is provided in the materials. Here garbage is placed on a conveyer belt for sorting out noncompostible matter, and sludge from a septic tank is mixed with paper wastes and wood chips for co-composting. Aeration of composting materials can be carried out in a variety of ways. These include by hand-turning, provided proper protective clothing is worn; by using windrow machines or tractors to turn windrows of composting materials, here made up of garbage and sludge; and by forced aeration in which air is blown or drawn through a static pile by a small horsepower motor. The large amount of heat generated destroys disease-causing organisms.

# **The Co-composting of Domestic Solid and Human Wastes**

**Letitia A. Obeng and Frederick W. Wright**

**The World Bank  
Washington, D.C.**

**The International Bank for Reconstruction  
and Development/THE WORLD BANK  
1818 H Street, N.W.  
Washington, D.C. 20433, U.S.A.**

**All rights reserved  
Manufactured in the United States of America  
First printing March 1987**

Technical Papers are not formal publications of the World Bank, and are circulated to encourage discussion and comment and to communicate the results of the Bank's work quickly to the development community; citation and the use of these papers should take account of their provisional character. The findings, interpretations, and conclusions expressed in this paper are entirely those of the author(s) and should not be attributed in any manner to the World Bank, to its affiliated organizations, or to members of its Board of Executive Directors or the countries they represent. Any maps that accompany the text have been prepared solely for the convenience of readers; the designations and presentation of material in them do not imply the expression of any opinion whatsoever on the part of the World Bank, its affiliates, or its Board or member countries concerning the legal status of any country, territory, city, or area or of the authorities thereof or concerning the delimitation of its boundaries or its national affiliation.

Because of the informality and to present the results of research with the least possible delay, the typescript has not been prepared in accordance with the procedures appropriate to formal printed texts, and the World Bank accepts no responsibility for errors. The publication is supplied at a token charge to defray part of the cost of manufacture and distribution.

The most recent World Bank publications are described in the catalog *New Publications*, a new edition of which is issued in the spring and fall of each year. The complete backlist of publications is shown in the annual *Index of Publications*, which contains an alphabetical title list and indexes of subjects, authors, and countries and regions; it is of value principally to libraries and institutional purchasers. The continuing research program is described in *The World Bank Research Program: Abstracts of Current Studies*, which is issued annually. The latest edition of each of these is available free of charge from the Publications Sales Unit, Department F, The World Bank, 1818 H Street, N.W., Washington, D.C. 20433, U.S.A., or from Publications, The World Bank, 66, avenue d'Iéna, 75116 Paris, France.

**Letitia A. Obeng is an economist and Frederick W. Wright a project officer in the Applied Technology Unit of the Water and Urban Development Department at the World Bank.**

**Library of Congress Cataloging-in-Publication Data**

**Obeng, Letitia A., 1954-**

**Co-composting of domestic solid and human wastes.**

**(World Bank technical paper, ISSN 0253-7494 ; no. 57)**

**Bibliography: p.**

**1. Compost. 2. Recycling (Waste, etc.)--Developing countries. I. Wright, Frederick W., 1955- .**

**II. Title. III. Series.**

**TD796.5.024 1987 628.4'458 87-6091**

**ISBN 0-8213-0894-7**

ABSTRACT

This report is part of a joint global research, development, and demonstration effort of the United Nations Development Programme and the World Bank. It reviews current literature and practices on the co-composting of human waste (fresh nightsoil or sewage sludge) together with the organic fraction of domestic solid waste (as well as with other wastes).

The report describes the composting process, reviews various co-composting systems, and discusses health aspects such as pathogen destruction. The uses of compost as a soil conditioner, mulch, fertilizer or for land reclamation are also described.

The report also develops several cost/benefit models for economic analysis of co-composting operations and outlines the economics of the process as a whole. The focus of the analytical methodology is on developing countries. The computer models are written for use on widely available micro-computers and are designed so that they can be adapted to site-specific economic conditions. A copy of the computer models is available on request.

Key issues for consideration in planning for composting are also discussed. Decision makers and planners will find this report a valuable reference on co-composting when addressing waste management and resource recovery issues in the developing countries.

**FOREWORD**

This is the seventh of a series of generic reports produced by the joint UNDP/World Bank Global Research and Development Project on Integrated Resource Recovery (GLO/84/007, GLO/80/004). The primary project goal is to achieve economic and social benefits through sustainable resource recovery activities in the developing countries by recycling and reusing solid and liquid wastes from municipal and commercial sources within the context of appropriate waste management.

Increasing recognition of the need for technical and economic efficiency in allocating and utilizing resources and the role that appropriate resource recovery can play in the water and sanitation sector have led this project to be included in the formal activities of the United Nations International Drinking Water Supply and Sanitation Decade.

Urban areas are finding it increasingly difficult to safely dispose of human wastes and domestic solid wastes. It is also becoming increasingly important worldwide to improve the nutrient and physical qualities of agricultural soils. This is especially true in the food production areas surrounding growing urban centers in developing countries. This report presents a review and analysis framework of co-composting, which is a process that can convert more than one waste, such as human and domestic solid wastes, into a useful resource.

The report describes composting and examines ways of co-composting of human waste (fresh nightsoil or sewage sludge) together with the organic fraction of domestic solid waste. It discusses the procedures entailed, the health aspects, and the uses of compost based on a literature review. Furthermore, an economic analysis methodology is developed using computer models that perform cost-benefit calculations of co-composting operations. These models are suitable for analysis of specific co-composting investments when modified to reflect local conditions. Copies of the LOTUS-123 <sup>1/</sup> template are available on request.

The authors would like to thank J. Pickford, G. Willson, C. Golueke, L. Diaz, D. Mara, M. Thalmann, and S. Cointreau and World Bank staff members M. Cohen, G. Tschanterl, D. de Ferranti, C. Bartone, S. Arlosoroff, M. Garn, W. Walters, A. Elwan, and R. Overby, who have reviewed this report and whose assistance has been invaluable to its production. They would also like to thank all others who have assisted in the preparation of this report.


Your comments on this report would be welcome, and we would be grateful to receive any case study information from which future editions of the resource recovery series could benefit. Please send your comments to WUDAT, The World Bank, 1818 H Street, N.W., Washington, D.C. 20433, USA.

S. Arlosoroff  
Chief, Applied Research and Technology Unit  
UNDP Projects Manager  
Water and Urban Development Department

# Integrated Resource Recovery

## The Co-composting of Domestic Solid and Human Wastes

Letitia A. Obeng and Frederick W. Wright



**CONTENTS**

|  |           |
|--|-----------|
| <b>List of Tables and Figures .....</b>                        | <b>xi</b> |
| <b>Chapter 1 Introduction .....</b>                            | <b>1</b>  |
| Aim .....  | 1         |
| Night Soil .....   | 1         |
| Sewage Sludge .....  | 1         |
| Solid Waste .....  | 2         |
| Co-Composting of Garbage with Human Waste .....                | 2         |
| <b>Chapter 2 The Composting Process .....</b>                  | <b>4</b>  |
| Rate-Related Factors .....                                     | 6         |
| Moisture Content .....   | 6         |
| Temperature .....  | 8         |
| Time .....   | 8         |
| Particle Size .....  | 8         |
| Oxygen Supply .....  | 10        |
| Nutrients .....  | 10        |
| pH Control .....   | 10        |
| Odor .....   | 11        |
| Other Factors .....  | 12        |
| <b>Chapter 3 Composting Systems .....</b>                      | <b>13</b> |
| Reactor Systems .....  | 13        |
| Nonreactor Systems .....                                       | 13        |
| Choice of System .....   | 14        |
| Sewage Sludge and Night Soil Co-Composted with Refuse .....    | 17        |
| Background .....   | 17        |
| Process .....  | 17        |
| Siting and Mixing .....  | 22        |
| Planning .....   | 22        |
| <b>Chapter 4 Control of Excreted and Other Pathogens .....</b> | <b>25</b> |
| Bacteria .....   | 27        |
| Viruses .....  | 29        |
| Protozoa .....   | 29        |
| Helminths .....  | 30        |
| Veterinary Pathogens .....                                     | 30        |
| Secondary Pathogens .....                                      | 32        |
| Plant Pathogens .....  | 34        |

|  |   |           |
|--|---|-----------|
| <b>Chapter 5</b>   | <b>Uses of Compost .....</b>  | <b>36</b> |
| Quality of Compost .....   | 36  |           |
| Application of Compost to Land .....   | 37  |           |
| Other Uses of Compost .....  | 39  |           |
| <b>Chapter 6</b>   | <b>Methodology for Evaluating the Economic Feasibility<br/>of Co-Composting .....</b> | <b>47</b> |
| Composition of Waste and Value of Resources Recovered .....                            | 47  |           |
| Scale and Technology of Co-Composting Plant .....                                      | 52  |           |
| Capital and Operating Costs .....  | 54  |           |
| Land Value and Landfill Requirements Costs .....                                       | 56  |           |
| Other Factors Affecting Financial Costs and Revenues .....                             | 57  |           |
| From Financial Costs/Revenues to Economic Costs/Benefits.....                          | 60  |           |
| Results from Hypothetical Model Calculations .....                                     | 65  |           |
| <b>Chapter 7</b>   | <b>Summary .....</b>  | <b>71</b> |
| Waste Material .....   | 72  |           |
| Market .....   | 72  |           |
| Compost Plant .....  | 72  |           |
| Pilot Scale Composting .....   | 72  |           |
| Benefits and Justification .....   | 73  |           |
| <b>Annex A:</b>  | <b>Other Methods of Co-composting with Sewage Sludge .....</b>                        | <b>75</b> |
| and Night Soil   |   |           |
| Sewage Sludge and Night Soil Composted with Bark .....                                 | 75  |           |
| Sewage Sludge and Night Soil Composted with Straw .....                                | 75  |           |
| Sewage Sludge and Night Soil Composted with Wood Chips .....                           | 75  |           |
| Sewage Sludge and Night Soil Composted with Other Materials..                          | 79  |           |
| Sewage Sludge and Night Soil Composted without the Addition<br>of Bulking Agents ..... | 82  |           |
| <b>Annex B:</b>  | <b>Pathogen Survival .....</b>  | <b>85</b> |
| <b>References .....</b>  |   | <b>91</b> |

**LIST OF TABLES AND FIGURES**

**TABLES**

|           |  |    |
|-----------|--|----|
| Table 1.  | Refuse Content from Various Municipalities .....   | 3  |
| Table 2.  | Microfloral Population during Aerobic Composting .....   | 4  |
| Table 3.  | Maximum, Optimum, and Minimum Temperature Ranges<br>for Mesophils and Thermophils .....  | 6  |
| Table 4.  | Feedback Loops in the Composting Ecosystem .....   | 7  |
| Table 5.  | Approximate Nitrogen Content and C/N Ratios<br>for Some Compostable Materials .....  | 11 |
| Table 6.  | Methods of Odor Control Using Compost Filters .....  | 12 |
| Table 7.  | Summary of Different Nonreactor Composting Systems .....   | 14 |
| Table 8.  | Comparison of Reactor and Nonreactor Systems .....   | 16 |
| Table 9.  | Composting of Sewage Sludge with Refuse .....  | 18 |
| Table 10. | Comparative Costs for Various Sludge Disposal Processes..  | 23 |
| Table 11. | Factors To Consider in Planning a Compost Plant .....  | 24 |
| Table 12. | Survival Times of Excreted Pathogens in Feces,<br>Night Soil, and Sludge at 20-30°C .....  | 25 |
| Table 13. | Survival Times of Excreted Pathogens On Crops<br>at 20-30°C .....  | 26 |
| Table 14. | Bacterial Pathogens Excreted in Feces .....  | 27 |
| Table 15. | Viral Pathogens Excreted in Feces .....  | 29 |
| Table 16. | Protozoal Pathogens Excreted in Feces .....  | 30 |
| Table 17. | Helminthic Pathogens Excreted in Feces .....   | 31 |
| Table 18. | Animal Pathogens Capable of Causing Infections in Man ...  | 32 |
| Table 19. | Concentrations of Thermophilic Actinomycetes in<br>Different Materials .....   | 33 |
| Table 20. | Plant Pathogens in Compost .....   | 35 |
| Table 21. | Differences between Mature and Raw Compost .....   | 37 |
| Table 22. | Metal Concentrations in Compost and Human Waste .....  | 38 |
| Table 23. | Physical Effects of the Addition of Compost to Clay<br>or Sandy Soils .....  | 39 |
| Table 24. | Criteria for the Specific Applications of Compost .....  | 40 |
| Table 25. | Compost Application Rates: Uses and Application Rates<br>of Sewage Sludge Compost to Achieve Fertilizer<br>Benefits and Improve Soil ..... | 41 |
| Table 26. | Application Rates for Sewage Sludge Compost in the First<br>Year of Use Based on N or P Fertilizer Recommendations                         | 44 |
| Table 27. | Domestic Solid Waste Composition .....   | 48 |
| Table 28. | Resource Recovery Coefficients .....   | 49 |
| Table 29. | Recovered Material Values .....  | 49 |
| Table 30. | Recovered Materials, Revenue/Ton of Domestic Solid Waste   | 50 |
| Table 31. | Material Balance Per 1 Ton Domestic Solid Waste .....  | 52 |
| Table 32. | Description of Base Case Models .....  | 53 |
| Table 33. | Estimated Capital Costs (Base Case) .....  | 54 |

|                   |   |           |
|-------------------|---|-----------|
| <b>Table 34.</b>  | <b>Estimated Staffing Requirements (base case) .....</b>                                  | <b>55</b> |
| <b>Table 35.</b>  | <b>Miscellaneous Base Case Operating Requirements<br/>(units/year) .....</b>              | <b>55</b> |
| <b>Table 36.</b>  | <b>Financial Input Prices (base case) .....</b>   | <b>55</b> |
| <b>Table 37.</b>  | <b>Operating Cost Estimate (base case) .....</b>  | <b>56</b> |
| <b>Table 38.</b>  | <b>Compost Markets and Prices (base case) .....</b>                                       | <b>59</b> |
| <b>Table 39.</b>  | <b>Economic Input Prices (base case) .....</b>  | <b>62</b> |
| <b>Table 40.</b>  | <b>Energy Used to Process Virgin and Recycled Materials ....</b>                          | <b>63</b> |
| <b>Table 41.</b>  | <b>Recycled Material Valuation - Energy Based .....</b>                                   | <b>63</b> |
| <b>Table 42.</b>  | <b>1984 Fertilizer Prices .....</b>   | <b>64</b> |
| <b>Table 43.</b>  | <b>Base Case Results -- Financial .....</b>   | <b>67</b> |
| <b>Table 44.</b>  | <b>Base Case Results -- Economic .....</b>  | <b>67</b> |
| <b>Table 45.</b>  | <b>Alternative Technologies -- Results (Economic Values) ...</b>                          | <b>68</b> |
| <b>Table 46.</b>  | <b>Sensitivity Tests -- Multiple Change .....</b>   | <b>69</b> |
| <br>              |   |           |
| <b>Table A-1.</b> | <b>Composting of Sludge and Night Soil with Bark .....</b>                                | <b>75</b> |
| <b>Table A-2.</b> | <b>Composting of Sludge and Night Soil with Straw .....</b>                               | <b>77</b> |
| <b>Table A-3.</b> | <b>Description of the Beltsville Aerated Static Pile<br/>and Windrow Composting .....</b> | <b>78</b> |
| <b>Table A-4.</b> | <b>Methods of Composting Sewage Sludge with Other<br/>Bulking Agents .....</b>            | <b>79</b> |
| <b>Table A-5.</b> | <b>Methods of Composting Sewage Sludge and Night Soil Alone.</b>                          | <b>82</b> |
| <br>              |   |           |
| <b>Table B-1.</b> | <b>Survival of Bacterial Pathogens during Composting .....</b>                            | <b>85</b> |
| <b>Table B-2.</b> | <b>Survival of Viral Pathogens during Composting .....</b>                                | <b>88</b> |
| <b>Table B-3.</b> | <b>Survival of Protozoal Pathogens during Composting .....</b>                            | <b>89</b> |
| <b>Table B-4.</b> | <b>Survival of Helminthic Pathogens during Composting .....</b>                           | <b>90</b> |

## FIGURES

|                  |  |           |
|------------------|--|-----------|
| <b>Figure 1.</b> | <b>Typical time/temperature relationships using mode<br/>values of readings taken at 14 monitoring points<br/>within each of 12 static piles .....</b> | <b>5</b>  |
| <b>Figure 2.</b> | <b>A typical time/temperature relationship for<br/>composting sewage sludge by the aerated pile method ...</b>   | <b>9</b>  |
| <b>Figure 3.</b> | <b>Elements of aerated pile composting system .....</b>  | <b>15</b> |
| <b>Figure 4.</b> | <b>Survival of pathogens at different temperature/time<br/>regimes .....</b>   | <b>28</b> |

## CHAPTER 1

### INTRODUCTION

The recycling of human waste has been an accepted practice throughout the world for many years. One method of reusing human waste is composting, which means converting it into a material that is safe to use, usually on land.

### AIM

The purpose of this report is to describe methods of co-composting garbage with human waste in various places (using selected literature) and some of the health aspects, uses, and the economics of composting. The report also suggests ways in which planners and operators in developing countries can co-compost these two wastes (garbage and human) to best suit their needs and requirements.

### NIGHT SOIL

Human waste may be deposited into buckets, pits, vaults, or flush toilet basins. When it is deposited into buckets, pits, or vaults, it is referred to as night soil. If the night soil is deposited into buckets or vaults, it has to be removed and treated away from the site of collection. If the night soil is deposited into pits or vaults, these have to be emptied when they become full. Emptying of these pits is often hazardous because full pits contain fresh excreta. If twin or double pits are in use, the night soil in one pit is usually stored for at least one year (preferably two) before the pit is emptied. During this time, most of the disease-causing organisms are destroyed. However, hardy pathogens such as *Ascaris* eggs may survive.

The night soil that is removed from the pits (either fresh or stored) can be reused in agriculture, as it contains many nutrients. It can be mixed with other materials in a biogas plant or it can be used as a raw material in a compost plant. During the composting process, most disease-causing organisms that may be present in the night soil will be destroyed. The resulting compost is a humus-like material with good soil-conditioning properties as it contains many nutrients and minerals essential for plant growth.

### SEWAGE SLUDGE

Waste that is flushed away into sewers is transported to sewage-treatment plants. The solid waste matter produced by this treatment is known as sludge. This material can be further treated by anaerobic digestion to produce digested sludge.

Many countries in Europe and in North America either use sewage sludge directly on the land or convert it into compost, which is put to many uses. The use of sewage sludge compost on land is restricted in some industrialized areas because it contains relatively high concentrations of heavy metals.

Sewage sludge and night soil are similar in their moisture and nutrient content. The advantage of night soil over sludge is that it does not contain heavy metals, but there has been little experience in night soil composting. Nevertheless, the experience with sewage sludge composting can provide some information that may be of use in night soil composting. This review focuses primarily on co-composting of garbage and human wastes, but there are also other ways of co-composting with sludge and night soil (see annex A). Any of these systems could be a useful guide to plant planners wishing to find a suitable method of composting human waste.

#### SOLID WASTE

In this report garbage refers to the organic material present in refuse or solid waste. Refuse also contains metals, glass, plastics, cloths, and other such materials. In most industrialized countries, solid waste consists primarily of non-compostable matter that has to be sorted out before the waste can be composted. Very often the main costs of refuse composting plants arise from these sorting activities. In many developing countries the sorting is done by scavengers before the refuse reaches the treatment plant. Diaz and Golueke (1985) discuss scavenging in relation to other aspects of solid waste management, including the social, political, and economic ones. In some countries the waste is mainly organic and does not need to be sorted, but in others sorting is required (see table 1). There is a wealth of information on the sorting of refuse, but that subject is beyond the scope of this report.

#### CO-COMPOSTING OF GARBAGE WITH HUMAN WASTE

The term co-composting means the composting of two or more raw materials together. Many examples of different materials being composted together are available. Some are cited in Annex A. In the case of human waste and garbage (the organic part of refuse), this kind of composting is advantageous because the two waste materials complement each other well. The human waste is high in nitrogen content and moisture and the garbage is high in organic (carbon) content and has good bulking quality. Furthermore, both these waste materials can be converted into a useful product.

Table 1. Refuse Content from Various Municipalities  
(weight percent)

| Constituents             | Iraq | Algiers, Algeria | Hong Kong | Abu Dhabi, UAE | Accra, Ghana | Alexandria, Egypt | Cairo, Egypt | Sao Paolo, Brazil |
|--------------------------|------|------------------|-----------|----------------|--------------|-------------------|--------------|-------------------|
| Vegetables               | 68.6 | 72.0             | 46.2      | 22.5           | 87.1         | 65.0              | 43.8         | 46.9              |
| Textiles                 | 3.8  | 2.6              | 9.0       | 0.3            | 1.2          | 2.5               | 3.0          | 3.4               |
| Paper/carton             | 10.2 | 16.0             | 25.7      | 42.4           | 5.7          | 23.0              | 9.2          | 25.9              |
| Straw                    | 1.0  | 0.1              | -         | 0.4            | -            | -                 | 7.7          | -                 |
| Timber                   | 1.1  | 1.0              | 2.5       | 2.9            | -            | -                 | 2.5          | 1.9               |
| Leather/rubber           | 1.8  | 1.2              | 0.3       | -              | -            | -                 | 0.9          | 1.5               |
| Horn/bones               | 1.2  | 0.2              | 0.3       | 2.9            | -            | 0.5               | 1.3          | 0.1               |
| Plastics                 | 2.1  | 2.5              | 8.1       | 6.3            | 1.3          | 0.25              | 2.0          | 4.3               |
| Metals                   | 2.3  | 2.5              | 1.9       | 14.0           | 2.6          | 1.75              | 3.0          | 4.2               |
| Crockery                 | 5.5  | 0.7              | 0.4       | 3.8            | 1.4          | -                 | 24.7         | 9.7               |
| Glass                    | 2.4  | 1.2              | 5.6       | 4.4            | 0.7          | 2.25              | 1.9          | 2.1               |
| Organic fines            | -    | -                | -         | -              | -            | 4.75              | -            | -                 |
| Total                    | 100  | 100              | 100       | 100            | 100          | 100               | 100          | 100               |
| Moisture of crude refuse | 58.5 | 60.0             | 44.7      | 30.0           | 50.0         | -                 | 30-40        | 62.0              |
| Compostable portion      | 87.7 | 90.0             | 77.9      | 73.5           | 94.9         | -                 | 87.3         | 84.6              |

- = not measured

Sources: Weber (1983); Hughes (1986).

## CHAPTER 2

### THE COMPOSTING PROCESS

Composting can be defined as the biological decomposition of the organic constituents of wastes under controlled conditions. This process can take place in the presence or absence of oxygen. The former is called aerobic composting and the latter anaerobic. If efficiently carried out, aerobic composting can rapidly produce a pathogen-free product, as this review attempts to show. Anaerobic composting by contrast requires much longer decomposition times and is seldom free of pathogen and odor problems.


The material being composted decomposes as a result of the activity of the bacteria, fungi, actinomycetes, and protozoa present in the waste material and of those that are seeded from the atmosphere. The densities of the different organisms are a function of the nature of the waste in which they are found. Table 2 shows typical numbers of some organisms present in various stages of composting. The efficiency of the process depends to a large extent on temperature since microbial succession occurs with the temperature changes brought about by microbial activity. Figure 1 shows a typical temperature pattern in a compost pile over a period of 25 days. When a composting mixture is prepared, mesophilic microbial activity within the mass generates heat, which raises the temperature within the mixture. When the temperature reaches a certain level, the mesophilic activity begins to subside and thermophilic activity begins to increase. This process continues until the temperature conditions become limiting to the survival of the thermophils, and their population declines. Subsequently, the temperature declines. At this point mesophilic organisms (mainly fungi and actinomycetes) once again increase. As the process approaches completion, the concentration

Table 2. Microfloral Population during Aerobic Composting

|                          | Numbers per gram wet compost          |                        |                                      | Numbers of microorganisms identified (species) |
|--------------------------|---------------------------------------|------------------------|--------------------------------------|--|
|                          | Mesophilic initial temperature - 40°C | Thermophilic 40°C-70°C | Mesophilic 70°C-initial temperatures |  |
| <b>Bacteria</b>          |                                       |                        |                                      |  |
| Mesophilic               | $10^8$                                | $10^6$                 | $10^{11}$                            | 6  |
| Thermophilic             | $10^4$                                | $10^9$                 | $10^7$                               | 1  |
| <b>Actinomycetes</b>     |                                       |                        |                                      |  |
| Thermophilic             | $10^4$                                | $10^8$                 | $10^5$                               | 14   |
| <b>Fungi<sup>1</sup></b> |                                       |                        |                                      |  |
| Mesophilic               | $10^6$                                | $10^3$                 | $10^5$                               | 18   |
| Thermophilic             | $10^3$                                | $10^7$                 | $10^6$                               | 16   |

Source: adapted from Poincelot (1974).

<sup>1</sup> number less than or equal to number stated.



**Figure 1.** Typical time/temperature relationship using mode values of readings taken at 14 monitoring points within each of 12 static piles.  
**Source:** Sikora et al. (1981).

of nutrients also becomes rate limiting and the temperature eventually returns to its ambient value. Table 3 indicates typical minimal, optimal, and maximal temperature ranges for mesophils and thermophils.

Table 3. Maximum, Optimum, and Minimum Temperature Ranges for Mesophils and Thermophils ( $^{\circ}\text{C}$ )

|             | Minimum | Optimum | Maximum |
|-------------|---------|---------|---------|
| Mesophils   | 10-25   | 25-35   | 35-45   |
| Thermophils | 25-45   | 50-55   | 75-80   |

Source: Glathe and Parkasdi (1966).

Excreted pathogens present in the raw waste material will be destroyed or inactivated during the thermophilic phase (see table 4). Since the composting process is aerobic, the raw materials must have sufficient structure and porosity for efficient decomposition to occur. In the case of sewage sludge and night soil composting, organic or inorganic materials normally have to be added so as to increase air spaces to allow for proper aeration, provide structural support, reduce the bulk weight of the composting mixture, and, in the case of organic additives, increase the quantity of degradable materials. The organic part of garbage or refuse is suitable for this purpose, as are other types of materials that can be added, such as wood chips, shredded tires, peanut shells, rocks, bark, rice hulls, peat, straw, sawdust, manure, and grass.

#### RATE-RELATED FACTORS

Various rate-related parameters or factors affect the efficiency of the composting process and the quality of the product. The most important ones are briefly described in this section. The optimal ranges given are not always found in practice as different operators may use conditions shown by experience to be the best suited to their particular raw materials and composting process.

##### Moisture Content

The moisture content of a composting mixture should be much greater than the lowest level at which bacterial activity will occur (which is about 12-15 percent). The optimum moisture content for efficient composting is usually in the range of 50-60 percent.

Sewage sludge and night soil contain a great deal of moisture (typically  $> 92$  percent) in their untreated state. Even when dewatered, they may still be too wet to be composted on their own and amendments or bulking

Table 4. Feedback Loops in the Composting Ecosystem

| Loop Components         |                 | Positive feedback (a)                  |  |  | Negative feedback (b)  |  |
|-------------------------|-----------------|--|--|--|--|--|
| Microbiological factor  | Physical factor | Temperature optimum for the population | Temperature level  | Component interaction  | Temperature level  | Component interaction  |
| Mesophilic population   | Temperature     | 38° C (approx)                         | Ambient temperature at assembly of mixture                 | Mesophils generate heat; temperature increases; mesophils increase     | Above 40° C, self-heating passes from mesophilic phase to thermophilic | Mesophilic temperature tolerance limit exceeded; populations collapse; accompanying heat outputs decline |
| Thermophilic population | Temperature     | 55° C (approx)                         | Above 40° C at start of thermophilic phase of self-heating | Thermophils generate heat; temperature increases; thermophils increase | Above 55° C  | Thermophilic temperature tolerance limit approached; population and accompanying heat output declines    |

a. Positive. The microbial succession progresses.

b. Negative. The microbial succession is regressed.

Source: Finstein et al. (1980).

agents will then be required to reduce the moisture content and provide structural integrity as well as increase the carbon content. Typical amendments include sawdust, straw, garbage, grass, etc. Typical bulking agents include wood chips, shredded tires, rocks, peanut shells, etc. The moisture content of a composting mass will tend to decrease as decomposition proceeds, mainly because of evaporation losses during the thermophilic phase, and in some cases water may have to be added to maintain optimal conditions. Process performance can be evaluated during the drying out of a composting mixture since it is relatively simple to measure moisture and can easily be done even with poor laboratory facilities.

#### Temperature

Aerobic thermophilic composting has different temperature stages, including the important thermophilic one. Most microorganisms grow best between 20 and 35° C. Excreted pathogens thrive at body temperature (37° C). Temperatures above 50° C achieved during thermophilic composting should be high enough to destroy these pathogens if maintained for a sufficient period of time. This, however, is only possible if the temperature is maintained above 50° C throughout the composting mass and there are no pockets of low temperature during that time.

The temperature changes observed during the decomposition of organic matter can be used as an indication of the proper functioning (or malfunctioning) of the process. Temperature is perhaps a more reliable indicator than moisture, aeration, or nutrient concentrations, since it directly affects pathogen control, which is important to the production of good compost. Figure 2 shows typical time-temperature profiles for composting sewage sludge by the aerated pile method. Other methods use different time scales to attain thermophilic temperatures. In addition, the maximum temperatures achieved vary from system to system, depending on the raw materials used and operational and design factors. Many compost plant operators believe that it is important to maintain very high temperatures (>65° C), but this has been shown to be counterproductive because thermophilic microbial activity rapidly becomes limited at these temperatures.

#### Time

The quality of a product greatly depends on the length of time that a mixture is composted. If high composting temperatures (optimum 50-55° C) are not maintained throughout the material for a sufficient length of time (> 2 days), pathogen destruction will not reach the required level. (Some heat resistant pathogens may survive this temperature range.) Reactor retention times and curing times may vary from system to system.

#### Particle Size

Composting material that consists of small particles is more readily decomposed than material with larger particles as the surface area of contact is greater. At the same time, if particles are too fine, there will be less oxygen diffusion. Furthermore, very fine material tends to lose some of its




Figure 2. A typical time/temperature relationship for composting sewage sludge by the aerated pile method. Curve 1 depicts a situation where conditions of moisture, temperature, and aeration are at optimum levels for rapid transition from the mesophilic into the thermophilic stage. Curve 2 represents a condition where certain parameters are deficient or outside their optimum range, resulting in adverse effects on the growth and activity of the indigenous organisms.

Source: Parr, Epstein, and Willson (1978).

usefulness as a soil amendment. Typical particle sizes of material used for composting range from 10 to 50 millimeters, the lower value being appropriate for forced aeration or agitated systems and the upper one for static piles or windrows.

### Oxygen Supply

The optimum levels of oxygen required for the growth of aerobic microorganisms range from 5 to 15 percent of the air, with 5 percent being the minimum essential for the growth of mesophils. The oxygen consumption in a composting mass depends on several factors: (a) the stage of the process; (b) the temperature; (c) the degree of agitation of the mass; (d) the composition of the composting mass; (e) the particle size of the mass; and (f) the moisture content. Oxygen consumption appears to increase and decrease logarithmically with changes in temperature, and the moisture content affects the air spaces within the composting mass. The rate at which the compost material is aerated also affects the process. If the aeration rate is high (33-78 cubic feet of air per day per pound of volatile solids) the excess flow of air causes the compost mixture to cool down. If this rate is low (4-6 cubic feet of air per day per pound of volatile solids), aerobic activity will decline and the process may become anaerobic.

### Nutrients

Carbon and nitrogen are two elements required for microbial growth. The carbon-to-nitrogen (C/N) ratio provides a useful indication of the rate of decomposition of organic matter. Microorganisms generally require 30 parts of carbon to each part of nitrogen for their metabolism. This ratio is therefore commonly used in the composting process; the most frequently used value is between 25 and 30. Sewage sludge and night soil are both relatively high in nitrogenous compounds, and the C/N ratio is normally less than 15 for these wastes (see table 5 for the nitrogen content and C/N ratios of various wastes). The addition of amendments or bulking agents material that have a high C/N ratio compared with that of sewage sludge or night soil can be used to adjust the final ratio to one within the optimal range. If the C/N ratio is too high, however, the decomposition process slows down as nitrogen becomes growth limiting; if the ratio is too low, the large amount of nitrogen present is rapidly lost by volatilization as molecular ammonia. Since nitrogen is a valuable plant nutrient, its levels in mature compost need to be kept reasonably high; thus, maintaining an optimum C/N ratio is advantageous to the process.

### pH Control

The optimal pH for the growth of bacteria and other composting organisms is in the range of 6.0 to 8.0. At a pH of 8-9, nitrogen may be lost through volatilization of molecular ammonia; if the pH is too acidic (< 5), microbial activity will cease. In some cases, pH may reflect process malfunction; if, for example, a composting mass begins to turn anaerobic, the pH may fall to about 4.5 owing to the accumulation of organic acids. Conversely, as the process approaches stability, the pH shifts toward neutrality (pH 7).

Table 5. Approximate Nitrogen Content and C/N Ratios for Some Compostable Materials

| Material                           | Nitrogen<br>% dry weight | C/N ratio |
|------------------------------------|--------------------------|-----------|
| Urine                              | 15-18                    | 0.8       |
| Mixed slaughterhouse wastes        | 7-10                     | 2         |
| Night soil                         | 5.5-6.5                  | 6-10      |
| Digested sewage sludge             | 1.9                      | 16        |
| Activated sludge                   | 5.0-6.0                  | 6         |
| Young grass clippings              | 4.0                      | 12        |
| Cabbage                            | 3.6                      | 12        |
| Weeds                              | 2.0                      | 19        |
| Grass clippings<br>(average mixed) | 2.4                      | 19        |
| Farmyard manure (average)          | 2.15                     | 14        |
| Seaweed                            | 1.9                      | 19        |
| Potato haulms                      | 1.5                      | 25        |
| Oat straw                          | 1.05                     | 48        |
| Wheat straw                        | 0.3                      | 128       |
| Fresh sawdust                      | 0.11                     | 511       |
| Newspaper                          | nil                      | -         |
| Food wastes                        | 2.0-3.0                  | 15        |
| Fruit wastes                       | 1.5                      | 35        |
| Refuse                             | 0.5-1.4                  | 30-80     |
| Wood                               | 0.07                     | 700       |
| Paper                              | 0.2                      | 170       |

Source: Gotaas (1956).

Odor

This indicator is not only an index of the efficiency of the process, but it also affects public acceptance of and support for composting plants, especially in areas of high population density. There are various methods of controlling or removing foul odors from composting materials. These usually are effective unless the process goes totally anaerobic, for example, and particularly foul odors are produced. In forced aeration systems a relatively simple and inexpensive method of deodorizing the exhaust air is to use some of the previously composted materials as a filter, since organisms present in the filter readily absorb and decompose the malodorous compounds present in the air. Simple filters consist of a small pile of compost through which the air is blown. (Some compost filters are described in table 6.)

Table 6. Methods of Odor Control Using Compost Filters

| Filter type    | Description   | Source   |
|----------------|---|--|
| Filter bed     | A bed of perforated piping covered with compost   | Composting plants at Duisburg and Heidelberg (Fed. Rep. of Germany) (Jäger and Jäger 1978) |
| Windrow filter | A windrow constructed over perforated pipe through which air from a reactor is blown  | Beringen Composting Plant (Switzerland)  |
| Filter pile    | Cone-shaped pile of screened compost containing 1 cubic yard of dry material per 10 tons of wet sludge being composted  | Beltsville Composting Plant United States (Willson et al. 1980)                            |
| Dano filter    | 16-inch diameter perforated asbestos cement pipes 8 feet apart are covered with 1-2 inches of gravel to a thickness of 16 inches and this is then covered with fresh compost to a depth of 5 feet | (Wesner 1978)  |

#### OTHER FACTORS

Increasing ammonia concentration and rising levels of carbon dioxide have been shown to correlate with different stages of the composting process (Japan Sewage Works Agency 1980). At composting installations with well-equipped laboratories, these parameters can be continuously monitored and thus be used as indicators of process operation.

## CHAPTER 3

### COMPOSTING SYSTEMS

The composting systems described in this report can be divided into two main categories: (a) reactor systems in which at least the initial composting occurs within a mechanical reactor and (b) nonreactor systems in which the entire composting process occurs outside a reactor. Most composting systems developed up to now have been used for composting refuse; however, since human wastes in the form of sludge and night soil are the main raw materials of interest in this report, systems that can be used to treat these wastes are described here as well as systems for their combined treatment with garbage.

#### REACTOR SYSTEMS

The different types of reactor systems used for composting are usually classified as vertical flow, inclined flow, and horizontal flow in which aeration occurs with or without agitation of the composting mass. There are many different reactor systems for composting. These systems can compost a combination of human waste (sludge or night soil) and garbage, provided the waste has been adequately prepared (presorted, pulverized, etc.). After a few days in the reactor, the waste material (raw compost) is put in piles or windrows to mature. A few of the more common reactor systems are described below.

A vertical flow system may have vertically stacked floors or decks in a silo or tower-type reactor. Aeration is effected by allowing the composting mass to drop from one level to the next over a period of days. The raw compost is then stored outside to mature.

The Dano system is a typical inclined flow type of system. It comprises a drum that is slightly inclined from the horizontal and can be rotated. Air is introduced into the drum by forced aeration. The composting mass stays in the drum for up to 5 days, after which it is placed in windrows to mature.

A typical horizontal flow reactor consists of a series of cells. A horizontal screw moves the waste from cell to cell. Air is introduced at the bottom of each cell. After a few days in the cells, the compost matures out in the open for several weeks.

#### NONREACTOR SYSTEMS

There are two types of nonreactor systems: (a) those in which the waste being composted is agitated or turned and (b) those in which the waste remains static during composting. The degree of mixing in the nonreactor system will vary considerably, depending on the technology used and the degree of control applied. In situations where the waste being composted is agitated or turned, this may be done by placing it in a windrow that is turned by a windrow-turning machine, by a front-end loader on a tractor, or manually by

using shovels. The static pile system relies on two methods of aeration: forced aeration of the composting mass and natural ventilation (air diffusion). A comparison of different nonreactor systems by de Bertoldi et al. (1982) has shown that turning is a less efficient method of producing good compost than forced aeration of a static pile. This is mainly because of the difficulty of attaining thorough mixing by turning. A study conducted by Periero-Neto, Stentiford, and Mara (1986) in which windrows were compared with aerated static piles showed that a better quality compost (good pathogen removal) was produced by the forced aeration static piles. Table 7 describes briefly four different nonreactor systems. A typical forced aeration pile is shown in figure 3.


Table 7. Summary of Different Nonreactor Composting Systems

| Item | General descriptions   |
|------|--|
| 1.   | The waste material is placed in alternate layers in a trench or pile. It is turned frequently by shovel over a 3 to 6 month period.  |
| 2.   | The waste material is formed into a windrow (triangular in cross section) using a front-end loader or windrower. This is then regularly turned by machine for 4 to 6 weeks.  |
| 3.   | The waste material is extruded into pellets (each with a 1/cm diameter), pressed into briquettes or formed into bales, stacked in piles, and aerated by natural ventilation. |
| 4.   | The material is constructed into a pile (static aerated pile) through which air is either blown or drawn over a period of about 3 weeks.                                     |

#### CHOICE OF SYSTEM

The major differences between reactor and nonreactor systems are in the capital and operating costs of the two systems. This is of great importance if financial resources are a constraint in the choice of a composting system. Because of their complexity in hardware and their need for highly technically skilled operators, reactor systems have high construction, operation, and maintenance costs, whereas nonreactor systems that are less complex and can rely on fewer technically skilled staff tend to cost less. Reactor systems for composting have been popular in industrialized countries, where there has been increasing need to compost solid and human waste. In addition, complex equipment has been required to sort out the large amounts of noncompostable waste material in areas with limited space availability. In many developing countries, there is no need to opt for the reactor system on the basis of limited space availability. In addition, the waste often comprises more than 60 percent compostable material. Often this is because scavengers have removed most of the noncompostable material. Comparison is made of some of the management and operational differences between reactor and nonreactor systems in table 8. Some of the important points to consider in planning for composting are discussed later.

**COMPOSTING  
WITH FORCED AERATION**



World Bank - 18059

**Figure 3. Elements of aerated pile composting system.**

Table 8. Comparison of Reactor and Nonreactor Systems

| Item                                       | Nonreactor systems   |   | Reactor systems  |   |
|--|--|---|--|---|
|  | Turned windrow   | Aerated pile  | Forced aeration, agitation   | Forced aeration, no agitation   |
| Capital costs                              | Generally low  | Generally low in small systems; can become high in large systems                    | Generally high   | Generally high  |
| Operating costs                            | Generally low  | High, depending largely on amendment or bulking agents                              | Generally low, depending on power source   | Generally low, depending on amendment or bulking agent  |
| Land requirement                           | High   | High  | Low for reactor but can be high where windrow drying is required                         | Low, but can increase if windrow drying is required   |
| Control of air supply                      | Limited unless forced aeration is used                                 | Complete  | Complete   | Complete  |
| Need for subsequent drying                 | Drying usually occurs in windrow but depends on climate                | Drying can be achieved in pile with high air supply; windrow drying may be required | Drying can be achieved in reactor; final drying in windrow or heat dryer may be required | Less drying potential from lower air flow-rates; final drying in windrow or heat dryer usually required |
| Sensitivity to cold or wet weather         | Sensitive unless in housing; demonstrated mainly in warm, dry climates | Demonstrated in cold and wet climates   | Demonstrated in cold and wet climates  | Demonstrated in cold and wet climates   |
| Composting demonstrated on digested sludge | Yes  | Yes   | Yes  | Yes   |
| Composting demonstrated on raw sludge      | Yes, but odor problems observed  | Yes   | Yes  | Yes   |

(cont.)

Table 8 (cont.)

| Item             | Nonreactor systems               |   | Reactor systems               |                                  |
|------------------|----------------------------------|---|-------------------------------|----------------------------------|
|                  | Turned<br>windrow                | Aerated pile  | Forced aeration,<br>agitation | Forced aeration,<br>no agitation |
| Control of odors | Depends largely on raw materials | Handling of raw sludge is potentially odorous; filter may be required | Potentially good              | Potentially good                 |

Source: Adapted from Haug (1980).

### SEWAGE SLUDGE AND NIGHT SOIL CO-COMPOSTED WITH REFUSE

#### Background

Several European countries, most notably Holland (Oosthoek 1981), France (Hirscheidt 1975), Austria (Ingerle 1978), and the Federal Republic of Germany (Tabasaran 1976), have a long history of refuse composting. Methods of preparing refuse for composting have been described in the literature (see, for example, Breidenbach 1971; Spohn 1978; Rabbani et al. 1983; Savage and Golueke 1986). Sorting processes for refuse and composting are not discussed in detail here as they are also well described in the literature.

In West Germany, the co-composting of sewage sludge with garbage originated out of the need to treat and dispose of ever-increasing amounts of sludge. Co-composting now is a viable alternative in many developing countries where great concern exists about the large amounts of garbage and poorly disposed and treated human wastes that are being produced in urban areas. These waste materials can be reused and recycled through composting, to improve the urban environment and to increase the quality and productivity of soils.

#### Process

Co-composting of garbage with human waste can be carried out both in reactor systems (Ingerle 1980) and nonreactor systems. Nonreactor systems are best used wherever the refuse does not require much sorting and pulverizing and where funds and other resources are scarce. The different reactor and nonreactor systems for composting already have been described. Table 9 gives examples of different reactor and nonreactor systems and how they have been used to co-compost garbage and human waste. Different types of sludge and night soil can be mixed with the garbage (or sorted refuse). Temperatures reached at composting time are indicative of efficient pathogen control.

Table 9. Examples of Co-composting of Sewage Sludge with Refuse

| Country/<br>city        | Plant type/<br>raw materials   | Process description   | Reference  |
|-------------------------|--|---|--|
| <b>Reactors</b>         |  |   |  |
| W. Germany              | Bioreactor cell system; dewatered digested sludge and refuse   | Experimental study. The sewage sludge is first pelletized (to a diameter of 10 millimeters) and then mixed together with the sorted pulverized refuse in bioreactor cells. Temperatures of up to 80° C are attained over a number of days.  | Spohn (1978), Miersch and Strauch (1978)                                   |
| W. Germany (Lemgo)      | Hazemag drum system with forced aeration; refuse and mixed raw/digested sewage sludge dewatered to 25 percent solids | After refuse is separated and pulverized, it is mixed in a drum together with the sludge for 24 hours; then the raw compost is matured in forced aeration piles for up to 5 months. Temperatures of up to 50° C are attained within the drum. A compost filter is used to control odor.   | Grote (1978)   |
| W. Germany (Heidelberg) | Multibacto system; a tower reactor consisting of several levels; refuse and dewatered digested sludge                | The sludge is dewatered to 40 percent solids before addition to the sorted pulverized refuse. The mixture falls from level to level within the tower during a period of 24 hours to 1 week during which temperatures of up to 70° C are reached. Maturation occurs in tunneled windrows (i.e., piled with "tunnels" to aid aeration and drying). Experiments using the towers demonstrate the variation in mesophilic and thermophilic populations (described in chapter 2) at the temperatures occurring at different levels within the tower. A compost filter is used to control odor. | Jäger (1977), Farkasdi (experimental, 1968), Sander (1967), Hart (1967)    |
| W. Germany (Duisberg)   | Dano drum/reactor; refuse and digested sludge  | Refuse is sorted before being put into the drum, where it is mixed with the sludge. Retention time is about 3 days, after which the raw compost mix is put in windrows to mature. Temperatures up to 72° C are reached and maintained in the drum. A compost filter is used to control odor.  | Hart (1967), Hasuk (1979), Hirschheydt (1975), Sander (1967), Ernst (1972) |

(cont.)

Table 9 (cont.)

| Country/<br>city          | Plant type/<br>raw materials   | Process description  | Reference                             |
|---------------------------|--|--|---------------------------------------|
| W. Germany<br>(Flensburg) | Rheinstahl<br>process drum<br>reactor; refuse<br>and dewatered<br>mixed sludge   | The refuse is milled and sorted. It is then mixed with the sludge in a drum for 24 hours. The raw compost is then matured in a windrow for 3-4 months. Temperatures of 60-70° C are maintained in the drum during the 24 hours. A compost filter is used to control odor.  | Schwabe<br>(1973),<br>Jäger<br>(1974) |
| W. Germany<br>(Beringen)  | Dano drum<br>reactor; refuse<br>and dewatered<br>digested sewage<br>sludge   | The refuse is sorted and milled and fed into a Dano drum together with the sludge. The retention time is 48 hours and a temperature of at least 40° C is maintained throughout. The raw compost is matured in windrows for 8-10 months (temperatures of up to 70° C are common). A compost filter is used to control odors from the drum.                    | Köhler &<br>Hardmeier<br>(1980)       |
| England<br>(Leicester)    | Dano; refuse<br>and digested<br>sewage sludge  | The refuse is sorted, homogenized, and mixed with the sludge. The mixture is fed into the drum where it stays for about 3 days; then the raw compost is screened and matured in windrows.  | Kuchta<br>(1967),<br>Hughes<br>(1977) |
| Sweden                    | Vertical reactors<br>each divided<br>into stages<br>by parallel<br>steel bars;<br>refuse and<br>dewatered sludge<br>and night soil | Experimental plant. The refuse is sorted and milled and is then mixed with the sludge and night soil. The mixture is added to a vertical reactor consisting of five stages. The retention time is 5 days and the average temperature is 55° C.   | Hovsenius<br>(1975)                   |
| Japan<br>(Toyohashi)      | Dano rotating<br>drums and verti-<br>tical reactors;<br>refuse and raw/<br>digested night<br>soil (and pou-<br>try wastes)         | The refuse is sorted and milled. The night soil is either digested aerobically first or dewatered and mixed with the refuse. The mixture is fed into Dano drums for 2 days, is kept in vertical reactors for another 2 days, and then stored. A temperature of 60° C is reached in both reactors. The raw compost is then stockpiled for 2 weeks before use. | Toyohashi<br>City (n.d.)              |

(cont.)

Table 9 (cont.)

| Country/<br>city            | Plant type/<br>raw materials  | Process description   | Reference   |
|-----------------------------|---|---|---|
| Italy                       |   | Refuse and sludge are composted using a biotunnel. Temperatures of 65-70° C are observed.   | Ferrero (1978)                                    |
| <u>Nonreactors</u>          |   |   |   |
| W. Germany<br>(Wiesbaden)   | Composting of<br>bales; refuse<br>and raw sludge  | Experimental plant. The refuse is sorted and milled and then mixed with the sludge. Next, the mixture is formed into bales using a press and then stored in the open to mature for about 14 months before being broken up. Temperatures (typical of windrow compost temperatures) of between 38° C and 72° C have been measured. Odor is not a problem. | Leonhardt (1979)                                  |
| W. Germany<br>(Schweinfurt) | Brikollare process<br>briquettes<br>20 x 25 x 50<br>centimeters are<br>formed; refuse<br>and dewatered<br>digested sewage<br>sludge | Refuse is sorted, ground, and then mixed with the sewage sludge. The mixture is then compressed into briquettes (which have holes for aeration). They are stored on pallets in a curing shed. Temperatures of 55-60° C are attained during curing (2-3 weeks). The briquettes are broken up before marketing.   | Hart (1967),<br>Sander (1967),<br>Nordsiek (1976) |
| Switzerland<br>(Biel)       | Same as above<br>briquettes<br>20 x 25 x 50<br>centimeters;<br>refuse and<br>dewatered<br>sewage sludge                             | The process is similar to the one above except that higher (60-65° C) temperatures are observed in the briquettes during 3 weeks of curing. The briquettes are broken up and sorted into different fractions before marketing.  | Heifner (1975),<br>Heifner (1977)                 |
| Austria                     | Voest Alpine<br>(platform<br>composting);<br>refuse and<br>sewage sludge  | Refuse is sorted and ground and then mixed with sludge. The mix is laid on a platform to a depth of 3-4 meters and composted with forced aeration for 3-4 weeks. Then the compost is matured on open-air platforms for up to 4 months.  | Willems (1979)                                    |

(cont.)

Table 9 (cont.)

| Country/<br>city                       | Plant type/<br>raw materials                              | Process description   | Reference                                      |
|--|---|---|--|
| England<br>(Manchester/<br>Dorchester) | Refuse and<br>sewage sludge<br>in forced<br>aeration pile | Experimental study. Refuse "fines," which pass through a 50 mm mesh, are mixed with sewage sludge (4-6% solids) with front-end loader, and the mixture is piled over a perforated aeration pipe for composting for about 30 days and then allowed to mature.  | Stentiford<br>et al.<br>(1985)                 |
| India                                  | Refuse and<br>night soil                                  | The refuse and night soil mixture is placed in brick-lined pits that have aeration and drainage channels. The mixture is turned at least twice during the 30-day composting period.   |  |
| Indonesia                              | Windrows;<br>refuse, manure,<br>night soil                | The raw materials are mixed and put in windrows, which are then left for 4-7 months.  | Sunawira<br>(1968)                             |
| China                                  | Night soil<br>and refuse                                  | Refuse (70-80 percent by weight) and night soil (20-30 percent by weight) are mixed and heaped in piles 4 meters at the base, 2 meters at the top, 1.5 meters high and 4 meters long. Bamboo poles for aeration are inserted at 30-centimeter levels and removed on day 2. The pile is sealed with a 40:60 percent soil-cinder paste. Temperatures of 50-55° C are achieved and maintained for 25 days. | Chinese<br>Academy<br>of<br>Sciences<br>(1975) |
| Haiti<br>(Port-au-<br>Prince)          | Night soil<br>and refuse                                  | Pilot plant, 175 cubic meters of preheated shredded refuse from a refuse treatment plant is mixed with 3.5 cubic meters of pit latrine waste using a front-end loader. Piles are constructed over a system of perforated pipes for forced aeration. Air is drawn through the pipes and exhaust gases conducted into a compost filter (Beltsville Aerated Pile Method).                                  | Dalmat<br>et al.<br>(1982)                     |

### Siting and Mixing

Many countries traditionally collect refuse separately from night soil and their refuse treatment and disposal sites differ from sludge production and disposal sites. The logistics of locating a night soil/sludge-garbage co-composting site must be carefully considered. A refuse disposal site is often suitable because of land availability. After the refuse is sorted and the rejects disposed of, it must be mixed with the night soil or sludge. Where windrows are to be used instead of aerated piles or reactors, experiments have shown that specially designed shredder machines are far more efficient at mixing than front-end loaders (Golueke et al. 1980).

### Planning

Many factors need to be considered when planning a composting plant. To begin with, the planner must carefully study the local situation before opting for one system or another. Table 10 compares some sludge disposal methods and gives an idea of the costs involved.

According to the figures in table 10, the costs of composting are lower than the costs for treatment processes such as heat drying and incineration but comparable to disposal-reuse processes such as landfilling, landspreading, and ocean disposal. As noted earlier, different methods of treating and disposing of wastes are often compared. Composting may not always be the most economically viable method of treating waste, sludge, and/or refuse, and thus governments, city councils, and private companies are often faced with the difficult task of deciding whether or not to compost.

Table 10. Comparative Costs for Various Sludge Disposal Processes  
(1976 U.S. dollars)

| Item  | Range of costs per<br>dry ton (US\$/ton) | Reference  |
|---|--|--|
| <b><u>Digested sludges</u></b>                  |  |  |
| Ocean outfall                                   | 10-35                                    | Wyatt and White (1975),  |
| Liquid Landspreading                            | 20-54                                    | Carroll et al. (1975),<br>Smith and Eilers (1975),<br>USEPA (1974)             |
| <b><u>Digested and<br/>dewatered sludge</u></b> |  |  |
| Ocean barging                                   | 31-44                                    | Wyatt and White (1975),  |
| Landfilling                                     | 23-53                                    | USEPA (1975),<br>Wyatt and White (1975),<br>Camp Dresser & McKee<br>(1975)     |
| Landspreading                                   | 26-96                                    | Camp Dresser & McKee<br>(1975)   |
| <b><u>Dewatered sludges</u></b>                 |  |  |
| Trenching <sup>a/</sup>                         | 116-134                                  | Resources Management<br>Associates (1975)                                      |
| Incineration <sup>b/</sup>                      | 57-93                                    | Brinsko (1974),<br>Camp Dresser and<br>McKee (1975),<br>Van Note et al. (1975) |
| Heat drying <sup>b/</sup>                       | 62-115                                   | Camp Dresser and<br>McKee (1975),<br>Stern (1975)                              |
| Composting <sup>a,b/</sup>                      | 35-50                                    | Colacicco, Derr,<br>and Kasper (1977)  |

a. Costs exclude transportation of sludge to site.

b. Costs exclude cost of removal of residues and benefits from resource recovery.

Source: Colacicco, Derr, and Kasper (1977).

It is important to note, however, that significant health benefits (even though difficult to quantify) derive from converting these highly pathogenic organic wastes into compost that is relatively pathogen-free. Furthermore, the application of compost to poor soils helps to improve their fertility and general condition.

Another important factor is the nature of the raw material(s) to be used, as this determines the complexity of the treatment plant required. If the raw material is refuse containing little organic matter, for example, a considerable amount of sorting and pulverization -- by machinery or manpower, or both -- will be required before the refuse can be composted. Other factors that need to be taken into consideration, especially since they may require extensive expenditure, are summarized in table 11.

Table 11. Factors To Consider in Planning a Composting Plant

|                        |   |
|------------------------|---|
| <b>Waste material</b>  | quantity and composition of waste<br>type of waste<br>collection of waste<br>pretreatment required<br>cost of bulking material<br>transport of raw wastes to plant<br>transport of compost<br>disposal of noncompostible materials<br>marketing possibilities<br>alternative disposal options |
| <b>Compost plant</b>   | location of plant<br>capital costs<br>land requirement (also for storage)<br>site development<br>equipment costs<br>expansion possibilities<br>applicability of existing types  |
| <b>Compost process</b> | system required<br>choice of equipment<br>energy/fuel requirements<br>laboratory needs<br>maintenance needs<br>maintenance costs<br>personnel costs   |
| <b>Compost demand</b>  | market research<br>market promotion<br>marketing costs  |

As table 11 indicates, planners must weigh many factors in deciding how to best compost garbage and human waste. They should not just pick any system and hope that it can be operated efficiently under local conditions. (Some of the questions on costs are discussed in Chapter 6.)

## CHAPTER 4

### CONTROL OF EXCRETED AND OTHER PATHOGENS

Excreted pathogens occur in sewage sludge at varying concentrations depending on their ability to survive the various sewage treatment processes and whether they accumulate in the sludge. Concentrations in night soil depend almost entirely on the levels being excreted at any one time and on the ability of the pathogens to survive in the external environment. Table 12 summarizes the survival times of pathogens excreted in feces, night soil, and sludge, and table 13 summarizes survival times on crops. Golueke (1983) has reviewed their survival in soil. The literature on the survival of enteric pathogens during various treatment processes has been thoroughly reviewed by Feachem et al. (1983), who present detailed information on health and other aspects of excreta-related infections. Furthermore, Blum and Feachem (1985) review the health aspects of night soil and sludge use in agriculture and discuss survival and health risks.

Table 12. Survival Times of Excreted Pathogens in Feces, Night Soil, and Sludge at 20-30°C

| Pathogens                          | Survival time (days) |
|------------------------------------|----------------------|
| <b>Viruses</b>                     |                      |
| Enterovirus*                       | <100 but usually <20 |
| <b>Bacteria</b>                    |                      |
| Fecal coliforms                    | <90 but usually <50  |
| Salmonella spp.                    | <60 but usually <30  |
| Shigella spp.                      | <30 but usually <10  |
| Vibrio cholerae                    | <30 but usually <5   |
| <b>Protozoa</b>                    |                      |
| <u>Entamoeba histolytica</u> cysts | <30 but usually <15  |
| <b>Helminths</b>                   |                      |
| <u>Ascaris lumbricoides</u> eggs   | Many months          |

\* Includes polio, echo, and coxsackieviruses.

Source: Feachem et al. (1983), p. 66.

Table 13. Survival Times of Excreted Pathogens on Crops at 20-30°C

| Pathogens                          | Survival time (days) |
|------------------------------------|----------------------|
| <b>Viruses</b>                     |                      |
| Enteroviruses*                     | <60 but usually <15  |
| <b>Bacteria</b>                    |                      |
| Fecal coliforms                    | <30 but usually <15  |
| <u>Salmonella</u> spp.             | <30 but usually <15  |
| <u>Shigella</u> spp.               | <10 but usually <5   |
| <u>Vibrio cholerae</u>             | <5 but usually <2    |
| <b>Protozoa</b>                    |                      |
| <u>Entamoeba histolytica</u> cysts | <10 but usually <2   |
| <b>Helminths</b>                   |                      |
| <u>Ascaris lumbricoides</u> eggs   | <60 but usually <30  |

\* Includes polio, echo, and coxsackieviruses.

Source: Feachem et al. (1983), p. 62.

Some pathogens may not survive the sludge production process. In addition, open-air drying of sludge and night soil eliminates pathogens, depending on the length of drying time. The key factors in determining the survival of pathogens are the temperature-time interactions. Feachem et al. (1983) have suggested various temperature-time regimes for selected pathogens to ensure their death in sewage sludge and night soil. These have been based on an evaluation of survival times for numerous pathogens over a wide range of temperatures (see figure 4).

Samples of sludge or night soil should be free of excreted pathogens (with the possible exception of hepatitis A virus and heat-resistant bacterial spores such as those of Clostridium perfringens) if they are heated for 1 hour at > 62°C, 1 day at > 50°C, or 1 week at > 46°C. These regimes are all within the safety zone shown in figure 4. Small-scale studies using 20-30 tons of compost material have shown that E. coli and Salmonella spp. are destroyed by heat more easily than fecal streptococci, and that even C. perfringens numbers decrease during composting and maturation (Pereira-Neto, Stentiford, and Mara 1986). Other workers have proposed different criteria for determining pathogen destruction in compost on the basis of work using


other media as well as compost. For example, Burge, Cramer, and Epstein (1978) and Burge, Colacicco, and Cramer (1981) suggest that F2 bacteriophage be used as an indicator of pathogen destruction since this organism is more resistant to heat than many excreted pathogens. Results of work done on this organism have shown that a 15-log reduction in F2 bacteriophage numbers can be expected if they are maintained at 55° C for 2 days (for example, a 7-log reduction of an infective dose of  $10^7$  - Vibrio cholerae would leave 1 Vibrio cholera bacterium). Maintaining pathogens at 55° C for 2 days as a minimum is within the safety zone shown in figure 4. This figure is a reliable indicator of survival times, especially since the use of standard fecal coliform counts may not be reliable (these have been shown to multiply in mature compost (Burge et al. 1981)).

#### BACTERIA

The main bacterial pathogens of interest are listed in table 14. The survival rate of excreted bacterial pathogens in night soil and sludge is variable and depends in part on the temperature and the length of time involved. At temperatures above 20° C, these pathogens will generally survive up to one month in samples of sludge and night soil. (Annex table B-1 indicates survival times for various bacteria. The data are based mainly on the absence of pathogens in the compost at the end of the sampling time, and in many cases there is no indication of the initial concentrations, which would

Table 14. Bacterial Pathogens Excreted in Feces

| Bacteria                           | Disease   |
|------------------------------------|---|
| <u>Campylobacter</u>               | Diarrhea  |
| <u>Pathogenic Escherichia coli</u> | Gastroenteritis or diarrhea                     |
| <u>Salmonellae</u>                 | Salmonellosis and other types of food poisoning |
| <u>Salmonella typhi</u>            | Typhoid fever                                   |
| <u>S. paratyphi</u>                | Paratyphoid fever                               |
| <u>Shigella</u>                    | Bacillary dysentery                             |
| <u>Vibrio cholerae</u>             | Cholera   |
| <u>Other vibrios</u>               | Diarrhea  |
| <u>Yersinia</u>                    | Yersiniosis                                     |



**Figure 4.** Survival of pathogens at different temperature/time regimes.  
Source: Feachem et al. (1983).

have an effect on the time for complete destruction or of frequencies of sampling.) However, in general, when the composting mass was maintained at temperatures above 50° C, complete destruction was shown to occur within 2 weeks (see examples in annex B table B-1).

## VIRUSES

The main viral pathogens of interest here are listed in table 15.

Data on the survival of viruses in sludge and night soil are less abundant than in the case of bacteria, principally because the methods used to determine viruses in samples are difficult to carry out and are often unreliable.

Survival of viral pathogens in compost of different materials is reduced to low levels within 2 weeks at temperatures between 35 and 70° C for most of the pathogens presented in annex table B-2.

Table 15. Viral Pathogens Excreted in Feces

| Viruses           | Disease                                 |
|-------------------|---|
| Adenoviruses      | Numerous conditions                     |
| Coxsackieviruses  | Numerous conditions                     |
| Echovirus         | Numerous conditions                     |
| Hepatitis A virus | Infectious hepatitis                    |
| Reoviruses        | Numerous conditions                     |
| Rotavirus         | Diarrhea or gastroenteritis in children |
| Poliovirus        | Poliomyelitis                           |

## PROTOZOA

The main protozoal pathogens of interest here are listed in table 16.

Reported survival of some of these pathogens in compost is presented in annex table B-3. The figures there indicate that in general the protozoal pathogens survive for short periods.

Table 16. Protozoal Pathogens Excreted in Feces

| Protozoa                     | Disease                              |
|------------------------------|--------------------------------------|
| <u>Entamoeba histolytica</u> | Amoebic dysentery and liver abscess  |
| <u>Giardia lamblia</u>       | Diarrhea and malabsorption           |
| <u>Balantidium coli</u>      | Mild diarrhea and colonic ulceration |

#### HELMINTHS

The main helminths of interest are presented in table 17. Certain helminths can survive in night soil and sludge up to a period of 3 months or longer, especially at cooler temperatures ( $<25^{\circ}\text{ C}$ ). The most resistant ones are *Ascaris* and hookworm ova (annex table B-4). In compost, survival is generally very low at temperatures maintained over  $35^{\circ}\text{ C}$  for a few days (annex table B-4).

Because the survival times for the different pathogens vary greatly at the different temperature-time regimes measured by researchers and composting plant operators, it is extremely important to establish reliable temperature-time criteria for pathogen destruction during composting. The regimes within the safety zone proposed by Feachem et al. (1983) and Burge, Colacicco, and Cramer (1981) may be of great use in this regard.

#### VETERINARY PATHOGENS

Pathogens excreted by animals may find their way into sludge or night soil if the wastes containing them become mixed with human wastes. Several infections can be transmitted from animals to man (see table 18). Only some of these diseases are enteric and are of interest here.

Enteric pathogens that may be isolated from animal waste include bacteria, viruses, protozoa, and helminths. They occur in varying numbers depending on the type of disease and the physical and chemical composition of the waste. Since these pathogens are enteric, their optimum growth occurs around body temperature. Thus the thermophilic temperature ( $> 45^{\circ}\text{ C}$ ) achieved during aerobic composting should be sufficient to destroy or inactivate the enteric pathogens, especially if the temperatures are maintained for sufficient lengths of time. Some exceptions to this may be spores of spore-forming bacteria found in animal wastes (such as Bacillus anthracis and some clostridia), which survive at high temperatures.

Table 17. Helminthic Pathogens Excreted in Feces

| Pathogen                         | Disease                           |
|----------------------------------|-----------------------------------|
| <u>Ancylostoma duodenale</u>     | Hookworm                          |
| <u>Necator americanus</u>        | Hookworm                          |
| <u>Ascaris lumbricoides</u>      | Ascariasis                        |
| <u>Clonorchis sinensis</u>       | Clonorchiasis                     |
| <u>Opisthorchis felineus</u>     | Opistorchiasis                    |
| <u>Opisthorchis viverrini</u>    | Opistorchiasis                    |
| <u>Diphyllobothrium latum</u>    | Diphyllobothriasis                |
| <u>Enterobius vermicularis</u>   | Enterobiasis                      |
| <u>Fasciola hepatica</u>         | Fascioliasis                      |
| <u>Fasciolopsis buski</u>        | Fasciolopsiasis                   |
| <u>Gastroducooides hominis</u>   | Gastroducooidiasis                |
| <u>Heterophyes heterophyes</u>   | Heterophyiasis                    |
| <u>Hymenolepis spp.</u>          | Hymenolepiasis                    |
| <u>Metagonimus yokogawai</u>     | Metagonimiasis                    |
| <u>Paragonimus westermani</u>    | Paragonimiasis                    |
| <u>Schistosoma haematobium</u>   | Schistosomiasis<br>(Bilharziasis) |
| <u>Schistosoma mansoni</u>       | Schistosomiasis                   |
| <u>Schistosoma japonicum</u>     | Schistosomiasis                   |
| <u>Strongyloides stercoralis</u> | Strongyloidiasis                  |
| <u>Taenia saginata</u>           | Taeniasis                         |
| <u>Trichuris trichiura</u>       | Trichuriasis                      |

Table 18. Animal Pathogens Capable of Causing Infections in Man

| Pathogen                             | Infection     | Mode of Infection                                   |
|--------------------------------------|---------------|---|
| <b>Bacteria</b>                      |               |   |
| <u>Bacillus anthracis</u>            | Anthrax       | Direct contact, excreta                             |
| <u>Brucella abortus</u>              | Brucellosis   | Cow to man, direct                                  |
| <u>Brucella suis</u>                 | Brucellosis   | Swine to man, contact                               |
| <u>Brucella melitensis</u>           | Brucellosis   | Goats to man, ingestion                             |
| <u>Leptospira icterohemorrhagiae</u> | Leptospirosis | Urine   |
| <u>Rickettsia typhi</u>              | Typhus        | Excreta   |
| <u>Salmonella</u>                    | Salmonellosis | Excreta   |
| <u>Listeria monocytogenes</u> *      | Listeriosis   | Cattle/dogs to man,<br>direct contact               |
| <b>Viruses</b>                       |               |   |
| Arboviruses                          | Togavirus     | Ingestion   |
| Herpes virus <sup>a</sup>            | B virus       | Monkey to man, direct contact                       |
| Pox virus cowpox <sup>a</sup>        | (cow to man)  | Direct contact                                      |
| <b>Protozoa</b>                      |               |   |
| <u>Toxoplasma gondii</u>             | Toxoplasmosis | Mammals/birds to man,<br>ingestion/inhalation feces |
| <b>Helminths</b>                     |               |   |
| <u>Fasciola hepatica</u>             | Fascioliasis  | Sheep and cattle to man                             |
| <u>Taenia saginata</u>               | Taeniasis     | Cow to man  |
| <u>Taenia solium</u>                 | Taeniasis     | Pig to man  |
| <b>Fungi*</b>                        |               |   |
| <u>Microsporum canis</u>             | Ringworm      | Dog to man, direct contact                          |

\*Not enteric.

#### SECONDARY PATHOGENS

Secondary pathogens affect people whose defense systems have been weakened by certain diseases or therapies. They may be present in sewage sludge or night soil and some are able to grow in compost. Examples of secondary pathogens are some thermophilic fungi and actinomycetes. These infect people who have had respiratory infections or prolonged antibiotic or steroid treatment (Hart, Russell, and Remington 1969). The probability of

people in good health becoming infected is very low (Olver 1979; Willson et al. 1980; Burge and Millner 1980).

The main thermophilic fungus of concern here is Aspergillus fumigatus, which causes a respiratory disease known as aspergillosis. The thermophilic actinomycetes (for example, Thermopolyspora polyspora and Micromonospora vulgaris) cause allergic reactions such as Farmer's Lung (Lacey 1974; Marsh, Miller, and Kla 1979). Millner (1982) lists several other actinomycetes reported to grow at the thermophilic temperatures attainable during the composting process (50° C). These secondary pathogens are ubiquitous and are very common in agricultural situations. Aspergillus fumigatus, for example, is found in soils, hay, wood, cereals, forage, and various moldy farm wastes. From the data on maximal concentrations of thermophilic actinomycetes in different materials (see table 19), it appears that the concentrations in compost are generally lower than those in the other materials (more mature compost usually has higher concentrations - up to 10<sup>8</sup> per gram of dry weight). Compost is able to support the growth of fumigatus and the actinomycetes because of the temperatures achieved during the process. Aspergillus fumigatus grows at temperatures of less than 20° C to about 60° C (Cooney and Emerson 1964; Kane and Mullins 1973a,b) and has been readily isolated from wood chips at 50° C (Tansey 1971). The actinomycetes have a similar temperature range (Lacey 1974). High concentrations have been isolated between 55° C and 60° C (Millner 1982). Certain factors can inhibit the growth of these secondary pathogens: low pH, anaerobic conditions, excessive moisture and high temperatures (> 65° C).

Toward the end of a composting process, when the compost is cooling down and becoming drier, the secondary pathogens may predominate. Their spores are readily dispersed from dry and dusty compost piles especially during and after mechanical agitation (Millner, Bassett, and Marsh 1980).

Table 19. Concentrations of Thermophilic Actinomycetes  
in Different Materials  
(numbers per gram, dry weight)

| Growth material               | Concentration         |
|-------------------------------|-----------------------|
| Moist hay                     | 1.7 x 10 <sup>7</sup> |
| 21-day sewage sludge compost  | 5.7 x 10 <sup>5</sup> |
| 4-month sewage sludge compost | 1.8 x 10 <sup>8</sup> |
| Bagasse                       | 9.6 x 10 <sup>6</sup> |
| Mushroom compost              | 6.6 x 10 <sup>6</sup> |
| Moist grain                   | 10 <sup>5</sup>       |

The degree of dispersal also depends on meteorological factors such as wind and rain (Millner et al. 1977). Experiments carried out to measure concentrations of these secondary pathogens at locations downwind of compost piles at treatment plants have shown that conditions differ for each compost plant, but that concentrations tend to be lower than those associated with secondary infections from moldy hay (Burge and Millner 1980; Millner 1982).

As already noted, the risk of infection in healthy individuals is low. Certain measures can be taken, however, to improve the general health standards at a composting plant and thus reduce the risk of these secondary infections even further:

1. Workers should be encouraged to maintain high standards of hygiene.
2. During periods of dry weather, the composting area should be sprinkled periodically with water to reduce dust dispersal.
3. During adverse weather conditions, workers should be encouraged to wear masks or respirators or some other covering to reduce dust inhalation.
4. Workers should be isolated from the spore-dispersing parts of the process, such as mechanical turning.
5. The composting plant should be located at "discreet" distances from hospitals and residential areas (the distance will vary from plant to plant, but in general should be at least 1 kilometer).

#### PLANT PATHOGENS

Numerous pathogens cause plant diseases. Most agricultural soils are infested with nematodes, bacteria, viruses, and fungi (Sasser 1971). Some of these may be present in compost made from garbage, vegetable, and other gardening wastes. Knoll (1980) has described standard laboratory methods that can be used to isolate and measure the concentrations of indicator plant pathogens in compost. Table 20 lists some pathogens that have been associated with compost as an indicator or that have been isolated from it. The most important ones are those that produce heat-resistant spores, such as the fungi listed in table 20 or some viruses. Most other pathogens are mesophils and would therefore be inactivated under thermophilic composting temperature-time regimes (although heat resistant spores present in compost may persist in the soil for long periods after being spread on land). Recent research has revealed that compost may have a beneficial effect on plants and soil-borne diseases. The application of compost to soils containing diseased plants has been followed by immediate and long-term reduction in the incidence and severity of certain diseases such as root rot of beans, cotton, and radish.

Table 20. Plant Pathogens in Compost

| Pathogens  | Plants affected                            |
|--|--|
| Bacteria (various)                               | Cabbage<br>Beans<br>Tomatoes               |
| Viruses, tobacco mosaic                          | Tobacco<br>Potato                          |
| Helminths, meloidogyne type,<br>nematodes        | Cucumber<br>Tomatoes<br>Lettuce<br>Carrots |
| <u>Globodera</u><br><u>rostochiensis</u>         | Potatoes                                   |
| Fungi, <u>Plasmodiophora</u><br><u>brassicae</u> | Cabbage<br>Rape                            |
| <u>Olipidium brassicae</u>                       | Cabbage<br>Lettuce<br>Other vegetables     |
| Sclerotinia                                      | Lettuce                                    |

## CHAPTER 5

### USES OF COMPOST

This chapter briefly reviews the uses of compost. The degree of use depends greatly on whether or not material of fecal origin is culturally and socially acceptable.

#### QUALITY OF COMPOST

A well-produced, mature compost is free from odor and easy to handle, store, and transport. A raw compost (one that has not matured) does not have these qualities, but will acquire them with time if it is allowed to mature. Table 21 lists some of the differences between raw and mature compost.

Mature compost contains trace and essential elements, of which the most important are nitrogen, phosphorus, potassium, and sulphur. These are available to the soil and plants, depending on their initial concentrations in the raw compost materials and on the degree of mineralization that occurs (Tester, Parr, and Paolini 1980). (Concentration in compost from sludge/night soil and garbage compost are considered equivalent, although concentrations of other elements will vary depending on the raw materials.) These elements are released by the compost and become available in the years following application. The compost can therefore be used in somewhat the same way as an inorganic fertilizer (except that in many cases the concentrations of these elements are so low that excessively large application rates would be required). As a result, compost is often considered a low analysis fertilizer or soil conditioner (Golueke 1972; Hand, Gershman, and Navarro 1977; Parr et al. 1978). However, the NPK values (and other mineral content) of compost can be fortified with chemicals to enhance its fertilizing capacity (Hileman 1982). Unlike inorganic fertilizers, compost has a humuslike quality that makes it even more useful, especially in areas of the world where the humus content of soil is being rapidly depleted as a result of excessive cultivation and land erosion (Tietjen 1975; Pagliali et al. 1981). That is to say, compost can replace lost humus.

Compost may contain high concentrations of heavy metals, depending on the source of the raw materials. If sludge from a mixed industrial-domestic source is used, concentrations of lead, zinc, and nickel may be very high. Some typical heavy metal concentrations in compost, night soil, and sludge are presented in table 22. Concentrations in night soil are negligible. Garbage and human waste plants utilizing night soil will produce compost low in heavy metals, especially if the refuse is largely organic. Other hazardous chemicals such as detergents and those in certain industrial wastes that may be composted will appear in the product if they are nonbiodegradable.

Table 21. Differences between Mature and Raw Compost

| Mature compost  | Raw compost   |
|---|---|
| Nitrogen as nitrate ion   | Nitrogen as ammonium ion  |
| Sulphur as sulphate ion   | Sulphur still in part as sulphide ion   |
| Lower oxygen demand   | Higher oxygen demand  |
| No danger of putrefaction   | Danger of putrefaction  |
| Nutrient elements are in part available to plants   | Nutrient elements not available   |
| Higher concentrations of vitamins and antibiotics   | Lower concentrations of vitamins and antibiotics                              |
| Higher concentrations of soil bacteria, fungi, which are decomposed, easily degradable substances | Higher concentration of bacteria and fungi, which decompose organic materials |
| Mineralization is about 50 percent  | High proportion of organic substances not mineralized                         |
| Higher water retention ability  | Lower water retention ability   |
| Clay-humus complexes are built  | No clay-humus complexes generated   |
| Compatible with plants  | Not compatible with plants  |

#### APPLICATION OF COMPOST TO LAND

The most important use of compost is its application to land. This takes several forms: It can be applied to land as a fertilizer, soil conditioner, or mulch, or can be used as a means of land reclamation. Furthermore, the use of compost can range from domestic applications by the home gardener to large-scale applications by commercial farmers to their cropland or by municipalities for parklands.

The application of compost to land has several advantages. Its positive effects on plant growth, fruit, crop yields, and other factors compared with the effects of fertilizers alone are well documented (see, for example, Arditti 1973; Hornick et al. 1979; Tokyo Metropolis 1979; Kurzweil

Table 22. Metal Concentrations in Compost and Human Waste

| Source material                   | Concentrations | Cadmium | Chromium | Copper | Nickel | Lead    | Zinc    | Reference                        |
|-----------------------------------|----------------|---------|----------|--------|--------|---------|---------|----------------------------------|
| Refuse/sludge compost             | kg/100t        | -       | 6.0      | 10.0   | 4.4    | 10.0    | 34.0    | Rhode (1972)                     |
| Refuse/sludge                     | kg/t           | 0.006   | -        | 0.24   | -      | 0.19    | 0.77    | Bucher (1974)                    |
| Sewage/sludge compost             | mg/kg          | 4.9     | 200.0    | 150.0  | 77.0   | 160.0   | 960.0   | Faust and Romano (1978)          |
| Sewage/sludge compost             | mg/kg          | 6.0     | 200.0    | 400.0  | 80.0   | 300.0   | 1,200.0 | Faust and Romano (1978)          |
| Night soil                        | mg/kg          | 0.024   | -        | -      | 0.15   | 0.25    | -       | Japan Sewage Works Agency (1980) |
| Night soil                        | mg/kg          | -       | -        | -      | 2.1    | 0.5     | 4.6     | Japan Sewage Works Agency (1980) |
| Mixed domestic/ industrial sludge | mg/kg          | 16.0    | -        | -      | 80.0   | 7.00    | 3,000.0 | Japan Sewage Works Agency (1980) |
| Mixed domestic/ industrial sludge | mg/kg          | 25.0    | -        | -      | 290.0  | 1,550.0 | 1,930.0 | Japan Sewage Works Agency (1980) |
| Sludge, digested, industrial      | mg/kg          | 110.0   | -        | -      | 320.0  | 1,360.0 | 2,790.0 | Willson et al. (1980)            |
| Sludge, digested                  | mg/kg          | 72.0    | -        | -      | 129.0  | 735.0   | 2,010.0 | Willson et al. (1980)            |
| Mixed domestic/ industrial sludge | mg/kg          | 3.4     | -        | 299.5  | 17.8   | 216.0   | 546.0   | Stentiford et al. (1983)         |

- = not measured.

1980; Angle, Wolf, and Hall 1981; and Sridhar et al. 1985). The advantages it has over inorganic fertilizers lie in its effects on the soil. Table 23 summarizes some of these effects with respect to clay or sandy soils. In both cases, the quality of the soil is improved and it is more productive. Some recommendations and criteria for the application of compost to land are presented in tables 24-26. Compost may not only amend the physical properties of the soil, but it may have other beneficial effects, such as raising the pH of acid soils. Production of compost may be of great interest, especially in countries with poor, arid soils.

Table 23. Physical Effects of the Addition of Compost to Clay or Sandy Soils

| Sandy soil + compost                      | Clay soil + compost                             |
|---|---|
| Water content is increased                | Aeration of soil increased                      |
| Water retention is increased              | Permeability of soil to water increased         |
| Aggregation of soil particles is enhanced | Potential crusting of soil surface is decreased |
| Erosion is reduced                        | Compaction is reduced                           |

Compost may be used on land for the following purposes: agriculture, horticulture, home gardening, vegetable gardening, viticulture, landscaping, landfill, forestry, or commercial farming. It is usually applied as mulch, soil conditioner, or fertilizer for many of these applications.

#### OTHER USES OF COMPOST

Apart from the traditional applications to land, compost has some other uses. For example, sewage sludge or refuse compost can be fed to piglets. Pigs are omnivores and so compost is palatable to them. The compost has to be ground into a fine material (< 4mm) and is fed only to piglets. In Switzerland it is bagged and sold on the market at about 120 SF per cubic meter (Helfer 1975). As noted earlier, animal enteric pathogens should in general be inactivated or destroyed.

Compost from night soil and vegetable matter has been used in fish farming experiments, where the compost has acted not only as a nutrient for the growth of algae but also as fish feed (Polprasert et al. 1981). Compost has also been used to make bricks porous. It is incorporated into the brickling material before firing; during firing the organic matter burns, leaving the fired bricks porous, as desired.

Table 24. Criteria for the Specific Applications of Compost

| Application                                      | Compost type          | Frequency<br>(years) | Quantities<br>(tons per hectare)                     |
|--|-----------------------|----------------------|--|
| Grain crops                                      | Fresh/mature          | 2-4                  | 20-60  |
| Root crops                                       | Fresh/mature          | 2-4                  | 40-100   |
| Grassland and<br>cultivation of<br>fodder plants | Fine fresh/mature     | 2-4                  | 20-50  |
| Fruit growing                                    | Fresh/mature          | 3                    | 100-200  |
| Vine growing                                     | Fresh/mature          | 3-4                  | 50-100 (light<br>soils)<br>80-240 (heavy<br>soils)   |
| Vegetables<br>(outdoor)                          | Fresh/special*        | 2-4                  | 50-100   |
| Vegetables<br>(greenhouse)                       | Mature/special        | 2-4                  | 10-15  |
| Landscaping<br>slopes                            | Fresh/mature          | 2                    | 100-300<br>20-40                                     |
| Pig feed   | Special mix with iron | -                    | (30 kilograms<br>per farrow in first<br>three weeks) |
| Control of<br>erosion                            | Fresh                 | -                    | up to 300  |

\*Special compost has added minerals or is very fine in texture.

Source: Adapted from Bundesrepublik (1979) and Tabasaran, Bidlingmaier, and Bickel (1981).

Table 25. Compost Application Rates: Uses and Application Rates of Sewage Sludge Compost to Achieve Fertilizer Benefits and Improve Soil

| Use                           | Compost<br>(metric tons per hectare) | Remarks   |
|-------------------------------|--------------------------------------|---|
| <b><u>Vegetable crops</u></b> |                                      |   |
| Establishment                 | 50-150                               | Rototill into surface 1-3 weeks before planting or in previous fall. Do not exceed recommended crop nitrogen rate.  |
| Maintenance                   | 50                                   | Rate is for years after initial garden establishment. Rototill into surface 1-2 weeks before planting or in previous fall.  |
| <b><u>Field crops</u></b>     |                                      |   |
| Barley, oats, rye, wheat      | 50-60                                | Incorporate into soil 1-2 weeks before planting or in previous fall.  |
| Corn                          | 150-185                              | Incorporate into soil 1-2 weeks before planting. Supplemental potash may be required, depending on soil test.   |
| Legumes                       |                                      | Legumes can be grown in rotation with corn, oats, or other nitrogen-required crops.   |
| <b><u>Forage grasses</u></b>  |                                      |   |
| Establishment                 | 195-340                              | Incorporate with top 4-6 inches of soil. Use lower rate on relatively fertile soil and higher rate on infertile soil. Supplement during first year's growth with 1/2 pound per 1,000 square feet (25 pounds per acre) of soluble nitrogen fertilizer when needed. |

(cont.)

Table 25 (cont.)

| Use   | Compost<br>(metric tons per hectare) | Remarks  |
|---|--------------------------------------|--|
| Maintenance   | 50-60                                | Broadcast uniformly on surface in fall or early spring 1 year after incorporated application.  |
| <u>Nursery crops<br/>and ornamentals<br/>(shrubs and trees)</u> |                                      |  |
| Establishment (soil incorporation)                              | 90-350                               | Incorporate with top 6-8 inches of soil. Do not use where acid-soil plants (azalea, rhododendron, etc.) are to be grown.   |
| Maintenance   | 10-25                                | Broadcast uniformly on surface soil. Can be worked into soil or used as a mulch.   |
| <u>Potting mixes</u>  | Equal ratio of material              | Thoroughly water and drain mixes several times before planting to prevent salt injury to plants.   |
| <u>Reclamation</u>  |                                      |  |
| Conservation planting   | Up to 450                            | Incorporate with top 6 inches of soil. Use maximum rate only where excessive growth for several months following establishment is desirable. For each inch beyond 6 inches of incorporation, add 1,000 pounds per 1,000 square feet on soils where groundwater nitrogen will not be increased. |
| <u>Mulch</u>  | 15-35                                | Broadcast screened or unscreened compost uniformly on surface after seeding; unscreened is more effective.   |

(cont.)

Table 25 (cont.)

| Use   | Compost<br>(metric tons per hectare) | Remarks   |
|---|--------------------------------------|---|
| <b><u>Turfgrasses</u></b>                   |                                      |   |
| Establishment (Soil incorporation)          | 100-300                              | Incorporate with top 4-6 inches of soil. Use lower rate on relatively fertile soil and higher rate on infertile soil.             |
| Surface mulch                               | 30-35                                | Broadcast uniformly on surface before seeding small seeded species (bluegrass) or after seeding large seeded species (fescues).   |
| Maintenance                                 | 20-40                                | Broadcast uniformly on surface. On cool-season grasses apply higher rate in fall or lower rate in fall and again in early spring. |
| Sod production,<br>incorporated with soil   | 150-300                              | Incorporate with top 4-6 inches of soil.  |
| Sod production,<br>unincorporated with soil | 300-900                              | Apply uniformly to surface. Irrigate for germination and establishment.   |

Source: Adapted from Hornick et al. (1979).

Table 26. Application Rates for Sewage Sludge Compost in the First Year of Use Based on N or P Fertilizer Recommendations

|  | N-based fertilizer<br>recommendations<br>(tons compost per hectare) | P-based fertilizer<br>recommendations | Remarks  |
|--|---|---------------------------------------|--|
| <b><u>Nursery crops<br/>and ornamentals<br/>(shrubs and<br/>trees)</u></b> |   |                                       |  |
| Establishment  | 100-380   | 35-100                                | Incorporate with top 6-8 inches of soil. Do not use where acid-soil plants (azalea, rhododendron, etc.) are to be grown. Broadcast uniformly on surface soil. Can be worked into soil or used as a mulch.  |
| <b><u>Reclamation</u></b>  |   |                                       |  |
| Conservation<br>planting   | Up to 500   | n.r.                                  | Incorporate with top 6 inches of soil. Use maximum rate only where excessive growth for several months following establishment is desirable. For each inch beyond 6 inches of incorporation, add 22 tons per acre on soils where groundwater nitrogen will not be increased. |
| <b><u>Mulch</u></b>  | 17-40   | n.r.                                  | Spread screened or unscreened compost uniformly on surface after seeding; unscreened is effective.   |

(cont.)

Table 26 (cont.)

|                              | N-based fertilizer<br>recommendations<br>(tons compost per hectare) | P-based fertilizer<br>recommendations | Remarks   |
|------------------------------|---|---------------------------------------|---|
| <b><u>Field Grass</u></b>    |   |                                       |   |
| Barley, oats,<br>rye, wheat  | 50-   | 10                                    | Incorporate into soil<br>1-2 weeks before plant-<br>ing or in previous<br>fall.   |
| Corn                         | 105-200   | 15-17                                 | Incorporate into soil<br>1-2 weeks before plant-<br>ing. Supplemental<br>potash may be required<br>depending on soil test.  |
| Legumes                      | n.r.  | 5                                     | Legumes can be grown<br>in rotation with<br>corn, oats, or other<br>nitrogen-requiring<br>crops.  |
| <b><u>Forage grasses</u></b> |   |                                       |   |
| Establishment                | 220-380   | 10-30                                 | Incorporate with top<br>4-6 inches of soil.<br>Use lower rate on<br>relatively fertile<br>soil and higher rate<br>on infertile soil.<br>Supplement during first<br>year's growth, using<br>25 pounds per acre<br>of soluble nitrogen<br>fertilizer when needed. |
| Maintenance                  | 50-70   | 10-12                                 | Broadcast uniformly on<br>surface in fall or<br>early spring 1 year<br>after incorporated<br>application.   |

(cont.)

Table 26 (cont.)

|   | N-based fertilizer<br>recommendations<br>(tons compost per hectare) | P-based fertilizer<br>recommendations | Remarks  |
|---|---|---------------------------------------|--|
| <b>Turfgrasses</b>                                  |   |                                       |  |
| Establishment<br>(Soil incorporation)               | 100-330   | 27-37                                 | Incorporate with top 4-6 inches of soil. Use lower rate on relatively fertile soil and higher rate on infertile soil.          |
| <u>Surface mulch</u>                                | 32-40   | n.r.                                  | Spread uniformly on surface before seeding small seeded species (bluegrass) or after seeding large seeded species (fescues).   |
| Maintenance   | 22-44   | 7-10                                  | Spread uniformly on surface. On cool-season grasses apply higher rate in fall or lower rate in fall and again in early spring. |
| <u>Sod production,</u><br>incorporated<br>with soil | 165-330   | 27-37                                 | Incorporate with top 4-6 inches of soil.   |
| <b>Vegetable crops</b>                              |   |                                       |  |
| Establishment                                       | 55-165  | 7-17                                  | Rototill into surface 1-2 weeks before planting or in previous fall.   |
| Maintenance   | 55  | 7                                     | Rate is for years after initial garden establishment. Rototill into surface 1-2 weeks before planting or in previous fall.     |

n.r. = not recommended.

Source: Adapted from Hornick et al. (1979).

## CHAPTER 6

### METHODOLOGY FOR EVALUATING THE ECONOMIC FEASIBILITY OF CO-COMPOSTING

In developing countries the waste stream is relatively higher in organic matter than that of industrialized countries. Since compost is derived only from the organic wastes, it would seem that developing countries have a relative advantage in the production of compost. In addition, domestic solid waste in developing countries contains few, if any, toxic materials which minimizes the risks of recycling them in the domestic solid waste to the land in the form of compost. The purpose of this chapter is to present and analyze the economic parameters underlying co-composting operations. This will be done by presenting the fundamental information needed to assess the viability of co-composting, followed by development of hypothetical models in financial and then economic terms, along with a discussion of the differences between them. The models will then be computerized and results and sensitivity analysis presented. The methodology followed conforms to World Bank guidelines for project economic analysis.

Analysis is being limited to co-composting domestic solid waste with night soil, although with minor modifications it would be applicable to compost operations using domestic solid waste or sludge separately. Direct composting of domestic solid waste would be more closely correlated to the figures presented here, since the night soil component is relatively small (less than 10 percent of total inputs). Direct composting of night soil/sludge, however, requires the use of a bulking agent or organic amendment to reduce its moisture content. (For a detailed description of night soil composting, see Shuval et al. 1981.) Co-composting utilizes the domestic solid waste to serve as a bulking agent for the night soil.

#### COMPOSITION OF WASTE AND VALUE OF RESOURCES RECOVERED

The hypothetical models developed in this chapter assume a typical composition of solid waste for developing countries, which limits the capital requirements for equipment such as hammermills or rasps (to grind incoming domestic solid waste) by the waste composition (highly organic) and the use of a manual picking or sorting process. The specifics of the waste stream and its need for size reduction would vary for each municipality. Typical domestic solid waste generation rates for developing countries that will be used as the basis for these models are 0.3 kilograms/person/day of domestic solid waste with a moisture content of 50 percent and a density of 250-400 kilograms per cubic meter and 1.5 liters of night soil/person/day with a solids content of 3 percent. The quantity of night soil that can be processed by the co-composting operation depends on the moisture content of the material

to be composted; this should be no greater than 55 percent. The analysis assumes fresh night soil is collected and used by the co-composting operation, which severely limits the amount used. The use of pit latrine sludge (20-25 percent solids), dried sewage sludge (10-20 percent solids), or dewatered sludge would allow a greater population base to be handled. The use of a lower moisture liquid human waste would change the analysis slightly by increasing the amount of compost produced in direct proportion to the increased solids but would have little if any impact on compost-processing costs. Local conditions will determine the source of liquid material for the co-composting operation.

For the purposes of modeling, the domestic solid waste composition as given in table 27 has been assumed.

Table 27. Domestic Solid Waste Composition

|                            | % Domestic<br>solid waste* |
|----------------------------|----------------------------|
| Vegetables/putrescible     | 58                         |
| Paper/carton               | 20                         |
| Textiles                   | 3                          |
| Metals (ferrous)           | 4                          |
| Glass                      | 3                          |
| Plastic and rubber         | 4                          |
| Inerts, ash, rejects, etc. | 8                          |
|                            | <u>100%</u>                |

\* Moisture content of 50 percent, density of 400 kg/m<sup>3</sup>.

Domestic solid waste composition and quantities generated are subject to wide variations as shown in chapter 1, table 1, and depend a great deal on the local collection/scavenging system. Waste composition and quantity also vary according to season (higher ash content in winter, higher moisture levels during wet season, etc.) and source (industry, economic level, etc.). In many areas, the waste stream may consist almost entirely of organic material, the recoverable material of any value having been removed by scavengers before collection and delivery to the composting plant. Because variations in composition could have a substantial impact on the operating viability of a composting system, waste composition must be determined prior to consideration of composting as a waste management option. Variations in quantities of waste may also effect the capacity utilization of the co-composting operation or the need for alternative disposal systems, particularly where co-composting operations are used for a significant portion of the waste stream. The moisture content of the domestic solid waste is very important when co-composting is done, since the lower the domestic solid waste moisture the greater the

amounts of night soil (3 percent solids) or sewage sludge (10-20 percent solids) that can be disposed of. The domestic solid waste collection system is not being analyzed here but plays a very important role and should be examined when composting as a disposal option is considered. Since composting is only possible on the organic material, the inert material (including metals, glass, plastics) needs to be sorted out if good quality compost is to be made. The percentage of available materials recovered will not approach 100 percent of their content in the domestic solid waste unless sophisticated recovery technologies are used. Table 28 illustrates reasonable resource recovery coefficients (for manual sorting) estimated from the available literature.

Table 28. Resource Recovery Coefficients

|                    | % Recovered |
|--------------------|-------------|
| Paper              | 60          |
| Textiles           | 70          |
| Metals (ferrous)   | 85          |
| Glass              | 50          |
| Plastic and rubber | 60          |

The remainder consists of compostable material (most of the unclaimed paper and some textiles also fall in this category) and rejects. The rejects (comprising mainly inert material such as construction waste and unrecovered recyclable materials) must be disposed of in an appropriate manner -- a sanitary landfill, for example -- or some other recycling technology such as construction land reclamation fill or waste-derived building blocks where feasible. Therefore, in many cases the appropriate site for the co-composting is the landfilling site, where sorting and separation and disposal of rejects will be done.

For modeling purposes, the US dollar equivalent prices for recovered materials will be assumed as given in table 31.

Table 29. Recovered Material Values

|                             | \$/Ton* |
|-----------------------------|---------|
| Paper                       | 20      |
| Textiles                    | 20      |
| Metals (ferrous)            | 15      |
| Glass                       | 20      |
| Plastics and Rubber (mixed) | 50      |

\* Prices are ex-plant.

The actual prices received for recovered materials are relatively unstable and highly dependent on the local market (rural, industry, transport availability, etc.). In addition, these materials tend to be bulky and transport costs constitute a high percentage of the end users cost. Also, the size of the composting operation has some bearing on prices for recovered materials. A small-scale plant would only be able to offer material users significant quantities after a period of time, whereas a large facility would be in a better position to negotiate a long-term sales contract. Prior to investing in a composting/resource recovery plant, detailed estimates must be made of the local market (quantity and price) for recovery materials. Table 30 estimates the value of recovered materials from one ton of waste, based on the assumed waste composition (table 29), resource recovery coefficients (table 30), and material values (table 31).

Table 30. Recovered Materials,  
Revenue/Ton of Domestic Solid Waste  
(US\$)

| Material     | Domestic solid waste content kg | Recovery coeff. % | Quantity recovered kg | Price \$/ton | Revenue \$/ton |
|--------------|---------------------------------|-------------------|-----------------------|--------------|----------------|
| Paper        | 200                             | 60                | 120                   | 20           | 2.40           |
| Textiles     | 30                              | 70                | 21                    | 20           | .42            |
| Metals       | 40                              | 85                | 34                    | 15           | .51            |
| Glass        | 30                              | 50                | 15                    | 20           | .30            |
| Plastics     | 40                              | 60                | 24                    | 50           | 1.20           |
| <b>TOTAL</b> | <b>340</b>                      | <b>--</b>         | <b>214</b>            | <b>--</b>    | <b>4.83</b>    |

As can be seen, the gross revenue generated for most items is rather small (particularly for textiles, metals, and glass) and one might assume it is not economical to recover them (recovery, of course, depends on local labor costs and potential markets). Yet, except for the paper, these are not compostable materials. Therefore, they would still need sorting and would then become rejects (requiring disposal) if not recovered and sold, and a significant percentage of the end cost has to be invested for both recycling and co-composting.

The other revenue-generating item will be the compost. The price (value) of compost is also sensitive to local conditions such as cropping patterns (vegetables or other high value crops), soil condition, availability of alternative soil conditioners (such as livestock wastes or crop residues), and costs of agricultural inputs (for example, inorganic fertilizers and water). Other potential buyers of compost include greenhouses and horticultural plant nursery operations (as a substitute for other more expensive

growing media, such as peat moss), land reclamation projects (strip mining or landfill cover), and public works (parks, landscaping, etc.).

The amount of compost produced depends on the quantity of compostable material, content of volatile solids, and its initial and final moisture content. Particle size, moisture content, as well as the carbon/nitrogen ratio (the mixing of night soil or sewage sludge with the compostable part of the domestic solid waste generally improves the C/N ratio) and oxygen content are the critical factors affecting the speed of the composting process and the quality of the finished compost.

A review of the available literature indicates a substantial variation in the yield of compost, particularly from solid waste. For example, the research done by the TVA at Johnson City indicates a 20-30 percent reduction in total solids (after removal of noncompostables) for municipal waste compost. Other sources show reductions in solids as low as 10 percent (Flintoff) and as high as 50-55 percent, again based on total compostable solids. Other reports make specific reference to reduction in volatile solids and show values ranging from 42 percent (Neto and Stentiford) up to 62 percent (Diaz). Still others report yields of compost based on the total waste stream, with figures ranging from 37-50 percent (EQI). Other factors that compound the problem of comparing these compost yields are the variations in waste composition, the final moisture content, and the degree of compost maturity. Before a decision is made on the economic viability of composting, the yield of the proposed co-composting plant needs to be estimated based on trials that utilize the local waste stream.

For modeling purposes, the input/output balance for one ton of waste and 80 kilograms of night soil<sup>1/</sup> is as presented in table 31.

The compost product, in addition to being a soil conditioner, would have some value as a low-grade fertilizer with analysis closely correlated to the waste input. Typical N (nitrogen), P (phosphate), and K (potassium) values for municipal waste and night soil compost are 1.3, 0.9, 1.0, respectively; however, wide variations exist. Because of the unmineralized nature of the nitrogen, much of it is unavailable for immediate plant use (typically, only 10 percent is available in the first year) and therefore acts much like a low-grade, slow-release fertilizer. The major value of compost is derived from its organic content which improves soil texture. Improved soil structure increases water retention capabilities resulting in either greater yields or lower irrigation requirements. Other benefits come from compost's ability to provide and/or improve utilization of plant nutrients, particularly micronutrients, and enhance the crop utilization of artificial fertilizers (thought to be a function of slower leaching). One point of caution when using compost on food crops is that waste-derived co-compost (particularly

---

1/ The 80 kg of night soil (3% solids) added after the separation step raises the moisture content of the compostable material to 55%. Use of pit latrine wastes or sewage sludge at 20% solid would be 140kg and increase the amount of compost to 360kg/1 ton domestic solid waste.

Table 31. Material Balance Per  
1 Ton Domestic Solid Waste <sup>a/</sup>

|                                    | Kg         |
|------------------------------------|------------|
| Recovered Materials                | 214        |
| Rejects <sup>b/</sup>              | 86         |
| Compost <sup>c/</sup>              | 335        |
| Loss of volatized solids and water | <u>445</u> |
|                                    | 1080       |

**a.** Assumed to have an initial moisture content of 50%.

**b.** Rejects consist of inerts (excluding ash and fines), and unrecovered metals, glass and plastics.

**c.** Quantity of compost produced is based on 700 kg of compostable material at 50% moisture plus 80 liters of night soil at 3% solids. During the composting process 33% of total solids are consumed and the final product has a 30% moisture content for a total weight reduction of 57%.

when sewage sludge is used) may contain heavy metals (lead, cadmium, nickel, zinc, mercury) which would limit the acceptable application rates. However, in the majority of urban areas in developing countries the potential percentage of heavy metals is negligible.

#### SCALE AND TECHNOLOGY OF CO-COMPOSTING PLANT

In order to present a wide range of composting alternatives, four different scale base case models of one nonreactor composting system, the windrow, will be developed and analyzed. The descriptions of the 3- and 50-ton-per-day plants are from Flintoff (1976) for India, and the 150- and 300-ton-per-day from consultants' work done for the recently appraised Egypt Solid Waste Management project. Interpolation of physical components was also done as a cross check to get a degree of consistency across the four hypothetical base case models. Financial prices used are based on the consultants' report for Egypt. It should be explicitly understood that, while efforts have been made to be realistic, these base case models are hypothetical and should be used with caution, although attempts have been made to make them as realistic as possible. Their main purpose is to allow the reader to work through the methodology using data from his or her specific situation. A description of these four base case models is given below in table 32.

Table 32. Description of Base Case Models

| Model designation | Capacity/description  |
|-------------------|---|
| A                 | 3 tons/8-hour day (Domestic solid waste input), entirely manual/windrow-style operations on an unpaved site of 500 m <sup>2</sup> , with storage tank (night soil) and a manual rotary screen (waste from 10,000 people and night soil from 160 people or sludge from 1,900 people).  |
| B                 | 50 tons/8-hour day, using a 2 ha paved site, windrow-style operations with conveyors, rotary screen, ballistic separator, storage tank (night soil), front-end loader, tractor and trailers (waste from 160,000 people and night soil from 2,500 people or sludge from 30,000 people).  |
| C                 | 150 tons/16-hour day, windrow-style operation using a 18.5 ha paved site with weigh bridge, storage tank (night soil), civil works, conveyors, shredding drums, magnetic separator, hydraulic baler windrow turning machine (1), frontend loaders (2), tipper trucks (4), workshop, laboratory generator, and bagging line (waste from 500,000 people and night soil from 8,500 people or sludge from 93,000 people). |
| D                 | 300 tons/16-hour day, using a 25 ha site, same description as in C with two times equipment and throughput.   |

In addition to these windrow (periodic-turning) systems, there are at least two other viable co-composting systems suited for conditions in developing countries, such as the static aerated pile, and reactor systems. These were described in some detail in chapter 3. The basic input/output relationships are the same for all co-composting systems. For the static aerated pile there would be minor changes in capital costs (suction fans and process controls but no windrow turning equipment) and reduced operating costs (less turning). For the enclosed reactor systems, the capital and operating costs would increase dramatically but have lower land requirements (only for the composting, not maturation). Analyses of these additional co-composting options will be approximated using sensitivity analysis that makes changes in both capital and operating costs as outlined in chapter 3, table 8. The physical operating parameters (waste input, recovery rates, and compost production) are the same for all models and technologies.

CAPITAL AND OPERATING COSTS

Base case investment costs for the four windrow models are detailed in table 33 below. Models A and B could be constructed in less than one year, while the larger models would require a two-year construction period. Staffing and operating coefficients are given in tables 34-36.

Table 33. Estimated Capital Costs (Base Case)  
(thousands of US\$)

| Description                           | Model       |               |                |                |
|---------------------------------------|-------------|---------------|----------------|----------------|
|                                       | A<br>(3tpd) | B<br>(50tpd)  | C<br>(150tpd)  | D<br>(300tpd)  |
| <b>Civil Works</b>                    |             |               |                |                |
| Site preparations                     | 1.0         | 25            | 160.0          | 240.0          |
| Fences and gates                      | 2.0         | 15.0          | 180.0          | 120.0          |
| Administrative building               | 5.0         | 25.0          | 160.0          | 240.0          |
| Composting area                       | -           | 75.0          | 200.0          | 320.0          |
| Maturing area                         | -           | 25.0          | 80.0           | 120.0          |
| Paving to roads and<br>Receiving area | -           | 25.0          | 80.0           | 120.0          |
| Water supply                          | 4.0         | 7.0           | 32.0           | 48.0           |
| Storage tank (night soil)             | 1.0         | 3.0           | 8.0            | 12.0           |
| Drainage                              | -           | 10.0          | 40.0           | 60.0           |
| Electrical installation               | -           | 15.0          | 160.0          | 280.0          |
| Miscellaneous buildings               | 1.0         | 25.0          | 1,040.0        | 40.0           |
| <b>Subtotal</b>                       | <b>14.0</b> | <b>250.0</b>  | <b>1,040.0</b> | <b>1,600.0</b> |
| <b>Equipment</b>                      |             |               |                |                |
| Weigh bridge                          | -           | -             | 25.0           | 25.0           |
| Conveyors and feeding<br>assembly     | 10.0        | 300.0         | 675.0          | 1,290.0        |
| Baling equipment                      | -           | 20.0          | 80.0           | 110.0          |
| Screening assembly                    | 5.0         | 30.0          | 120.0          | 175.0          |
| Electrical equipment                  | -           | 50.0          | 150.0          | 250.0          |
| Compost-turning machines              | -           | -             | 150.0          | 300.0          |
| Front-end loaders                     | -           | 75.0          | 150.0          | 300.0          |
| Internal transport <sup>a/</sup>      | -           | 30.0          | 250.0          | 500.0          |
| Spare parts                           | 2.0         | 50.0          | 150.0          | 230.0          |
| Laboratory                            | 1.0         | 5.0           | 10.0           | 10.0           |
| Workshop/clothing/tools               | 1.0         | 5.0           | 15.0           | 35.0           |
| Generator                             | -           | 50.0          | 100.0          | 150.0          |
| Bagging plant <sup>b/</sup>           | -           | 50.0          | 150.0          | 150.0          |
| Installation & Engineering            | 1.0         | 200.0         | 850.0          | 1,325.0        |
| Training and Tech. Asst.              | 10.0        | 25.0          | 125.0          | 150.0          |
| <b>Subtotal</b>                       | <b>30.0</b> | <b>890.0</b>  | <b>3,000.0</b> | <b>5,000.0</b> |
| Physical Contingency (15%)            | 6.6         | 171.0         | 606.0          | 990.0          |
| <b>TOTAL</b>                          | <b>50.6</b> | <b>1311.0</b> | <b>4646.0</b>  | <b>7590.0</b>  |

a. Either tipper trucks or tractors and trailers.

b. Used for fine-grade compost only.

Table 34. Estimated Staffing Requirements (base case)

| Description       | A | B  | C  | D  |
|-------------------|---|----|----|----|
| Management staff* | 1 | 4  | 8  | 8  |
| Labor             | 5 | 10 | 36 | 47 |

\* Management staff includes some or all of the duties; supervisor, mechanical engineer, accountant, maintenance engineer, electricians and lab technicians.

Table 35. Miscellaneous Base Case Operating Requirements (units/year)

| Description                          | A   | B     | C     | D     |
|--------------------------------------|-----|-------|-------|-------|
| Electricity (thousands of kw-hr)     | -   | 125.0 | 415.5 | 780.0 |
| Water (thousands of m <sup>3</sup> ) | 0.5 | 6.5   | 18.0  | 40.5  |
| Fuel (thousands of liters)           | -   | 70.0  | 232.5 | 435.0 |
| Lubricant (thousands of liters)      | -   | .3    | .9    | 1.8   |

Table 36. Financial Input Prices (base case)

| Item        | Price                   |
|-------------|-------------------------|
| Electricity | 1.6 US ¢/kw-hr          |
| Water       | 2.3 US ¢/m <sup>3</sup> |
| Fuel        | 20 US ¢/liter           |
| Lubricant   | 1.20US\$/liter          |

Maintenance costs are estimated at 2 percent/year of total equipment costs.

Average financial wage rates used for the base case analysis are \$1,620/person/year for management and \$1,250/person/year for labor. These rates, as with other input prices, would of course vary from country to country and should be adjusted to the specific location being studied. Other operating cost parameters are listed in table 37.

Table 37. Operating Cost Estimate (base case)  
(thousands of US\$/year)

| Description                      | A           | B           | C            | D            |
|----------------------------------|-------------|-------------|--------------|--------------|
| <b>Labor</b>                     |             |             |              |              |
| Management                       | 1.6         | 6.5         | 13.0         | 13.0         |
| General                          | 6.3         | 12.5        | 45.0         | 58.8         |
| Fringe benefits @ 25percent      | 2.0         | 4.7         | 14.5         | 17.9         |
| Overtime 25percent               | 2.0         | 4.7         | 14.5         | 17.9         |
| Subtotal                         | 11.9        | 28.5        | 86.9         | 107.6        |
| <b>Other</b>                     |             |             |              |              |
| Electricity                      | -           | 2.0         | 6.6          | 12.5         |
| Water                            | 0.0         | .1          | .4           | .9           |
| Fuel                             | -           | 1.4         | 4.7          | 8.7          |
| Lubricant                        | -           | .4          | 1.1          | 2.2          |
| Maintenance                      | 0.9         | 22.8        | 80.8         | 132.0        |
| Subtotal                         | 0.9         | 26.7        | 93.6         | 156.3        |
| <b>Total Plant Running Costs</b> | <b>12.8</b> | <b>55.2</b> | <b>180.5</b> | <b>263.9</b> |

Management of the co-composting operation should be stressed, particularly since the handling of pathogens is involved. Proper training and record keeping is essential to production of good quality hygienic compost.

#### LAND VALUE AND LANDFILL REQUIREMENTS COSTS

The plant must also bear the cost of reject material disposal (amounting to at least 119 kilograms/ton domestic solid waste input). These costs will include transport to a sanitary landfill facility, its capital (including land), and operating costs. For base case modeling purposes the land price for both the landfill and the composting facility is assumed at \$25,000/hectare (nearby urban areas). Transport cost to the landfill is being assumed at a nominal US\$1.0/ton of rejects (i.e., the compost plant is close to the landfill and transport equipment from the plant will be used). Typical densities for rejects, which consist primarily of inorganic waste (stones and building materials such as concrete, brick, etc.), are relatively higher (approximately 30 percent) than generally landfilled wastes. Assuming the sanitary landfill depth is 3 meters (excluding thickness of cover material), and the rejects have a compacted density of 0.67 tons/cubic meter, each ton of rejects therefore requires 1/2 square meters of land area. For without the project case a reasonable density for compacted landfilled waste (without composting/resource recovery, i.e., without project) is 0.5 tons/cubic meter which would require 0.67 square meters of land area per ton. Base case landfill operating costs have been estimated at US\$2.43/ton (including costs of equipment, civil works, and operations) excluding land. It is worth noting that the landfilled rejects, because of their low organic content, would

create a landfill that did not produce methane gas. This can either be considered a plus or a minus depending on long-term management of the landfill (reduced risk of explosion, or lost income potential from gas recovery). Also, for the same reasons, there should be fewer rodent and odor problems associated with the landfilling of rejects and it should be possible to use them for land reclamation (swamp, coastal) activities, which would result in almost total elimination of landfill requirements. In addition, since the rejects are of very low value, they should not attract scavengers to the landfilling site.

Landfill disposal or a give-away program may also be required for the poorer quality compost if it cannot be marketed. Compost has been successfully used for landfill cover and surface reclamation of sanitary landfills in place of soil. For modeling purposes compacted compost is estimated to require 0.55 square meter of land per ton (depth of 3 meters). Costs for transport and landfill operations would be approximately the same as for rejects.

All of the base case model assumptions (quantities and prices) are subject to a fairly high variation, and should be modified to reflect the circumstances of any specific project environment under review. As part of the analysis, sensitivity tests will be performed to vary assumptions systematically for individual and groups of line items in the models. The intent will be to determine general viability of composting and highlight the key parameters. The base case models have been developed using Lotus 123 (a popular personal computer spreadsheet) which can be modified easily to reflect particular situations.

#### OTHER FACTORS AFFECTING FINANCIAL COSTS AND REVENUES

In addition to the basic quantitative capital/operating parameters and prices outlined earlier, the planner must consider several other items, a few of which are discussed here.

Transport distances to the compost facility (or landfill) and local systems for domestic solid waste and night soil collection are a major cost of any waste management scheme. These costs are not being addressed here since it is assumed that the collection costs are almost equal regardless of the final disposal method. This is not to say that collection options should not be examined. For example, for domestic solid waste it is generally accepted that it is more economical to separate the recoverable materials at the source, prior to mixing with the general waste stream. Source separation or widespread scavenging would reduce the recycling revenue of the compost plants to almost zero while having only a limited impact on operating costs since sorting of rejects (with no value) must still be carried out. Another factor to consider is the type of domestic solid waste collection vehicle. Compacting trucks are generally inadequate for the developing countries due to maintenance difficulties and the already high density of the waste. Vacuum trucks for pit latrines, septic tanks or cess pools are often very effective since they limit the health risks involved in human handling and can discharge

the human wastes to the composting plant directly. Still another consideration is the organization of the collection process (transfer stations, utilization of capital, and labor). All of these will depend a great deal on local conditions and practices. The compost plant has been assumed to be located near the currently used landfill. It is important to analyze the specific situation -- it may be less expensive to locate the compost plant either closer to the waste generation point (lower collection transport costs) or closer to the agricultural areas (lower transport costs for the compost).

The seasonality of the waste stream will also affect the viability of the compost facility. In general, two elements pertain: (1) the volume of domestic solid waste and night soil, and (2) the composition (moisture and ash content in particular). The design capacity of the compost plant must allow for either adequate storage and processing flexibility (multiple shifts) to meet peak loads or alternative disposal systems. The plant capacity utilization will also have a significant impact on operating efficiency. For the purposes of the four models, it is assumed that they average 80 percent of design capacity from the year after investments are completed, and only 50 percent during final year of construction. This figure allows for variations in the waste stream and down-time for equipment and site maintenance. Another seasonal factor would be the efficiency of the composting process during the rainy season when the windrows may require temporary covers or more frequent turning. In areas with heavy rain seasons, a simple roof shelter may be built (adding to the capital cost but maximizing the potential operating throughput).

It is typical of most waste disposal operations that they operate at a loss, which is true for almost all compost operations in both industrialized and developing countries (depending of course on operating costs and the value of compost and recovered materials). This net composting operating cost of domestic solid waste disposal is generally covered by charging a "tipping fee" for accepting the waste from the collection system. The tipping fee (if set high enough) would make composting a viable activity for the private sector. A waste management planner would try to set the tipping fee as far as possible below the costs of alternative disposal (dumping, landfill, sanitary landfill, incineration, etc.), yet high enough to make composting financially viable. For the purposes of the four financial models, the initial tipping fee will be set at US\$1.0/ton waste input,<sup>1/</sup> and sensitivity tests will be carried out to determine the level of tipping fee needed to run a financially viable composting facility. If the municipality runs both the collection and composting operations, the tipping fee becomes a proxy for the estimated savings on landfilling costs and allows the municipality to compare the alternatives. In this case, one could substitute a collection fee that is then allocated to the collection/disposal operations for costs recovery. This fee, of course, must be compared with the waste generator's willingness and ability to pay.

---

<sup>1/</sup> This tipping fee would be extremely low in comparison with that found in some parts of the United States where landfills are scarce and tipping fees for landfills or incineration facilities can range up to US\$30/ton, or even higher for certain wastes such as sewage sludge.

The marketability and price received for compost are probably the most important financial factors. As mentioned earlier, the demand for compost is very crop- and location-specific. In temperate winter or tropical monsoon climates, the land application of compost may be seasonally restricted and require storage capacity either at the application area or composting site. Compost, due to its moisture retention abilities, is often in greater demand for certain higher-valued and higher-risk crops. Moreover, the quality of the compost, that is, nutrients, particle size, and maturity, has a great impact on its price. Throughout the available literature, the need for a well-thought-out and executed compost marketing program is stressed. Failure to market the compost adequately has been cited as the main cause for the failure of composting operations. In many areas, compost users will need to have its use and value demonstrated to them. The demonstration of composts agricultural usefulness may be dramatic in developing countries where farmers often cannot get or do not use fertilizers or manure since the potential for incremental yield increases from using compost would be more than in other regions of the world. For existing compost plants the range of prices is from \$0/ton (actually it is given away) up to a reported US\$40/ton. This range of prices certainly covers different quality composts being used for different purposes. For base case modeling purposes, it is assumed that there are four compost market outlets (table 38).

Table 38. Compost Markets and Prices (base case)

| Markets                      | % of Production Sold to | Price (\$/Ton) |
|------------------------------|-------------------------|----------------|
| Horticulture                 | 10                      | 14             |
| Land reclamation/Agriculture | 50                      | 10             |
| Public works                 | 30                      | 7              |
| Landfill cover               | 10                      | 0              |

These prices are assumed ex-plant and would of course depend greatly on local conditions and marketing efforts. These four market outlets would not all get the same quality compost. The last category, landfill cover, would include the poorer quality product and in some cases would not have a value of zero, since alternative landfill cover may have a value, particularly if it must be transported from a significant distance. The horticulture market would only get the highest quality compost. Costs of transport and disposal for the landfill cover compost are included as a cost in the models.

The financial factor most often overlooked by planners is the working capital requirements. Working capital breaks down into: (1) permanent (minimum resource requirements for carrying operations), and (2) variable (seasonal requirements for such things as unsold compost). For modeling purposes net working capital requirements are estimated at one month's gross revenue and costed in the model at a 12 percent annual interest rate (i.e., 1 percent of annual gross revenues).

#### FROM FINANCIAL COSTS/REVENUES TO ECONOMIC COSTS/BENEFITS

The basic thrust of project economic analysis is to determine if the co-composting process is a beneficial (productive, or lower cost disposal, waste management) use of scarce resources (capital, material, and labor). There are several fundamental differences in this process from the financial accounting system -- the object here is to quantify the impact on the economy and not simply assess the financial operations. Considerations include the "economic" cost of labor, transfer payments, and other external and nonquantifiable effects of the project in terms of the economic costs and benefits.

The most significant adjustment to the financial base case model comes from the use of "shadow prices," or economic conversion factors, which attempt to adjust imperfect financial market prices to their true economic values. These financial prices often include government transfer payments, such as taxes, subsidies, and quotas, and are adjusted through their exclusion and through the use of international (free trade) border prices.

The economic valuation of goods that are not usually traded internationally (e.g., recycled goods -- paper, glass, low-grade metals, textiles; compost; labor) is less refined, and it is often impossible to estimate the correct economic exchange price. Several valuation options exist. The simplest would be to assume that the economic price equals the financial price (economic conversion factor = 1.0), that is, assume a free market does exist. Another option is to value these goods in terms of other traded goods; for example, the recycled materials can be valued based on the energy saved -- the oil equivalent -- through their use in the production process. For the compost, with more research, estimates could be made of its value in terms of reduced agricultural inputs, such as soil conditioners, fertilizer, and water, or increased production of internationally traded agricultural products (wheat, corn, fruits, vegetables, etc.), or both. When using the latter method -- tradable resources saved or incremental tradable goods produced -- the analysis should include the incremental costs of realizing these benefits. Examples of incremental costs include transport of recycled materials to the processing factory or transport and spreading for the compost.

There are several problems with either of these economic valuation methods. For each country/location a different approach might be more realistic. Where there is already an active recycling trade, the use of market prices adjusted for macromarket imperfections makes the most sense. It is also worth noting that many developing countries do not have internal sources for virgin materials and therefore have only two alternatives, importation or recycling. In addition, many of these countries are extremely short of foreign exchange for imports. This would argue for the relative economic advantages of recycling, which should be accounted for by a properly calculated conversion factor. The same is true for compost, but there will rarely be an active, significant volume soil conditioner trade. In addition, it has proved to be very difficult to isolate the agricultural value of compost within the extremely complex agroeconomic system, which includes sun, water,

nutrients, soils, plant varieties, and farming methods. However, there have been numerous experiments that have conclusively shown increased yields, over a wide range, attributed to the use of compost. The yield impact of compost depends greatly on the existing conditions, with less impact on high quality soils and often resulting in dramatic yield increases on poor soils. It is also very risky to use market prices if the composting/resource recovery facility is large: an oversupply may be created and cause prices to fall.

It is also worth stressing here that economic benefits should not be counted twice. For example, if the market price (adjusted by a conversion factor) is used to estimate economic value, one cannot also count the energy savings or agricultural impact. This would be double counting since the market price includes the consumers' "economic" benefits of using the material or compost.

Nonquantified impacts include the project's impact on land values and quality of life. The value of land near the compost plant may decline and values near the forgone landfill, which would now be smaller or more sanitary, may increase. Health and sanitation benefits can result from composting, and particularly co-composting, when it is compared with more traditional waste disposal options such as open dumping of solid waste or direct land disposal of night soil, sludge and septage.

External environmental impacts of composting/resource recovery could possibly be of value. There are both positive effects -- reduced health water and soil pollution hazards and raw material needs, as well as improved soil structure resulting in less erosion -- and negative ones -- smell, leachate -- which depend on how well the composting operation is managed. If the composting facility is well designed and managed, it is expected to have little if any negative impact on the environment and numerous benefits. Some of these benefits are captured elsewhere in the analysis in such things as recycled materials, less land for landfill, or the market value of compost. Others are not, such as improved sanitation and health. These nonquantifiable benefits are excluded from the analysis. It should also be noted that most of these nonquantifiable benefits of composting may not accrue to the composting enterprise.

For any particular investment, there is also the consideration of sunk costs, for example, existing landfill operations, including land and equipment. For composting, this is not usually significant since rejects would continue to be landfilled and it is unlikely that composting would handle the entire waste stream, more often being only a component in the overall waste management scheme.

Another significant adjustment to the financial model is needed for labor. The economic price of labor depends on the local market supply-and-demand curves, which in turn depend on the opportunities for alternative work and valuation of leisure. For the purpose of these four models, the assumption is that skilled labor is in relatively short supply, with an economic conversion factor greater than 1.0, for example, 1.5, and that there

is a relative surplus of unskilled labor, a factor of, say, 0.5 -- a typical situation in developing countries.

For the illustrative calculations below, capital cost estimates from the financial base case models will remain unchanged in the base case economic models. These costs were originally estimated in US dollars and therefore will serve as economic values for our purposes.

As mentioned earlier, the labor costs for the base case economic models will be adjusted by factors of 1.5 and 0.5 for management and general labor, respectively. Fringe benefits and overtime will remain at 25 percent each, although there may be some small element of a transfer payment in the fringe benefits. Other operating costs will be adjusted to reflect economic prices as discussed previously (table 39).

Table 39. Economic Input Prices (base case)

| Item            | Value                   |
|-----------------|-------------------------|
| Skilled labor   | 2,430 US\$/year         |
| Unskilled labor | 625 US\$/year           |
| Electricity     | 10 US ¢/year            |
| Water           | 2.9 US ¢/m <sup>3</sup> |
| Fuel            | 40 US ¢/liter           |
| Lubricant       | 1.20 US ¢/liter         |

The base case financial price for water has been adjusted upward by an arbitrary 25 percent, even though its economic value is very difficult to estimate; in any case, it is a very small input. The price of water would be more significant if it were used to value the compost's agricultural input savings.

The base case economic models will value the recycled materials at the financial prices, which are rather conservative. The alternative valuation, energy saved, has been estimated for the United States (table 40).

If the energy costs of mining the virgin ore are also included, the values of scrap in terms of energy savings increase. In many cases, these figures are misleading; for example, steel energy savings are dependent on the type of furnace, type of scrap, and end product. For glass the energy savings would be much greater if intact containers were recycled. The type and amount of contamination in plastics greatly affect both the recycling options and energy savings. For paper the quality of the fibers decreases during reprocessing, thereby making it less valuable.

Table 40. Energy Used to Process Virgin and Recycled Materials

| Material                   | Virgin ore | Recycled material | Savings (%) |
|----------------------------|------------|-------------------|-------------|
| (thousands of BTU/kg)      |            |                   |             |
| Steel                      | 18.3       | 9.7 (100% Scrap)  | 8.6 (47)    |
| Glass                      | 17.2       | 15.9              | 1.3 (8)     |
| Plastics<br>(polyethylene) | 109.1      | 3.0               | 106.1 (97)  |
| Newsprint                  | 25.1       | 19.4              | 5.7 (23)    |

Source: Adapted from Hayes (1978).

Assuming that the above figures are reasonable and that the marginal source of energy is imported oil, the approximate energy-based economic value of the recovered materials is shown in table 41.

Table 41. Recycled Material Valuation - Energy Based

| Material                        | \$/ton <sup>/1</sup> | Value \$/ton <sup>/2</sup><br>Domestic solid waste |
|---------------------------------|----------------------|--|
| Paper                           | 30.0                 | 3.60   |
| Textiles <sup>a/</sup>          | 30.0                 | .63  |
| Metals                          | 45.4                 | 1.54   |
| Glass                           | 6.9                  | .10  |
| Plastics & rubber <sup>b/</sup> | 280.0                | 6.72   |
| Total                           |                      | 12.59  |

/1 Based on table 43 and World Bank Commodity Price Data.

/2 Calculations done as in table 32.

a. No data available for rag recycling, value based on newsprint.

b. One half polyethylene.

Except for glass, these energy-based valuations are higher than the financial prices and will only be used for a sensitivity test. This valuation would need adjustment for transport to the recycling plant and any processing overheads beyond the use of virgin materials.

For the economic value of compost in the models, three alternative valuations will be tested. The compost's economic value for a specific project area depends on its quality and ultimate use. As an upper value it is assumed that compost has value equivalent to peat, which is a traded good. Recent peat export prices for Ireland have been about US\$70/ton,<sup>1/</sup> excluding transport which can be costly. The world trade in peat moss is relatively small and is primarily sold to the home garden or commercial nursery markets. Compost should not be considered the full equivalent of peat moss. Therefore, as an upper value of compost we will use the value of peat without any adjustment for transport, that is, US\$70/ton.

Compost is at its lowest value as a low-grade fertilizer; the soil structure value is not included. This would represent a floor on its value if the necessary transport and application costs were ignored.

Approximate 1984 fertilizer prices are listed in table 42.

Table 42. 1984 Fertilizer Prices (approx.)

| Fertilizer   | \$/Ton |
|--|--------|
| Urea (46 percent N)                                    | 170    |
| TSP (46 percent P <sub>2</sub> O <sub>5</sub> )        | 130    |
| Muriate of potash (60% K <sub>2</sub> O <sub>5</sub> ) | 85     |

Based on a co-compost nutrient mix of 1.3, 0.9, 1.0 (N, P, K),<sup>2/</sup> the approximate value would be US\$8.75/ton (ignoring some obvious benefits including the slow-release nature of the nitrogen and the value of the micro-nutrients). The World Bank projections for fertilizers in constant terms show that prices should rise by 37 percent for N, 12 percent for P, and 15 percent for K through 1995. To keep the economic analysis simple, these as well as any other (energy, land) relative increases in economic prices will not be included in this analysis. The fertilizer value needs to be reduced by the

1/ 50% moisture content fob costs 5 Irish pounds/300 liter bale.

2/ If greater amounts of dried sewage sludge were used, these nutrient values would be higher, but in any case they will vary depending on local waste composition.

increased handling, transport, and application costs compared with the equivalent amount of inorganic fertilizer. This cost is estimated at US\$2.75/ton which, when deducted, gives a low-end economic value for compost of US\$6.0/ton ex-factory.

As a realistic base case value for the compost, a conservative estimate was to be used of yield increases and inputs saved that were attributable to compost. Because of the many factors affecting crop yield, this valuation method is probably the least certain but would be the most realistic economic value. For example, typical net incomes for field crops in the developing countries range between US\$200-500/ha, and up to US\$1,200/ha for fruits and vegetables. The reasonable application rate of compost for vegetable crops can be estimated from the figures presented in chapter 5, table 24 and amounts to 50-100 tons every 2 to 4 years. If we assume that 25 tons/ha of compost per year allows net income to increase approximately US\$500-600/ha (switching from field crops to vegetables), the upper agriculture value would be US\$20-24/ton. From this figure we must deduct transport from the plant and application costs. A compost value of US\$20/ton will be used as a proxy in the base case economic models.

This value is very subjective in that it is a substitute for input savings on fertilizer, soil conditioners, and water, which accrue over a period of years; the value of increased crop yields, which depend on the local cropping patterns, soil conditions, etc; and the transport/application costs to achieve these benefits. For areas with badly overexploited soils and/or shortages or lack of fertilizer inputs, the yield response from using compost could be dramatic and therefore its economic value may be much higher in specific locations. There is a lack of data on the benefit of compost resulting from the improvement of the physical structure of soil, and this may be a constraint on the increased demand for, and value of, compost. The market outlets for compost will remain the same for the economic analysis but prices will be equal for all but landfill cover (lowest quality), which will remain at zero.

The base case economic values for other cost factors such as landfill, miscellaneous operating expenses, and working capital, will remain unchanged from the financial models.

#### RESULTS FROM HYPOTHETICAL MODEL CALCULATIONS

The computer model developed (using Lotus 1-2-3) takes the form of a simple line-item budget covering a 20-year period. All of the parameters discussed in this chapter are included. The models assume replacement of equipment in year 10, with no salvage value. There is no provision for resale of the land, or re-use of the landfill. The base case models are built up from the financial price assumptions adjusted by a factor that is set to 1, for the financial analysis, and set to the shadow economic conversion factor for the economic analysis. These factors can readily be substituted to adapt any "base case" situation to a particular investment situation. There are also some standard input/output operating coefficients -- waste composition

and density -- and four sets (one for each base case model) of physical parameters as described in this chapter.

Capital investments are assumed to take one year for models A (3 tons per day) and B (50 tons per day) with a 50 percent capacity utilization reached in that year. For the larger models C (150 tons per day) and D (300 tons per day) investments occur over a two-year period (50 percent each year) with a 50 percent capacity utilization in year 2. For the remainder of the 20 years, capacity utilization is 80 percent.

Since this chapter is not intended to evaluate the financing of investments, no calculation has been included for funding the initial capital investments.

Analysis indicators are calculated at two stages or bottom lines in the hypothetical models. The first is based on the "net with project" (with), which represents the compost facility operations including tipping fee and would be a good indicator if the private sector were running the composting plant but had no responsibility for the landfill. The second indicator is the "net incremental" (incr), which takes into account the benefits of reduced landfill (without project) and excludes the tipping fee (transfer payment). The latter situation would be typical of a situation where the operations -- composting and landfill -- are run by the same entity, that is, municipality. Both bottom lines are calculated for the financial and economic factors, although the "net with" is not really meaningful for the economic analysis. The incremental bottom line is more relevant, even in the financial model, if the compost plant is to be run by the municipal government.

The indicators calculated for each hypothetical model include internal rate of return (IRR), net present value (NPV) per ton of domestic solid waste, which is the cashflow NPV at 12 percent divided by the discounted (at 12 percent) amount of waste processed (NPV/ton). This last indicator adjusts the models to a consistent unit for comparison and is traditionally used in calculating average incremental costs for utility rate setting. In the context of this analysis it gives an indication of the average cost incurred for each ton of waste processed by the co-composting operation.

The results for the hypothetical base case financial models indicate that co-composting is not a financially worthwhile operation even if the forgone landfill benefits are counted. It seems clear that co-composting (including recovery of recyclable materials) will not reduce the cost of waste management and more likely would only increase the financial burden of waste management on municipalities. The base case economic analysis has similar implications and shows that co-composting is likely to be a higher cost waste management alternative than sanitary landfill. See table 43 for the base case financial results and table 44 for the base case economic results.

Sensitivity analysis on the hypothetical financial base case indicates that either the compost or the recycling revenues would need to increase by a factor of 4-5 times for the composting plant (with) to break

Table 43. Base Case Results -- Financial  
NPV(12%)/Ton Domestic Solid Waste Processed

| Category               | Model        |              |              |              |
|------------------------|--------------|--------------|--------------|--------------|
|                        | A            | B            | C            | D            |
| <b>COSTS</b>           |              |              |              |              |
| Capital                | -10.9        | -17.5        | -23.1        | -18.7        |
| Operating              | -15.6        | - 5.2        | - 5.5        | - 4.4        |
| <b>REVENUES</b>        |              |              |              |              |
| Recycled materials     | 4.8          | 4.8          | 4.8          | 4.8          |
| Compost                | 2.9          | 2.9          | 2.9          | 2.9          |
| Tipping fee            | 1.0          | 1.0          | 1.0          | 1.0          |
| Net With Project       | <u>-17.8</u> | <u>-14.0</u> | <u>-19.9</u> | <u>-14.4</u> |
| <b>WITHOUT PROJECT</b> |              |              |              |              |
| Reduced landfill       | 4.1          | 4.1          | 4.1          | 4.1          |
| Tipping fee            | - 1.0        | - 1.0        | - 1.0        | - 1.0        |
| Net Incremental        | <u>-14.7</u> | <u>-10.9</u> | <u>-16.8</u> | <u>-11.3</u> |

Table 44. Base Case Results -- Economic  
NPV(12%)/Ton Domestic Solid Waste Processed

| Category                        | Model        |              |              |              |
|---------------------------------|--------------|--------------|--------------|--------------|
|                                 | A            | B            | C            | D            |
| <b>COSTS</b>                    |              |              |              |              |
| Capital                         | -10.9        | -17.5        | -23.1        | -18.7        |
| Operating                       | -11.9        | - 5.9        | - 6.0        | - 5.1        |
| <b>REVENUES</b>                 |              |              |              |              |
| Recycled materials              | 4.8          | 4.8          | 4.8          | 4.8          |
| Compost                         | 6.0          | 6.0          | 6.0          | 6.0          |
| <b>NET WITH</b>                 |              |              |              |              |
| Reduced landfill                | <u>-12.0</u> | <u>-12.5</u> | <u>-18.3</u> | <u>-12.9</u> |
|                                 | <u>4.1</u>   | <u>4.1</u>   | <u>4.1</u>   | <u>4.1</u>   |
| <b>NET INCREMENTAL</b>          |              |              |              |              |
|                                 | <u>- 7.9</u> | <u>- 8.5</u> | <u>-14.3</u> | <u>- 8.9</u> |
| <b>Internal Rate of Return%</b> |              |              |              |              |
| - Incremental                   | - 9.0        | - 0.8        | - 4.6        | 0.0          |

even (IRR = 12% or NPV/ton [12%] = 0) at a 12 percent discount rate. The increase in either compost or recycled revenues required would be somewhat less -- approximately three to four times as high -- if the compost plant received a tipping fee equal to the forgone landfill costs of about US\$4/ton (i.e., net incremental). A tipping fee of 14-20 US\$/ton (equivalent to the net with project loss) would be required for the plant to break even financially at a 12 percent discount rate. The required increase in total revenues -- compost plus recycled materials -- would need to more than double from the base case for the "with project" to have a 12 percent rate of return.

Sensitivity on compost revenues in the hypothetical economic base case indicates that the use of a peat-based valuation (US\$70/ton) would make co-composting viable. The use of the N-P-K valuation for compost results in about a US\$4/ton decrease in NPV from the economic base case. Energy valuation for recycled materials makes significant impact on the economic base case, decreasing waste processing costs about US\$7/ton in PV from the base case. The substitution of sewage sludge for night soil would raise compost production and revenues about 7 percent.

Table 45 outlines the results of adjusting the base economic models to approximate the aerated pile and an enclosed reactor system (Model A is excluded since it is using manual processing).

Table 45. Alternative Technologies -- Results (Economic Values)  
NPV (12%) \$/ton Domestic Solid Waste Processed

| Composting technology      | Model |     |     |
|----------------------------|-------|-----|-----|
|                            | B     | C   | D   |
| Reactor <sup>a/</sup>      |       |     |     |
| NPV/ton (with)             | -25   | -33 | -25 |
| NPV/ton (incr)             | -21   | -29 | -21 |
| Aerated pile <sup>b/</sup> |       |     |     |
| NPV/ton (with)             | -15   | -13 | - 8 |
| NPV/ton (incr)             | -11   | - 9 | - 4 |

- a. Investment costs (excluding land) up 60%, operating costs up 20%, land for plant down 20%.
- b. Investment costs up 20% for model B and down 20% for models C & D (to reflect the addition of fans to all models and deletion of windrow-turning machines in models C & D), operating costs down 20%.

The reactor option is much more costly; the aerated pile costs, however, are slightly worse for labor-intensive model B and slightly better for models C & D by about US\$4/ton in NPV terms than the base case economic models. The potential advantage of the aerated pile system is that the process is somewhat more controlled in terms of uniform temperature achieved, which is critical in destroying the pathogens in the night soil sludge and septage and thus removing them from the environment. The aerated pile system should be investigated as the system of lowest cost when considering co-composting.

Sensitivity of the economic models to land pricing was also tested. There was a marginal impact of higher land prices on the models' indicators for the with or incremental bottom lines since land is a relatively minor component of the compost plant net with project, and increased costs there are offset by increased benefits (landfill forgone) in the without. The real impact of land prices was seen in the widening of the difference between the net with and net incremental indicators. The relative land valuation might become critical in the situation where sanitary landfill options are no longer available within a reasonable distance to the waste source.

Sensitivity tests on a combination of factors were also carried out. These are intended to demonstrate the potential cost effectiveness of co-composting in specific local situations that might be more favorable than assumed for the base case analysis. These sensitivity results are presented for Model A - 3tpd economic base case in table 46 below.

Table 46. Sensitivity Tests - Multiple Change

| Category                                 | Model A - 3tpd - Economic<br>% Change from Base Case |       |      |       |      |
|--|--|-------|------|-------|------|
| <u>Line Item Changes</u>                 |  |       |      |       |      |
| Compost revenues                         | +100   | +50   | + 25 | +100  | 0    |
| Recycled revenues                        | +100   | +50   | + 25 | +50   | 0    |
| Reduced Landfill costs (without project) | 0  | +100  | +100 | +50   | +200 |
| <u>Results</u>                           |  |       |      |       |      |
| IRR - incremental                        | +18.3  | +15.5 | +9.6 | +17.5 | +3.3 |
| NPV/Ton - incremental (12%)              | + 3.0  | +1.6  | -1.1 | +2.6  | -3.8 |

From the illustrative calculations done here one may conclude that, if local conditions correspond to any of these sensitivity scenarios, further detailed investigation is warranted. However, any significant investment in composting should be done only after detailed analysis of potential markets and a commitment has been made to actively market the compost and recovered recyclables.

Many other sensitivity tests have been carried out and a copy of the Lotus 1-2-3 template can be made on diskettes (one 5-1/4" IBM format required) sent in by interested persons. A short user's manual will also be provided on the diskette explaining the structure of the template. There are customized menus that allow the selection of model size, economic or financial prices (factors), as well as various sensitivity tests for IRR and NPV/PV on investments, operating and maintenance, recycled materials, sales, compost sales, tipping fee and without project (-100 percent, -50 percent, +100 percent, +200 percent, +300 percent, +400 percent, +500 percent). A custom menu for printing the assumptions, or results, is also included. For those readers familiar with the Lotus 123, any of the assumptions outlined in this chapter can, of course, be changed to allow for analyses of specific situations: (1) where compost values (prices) may be higher than the base case assumptions because of, for example, scarce or poor quality land, large horticulture industry, or shortages of inputs; (2) where a subset of the domestic solid waste collected may not require sorting prior to co-composting, as in produce markets; or (3) where sanitary landfill of domestic solid waste is not an option such as when there exists a high water table or scarcity of land and co-composting is thought to be a cost-effective component of the waste management.

## CHAPTER 7

### SUMMARY

Refuse collection, treatment, and disposal is one of the major problems facing urban planners and operators in many developing countries today, in addition to the problems associated with inadequate treatment and disposal of human wastes.

Unsightly piles of waste, drains clogged with refuse and night soil, open sewers filled with human and domestic wastes, and septic tank sludge dumped in the open are all examples of ways in which the urban environment is being polluted today in many cities and towns of the developing world. City dwellers are being exposed to diseases transmitted by pathogens present in these wastes as well as to the nuisances produced by the situation. Furthermore, the volume of waste being produced is rapidly increasing with the influx of rural dwellers into the urban environment. Indeed, proper refuse and human waste management is fast becoming a priority in many cities in developing countries that are rapidly growing in size.

In the preceding chapters, co-composting of garbage with human wastes has been described in detail through both a review of the literature and economic and financial models, with discussion centering on the following issues:

- the robustness of the aerobic composting process
- the variety of available composting systems
- the possibilities of co-composting different wastes
- the effectiveness of efficient composting systems in destroying disease-causing organisms
- the many uses of compost
- the economics of different-sized composting systems.

The choice of co-composting as a waste treatment alternative for garbage and human waste must be considered in the light of other existing treatment alternatives such as landfilling, incineration, and the ocean dumping of sludge.

Before deciding to compost, the planner must consider and review several basic factors already described in previous chapters. This includes information on the waste material; transport of the wastes and the compost that is produced; marketing of the product; the construction, operation, and maintenance costs; the location and land requirements of the plant; and the type of plant that would be most suitable for producing compost under local conditions. If the decision is taken to consider composting as an option for

waste treatment and management, the role these factors will play in ensuring the success of a composting operation must be stressed. Some of the more significant elements are reiterated below.

#### WASTE MATERIAL

It is important to determine the nature and composition of the wastes to be composted. Such basic information will be of use later when the time comes to choose an appropriate composting system. Furthermore, it is useful to know how the collection of these wastes would fit into the overall waste management system (e.g., landfilling and incineration) and if there are already waste-recycling activities to which this could be added, such as organized sorting of garbage for recyclables or scavenging and biogas operations.

#### MARKET

Is there a market for any compost that might be produced? Perhaps there are crop farmers or horticulturists in the city outskirts who would use it to improve the quality and productivity of their crops. Maybe the public or private sector is involved in a landscaping program, or perhaps there is badly eroded topsoil or sandy and/or clay soils that could be reclaimed for productive use. The financial viability of co-composting garbage and human waste is dependent on a well-developed market that is willing to pay at least for the costs of production.

#### COMPOST PLANT

Next, we ask about the type of plant, taking into consideration possible location, availability of trained technical staff and manual labor, and financial resources to cover capital and operating costs, in order to determine which system would be most appropriate for the city. Economic and financial feasibilities will be of importance in considering the costs involved for a specific system. The planner may often find that a simple windrow or forced aeration system will best suit the capabilities of the establishment and will be therefore most effectively run. There is also the consideration of the potential for manufacture nationally, thus reducing the requirement for foreign exchange components.

#### PILOT SCALE COMPOSTING

Once the waste materials and composting system have been identified, it is useful, if a large-scale operation is being planned, to start with a pilot plant. This will serve two purposes: first, the prospective operators will become familiar with the process; second, it will serve as a good public relations exercise to produce small amounts of compost for sale or as samples for the potential market.

## BENEFITS AND JUSTIFICATION

Finally, what benefits accrue from the separation/compost operation? There are those that can be readily quantified, such as reducing the need for sanitary landfill of garbage and recovering materials for industry, which often obviate importation or mining of similar industrial materials. For specific waste management activities, the careful integration of composting operations should allow for more efficient collection networks, the savings of which can easily be quantified and used to offset the cost of composting. In addition, it should be relatively simple to demonstrate the benefits of compost in terms of improved soil productivity, measured as increased yields and/or reduction of other inputs (fertilizers and water), and easier tillage. This can easily be carried out in a controlled trial using compost produced locally on a trial basis for two or three cropping seasons perhaps at the pilot compost plant.

Other benefits, such as the effect of compost on the quality and longevity of the soil, the reduced health risk of having pathogenic material in the environment, and the improved aesthetic quality of the surroundings, are difficult to quantify but are of importance in ensuring adequate maintenance of the environment.

There are many examples in the world where the high costs of environmental degradation are plainly seen with hindsight but were not quantified at a time when something could have been done to prevent them. The valuation of productive soils in the future may be much greater than we now can quantify and, with hindsight, composting may eventually look more attractive.

Situations in which the economic models will show that composting is economically viable or the least-cost waste management alternative are quite site-specific. Where landfilling of waste is very costly due to high land values or high transport costs, composting may become the least-cost alternative for waste management. Often the composting plant can be located in such a way as to reduce collection and landfill costs, both of which should be included as benefits when evaluating least-cost waste management alternatives. The marketability for the compost is the other critical benefit. At the present time horticultural nurseries in peri-urban areas and desert land reclamation areas offer the best economic returns. It is possible, however, that the economic benefits from improved soil structure are considerably greater than has been generally appreciated, although the analysis in this report does not attribute any specific economic value to such improvement, simply because there is a lack of empirical field data from which to quantify economic returns. Were such quantification to be available, it is likely that the models prepared for this report would show that composting is also economically attractive under other conditions.

To embark on a large composting operation is to embark on a long-term activity which ensures both the improvement of soil for agricultural purposes, at a time when increased food production is so important, and the conversion of waste materials into resources.

ANNEX A

OTHER METHODS OF CO-COMPOSTING WITH SEWAGE SLUDGE AND NIGHT SOIL

**SEWAGE SLUDGE AND NIGHT SOIL COMPOSTED WITH BARK**

The composting of sludge and night soil together with bark is carried out in both reactor and nonreactor systems. The use of bark depends, of course, on the availability of the material (for example, on the location of a wood-processing plant in the vicinity or within easy transport distance). Table A-1 describes some of these systems. In all cases, the temperatures achieved during the composting period would indicate adequate pathogen removal. In compost plants where bark is used as a bulking agent, odor control does not appear to be a problem, possibly because of the odor-absorbing properties of the bark. Problems can occur if the wood has been treated with pesticides, since they may persist in the compost.

**SEWAGE SLUDGE AND NIGHT SOIL COMPOSTED WITH STRAW**

Straw is a waste material that is readily composted with sewage sludge in reactor as well as nonreactor systems. The examples described in table A-2 are of both types (though mainly the latter). The use of straw in composting is common in farming communities but is not limited to them. As table A-2 indicates, a windrow compost product can be ready within 4 months of starting the process. Forced aeration would speed up the composting process.

**SEWAGE SLUDGE AND NIGHT SOIL COMPOSTED WITH WOOD CHIPS**

The Beltsville aerated static pile composting process is well documented and reviewed in the literature (see, for example, Nurizzo 1981). The windrow method of composting sludge with wood chips is also well documented. The two processes are similar in terms of product quality but the windrow method appears to be more suitable for digested than for raw sewage sludge. The forced aeration process is also used for composting night soil (Patterson and Rogers 1979; Shuval, Gunnerson, and Julius 1981).

Table A-1. Composting of Sludge and Night Soil with Bark

| Raw material  | Process   | Description   | Reference   |
|---|---|---|---|
| Night soil and bark                                     | Dry (summer) toilet                             | Bark was added to night soil in dry toilets at the rate of 4 parts bark to 1 part night soil. Temperatures of over 60° C were achieved.   | Alestalo and Koistinen (1975)   |
| Sludge and bark   | Windrows  | Bark and sludge (and other wastes) were mixed together and composted to produce "Bambe," a marketable product.  | Adams (1971)  |
| Digested sewage, sludge, and bark                       | Open baskets                                    | Dewatered digested sewage sludge was mixed with bark (1:3) and composted in large baskets that could be easily stacked. Temperatures of up to 75° C were attained. The retention time in the baskets was 9-12 weeks followed by 3-4 weeks maturation in piles to produce "Rindekompost."                            |   |
| Raw dewatered sewage sludge and bark                    | Windrows  | Dewatered sewage sludge (25 percent solids) mixed with bark (1:3) and composted in windrows for at least 21 days. In general, temperatures of 50-75° C are maintained for at least half of this time, although it is less in the winter.  | Wesner (1978), Oliver (1980)  |
| Dewatered sewage sludge and bark (and recycled compost) | Vertical reactor with 10 levels Dambach Schnoor | Dewatered sludge (22-25 percent solids) is mixed with bark (2:1) and fed into a 10-level reactor. Retention time is 30 days and movement from level to level through traps in floor occurs every 3 days. Temperatures are usually maintained at 70° C or higher for about 10 days and over 50° C more than 15 days. | Schwanhauser (1978), Biddingmaier (1979), Tabasaran (1980), Tabasaran et al. (1981) |

Table A-2. Composting of Sludge and Night Soil with Straw

| Raw material                          | Process         | Description   | Reference  |
|---------------------------------------|-----------------|---|--|
| Raw dewatered sewage sludge and straw | Windrows        | (Full-scale experimental plant.) The sewage sludge (25-30 percent solids) was mixed with straw (1:1 volume) and composted in windrows, which were turned regularly (8 times) for 3 months. At the end of this time the compost was ready for use. Temperatures of 55-60° C were regularly achieved even in some of the colder months. | Muhlacker (1980)   |
| Raw dewatered sewage sludge and straw | Windrows        | Experiments. The sludge (21.8 percent solids) was mixed with straw at a ratio of (28:1). Temperatures of 55-62° C were maintained in windrows, which were turned once weekly for 3 months (in earlier stages there were problems with fly control).   | Tabasaran and Leusterer (1979)   |
| Digested sludge and straw             | Windrows        | Experiment. Digested sludge was mixed with straw at a ratio of 1:1.25 in windrows for 6 weeks during which temperatures of 65-70° C were achieved as above, except the ratio of mixture was 1:5 of sludge to straw.   | Klausing (1975), Bidlingmaier and Tabasaran (1980), Bidlingmaier (1979), Bidlingmaier and Bickel (1980), Strauch, Berg, and Fleischle (1980) |
| Sewage sludge and straw               | Biomist windrow | The straw is chopped and mixed with the sewage sludge and then sprayed out into a windrow.  | Bidlingmaier (1979), Bidlingmaier and Bickel (1980), Bidlingmaier and Tabasaran (1980)   |

(cont.)

**Table A-2 (cont.)**

| Raw material            | Process                 | Description  | Reference                      |
|-------------------------|-------------------------|--|--------------------------------|
| Sewage sludge and straw | Dambach Schnorr reactor | Dewatered sewage sludge is mixed with chopped straw (and/or other bulking agents) and fed into the reactor, which has a retention time of 30 days. | Bidlingmaier and Bickel (1980) |

**Table A-3. Description of the Beltsville Aerated Static Pile and Windrow Composting**

| Raw material   | Process description   | Reference       |
|--|---|-----------------|
| Sewage sludge and wood chips (windrow)                       | Digested sewage sludge is mixed with wood chips (1:3 volume ratio) in windrows 1.8 meters high and 2.1 meters wide. The windrows are turned daily for at least 2 weeks, then they are spread out, dried, and cured for 30 days. The wood chips are screened out for reuse.  | Dallaire (1978) |
| Sewage sludge and wood chips (aerated pile)                  | Raw sewage sludge (22 percent solids) is mixed with wood chips, and then transferred to a composting pad consisting of wood chips spread over perforated piping. Air is drawn through the pipe into a compost filter. The pile is maintained for 21 days followed by screening and drying. Temperatures of 55° C are achieved throughout the pile.      |                 |
| Night soil (toilet wastes), paper, wood chips (aerated pile) | The night soil is mixed with paper and wood chips on a concrete pad and then transferred to the composting pad, which is a bed of wood chips covering a perforated pipe. Air is drawn through the pipe into a compost filter. The pile is maintained for 21 days at temperatures of 60° C for most of this time. The compost is then cured for 30 days. |                 |

The two processes using sewage sludge are described briefly in table A-3 together with a process using night soil (from chemical toilets). It should be noted that it is not essential to use only wood chips in the Beltsville process; other organic bulking agents (for example straw, woodbark) may also be used. Detailed experiments carried out on pathogen removal using the Beltsville aerated pile process have shown it to be efficient at reducing the pathogen content of the product (Burge, Cramer, and Epstein 1976; Burge, Marsh, and Millner 1977; Burge and Millner 1980).

#### SEWAGE SLUDGE AND NIGHT SOIL COMPOSTED WITH OTHER MATERIALS

Many other raw materials have been composted together with sewage sludge and night soil. Some of these are described in table A-4 to show the versatility of the process.

In many areas, animal wastes are composted together with sewage sludge and/or night soil. As noted in chapter 3, this should have no adverse effects on pathogen control.

Table A-4. Methods of Composting Sewage Sludge with Other Bulking Agents

| Raw material   | Process                       | Description   | Reference  |
|--|-------------------------------|---|--|
| Sludge, mushroom wastes, poultry wastes, organic bulking agent | Biomist windrow               | The mixture is sprayed out onto a windrow.  | Mach (1978)  |
| "  | Kneer bioreactor (BAV system) | The mixture is retained in the reactor for 14 days. Temperatures of 60-85° C are maintained for most of this time. Then the raw compost is matured for 6-8 weeks in a windrow.  | Mach (1978)  |
| Raw sewage sludge and sawdust and recycled compost             | BAV bioreactor (open)         | Dewatered raw sewage (25 percent solids) is mixed with sawdust and return compost (50, 10, and 40 percent, respectively) and fed into a cylindrical reactor, which is open at the top. Retention time is 3 days. This is followed by 6-8 weeks of maturation in windrows. Temperatures of 75-80° C are reached. | Oger (1981), Bidlingmaier (1979), Bidlingmaier and Tabasaran (1980), Tabasaran et al. (1981) |

(cont.)

Table A-4 (cont.)

| Raw material  | Process                    | Description   | Reference  |
|---|----------------------------|---|--|
| Raw sewage sludge and peat, straw lignite.          | BAV bioreactor (open)      | As above, except mixture is 1:1.  | Wolf (1974)  |
| Raw sewage sludge and sawdust and recycled compost. | Weis bioreactor (closed)   | The dewatered sewage sludge (25 percent solids) is mixed with sawdust and recycled compost and fed into a closed cylindrical reactor, where it is retained for 10-14 days.  | Bidlingmaier (1979),<br>Bidlingmaier and Bickel (1980),<br>Bidlingmaier and Tabasaran (1980),<br>Tabasaran et al. (1981) |
| Sewage sludge and peat                              | Biohum process windrow     | The raw materials are mixed together and composted in a windrow.  | Mach (1978)  |
| Sewage sludge and rice hulls and recycled compost   | Trough fermenter           | The digested sewage sludge is mixed with rice hulls and finished compost (1:1:1 volume) and fed into a trough where it is composted for 2 weeks by forced aeration and turning. This is followed by 1-2 months of maturation. Temperatures reach up to 70° C.   |  |
| Sewage sludge and shredded paper                    | Fairfield digester reactor | Dewatered sewage sludge is mixed with shredded paper and fed into a reactor. The retention time is 7 days and temperatures reach 70° C during this time.  | Wesner (1978)  |
| Sewage sludge and sawdust (also recycled compost)   | Triga process cell reactor | The sewage sludge (15-20 percent solids) is mixed with sawdust at a ratio of 1:5 wt and fed into a vertical reactor consisting of four cells. The retention time is 12-15 days and temperatures of 70-80° C are achieved. Maturation occurs in piles (in a shed) in which temperatures often reach 50° C. | Schneider (1981)   |

(cont.)

Table A-4 (cont.)

| Raw material  | Process                              | Description  | Reference   |
|---|--------------------------------------|--|---|
| Sewage sludge and sawdust (and other bulking material)  | Windrows                             | The windrows are turned for 3 months and then sold as a product "Grow Rich." The contents of the windrows are dewatered sewage sludge (30 percent solids) and sawdust at weight ratios 80:20. The maximum temperature achieved is 74° C.   | Heaman (1977), Breer (1980)                               |
| Water hyacinth, night soil, rice straw                  | Windrow/ piles                       | Experiment. Night soil, water hyacinth, and (in some cases) rice straw were mixed and composted in piles for 2-3 months. Temperatures of 43-64° C were maintained for at least 8 days in the coolest parts of the piles.                   | Polprasert and Muttamara (1980), Polprasert et al. (1982) |
| Night soil rice husks, grass cuttings, briquette cinder | Windrows aeration by various methods | Night soil is mixed with different amounts of rice husks, grass cuttings, or briquettes of cinder into windrows. These are aerated by various methods. Temperatures of up to 70° C are achieved and >50° C maintained for at least 8 days. | Kim and and Bae (1981)                                    |

### SEWAGE SLUDGE AND NIGHT SOIL COMPOSTED WITHOUT THE ADDITION OF BULKING AGENTS

The processes described in table A-5 indicate some of the ways in which sewage sludge or night soil can be composted without the addition of any bulking agents. In all the examples given, the sludge has to be dewatered before being mixed with the recycled compost. (If night soil is used instead, some dewatering may also be required.) The temperatures achieved during composting in the examples given here should be sufficient to ensure a relatively pathogen-free product if they are maintained for almost all the retention time and are kept uniform throughout the reactor.

Table A-5. Methods of Composting Sewage Sludge and Night Soil Alone

| Raw material  | Process            | Description  | Reference   |
|---|--------------------|--|---|
| Sewage sludge and recycled compost                              | Laboratory reactor | Dewatered sludge cake was successfully composted in a laboratory scale reactor in which temperatures of 60-70° C were maintained.  | Schuchardt and Baader (1979)  |
| Digested sewage sludge and recycled compost (also some sawdust) | Bioreactor         | Dewatered digested sewage sludge (20-25 percent solids) is mixed with recycled compost in a vertical reactor for 14 days. Temperatures of 60-70° C are reached. The air drawn out of the reactor is passed into an activated sludge tank. Maturation of compost takes place for 6 weeks in windrows. | Molliet (1981)  |
| Sewage sludge and recycled compost                              | HKS process        | The sludge and recycled compost are added to a slowly rotating drum (which is stopped at night). The retention time is 24 hours followed by a 2-week maturation period in a windrow. Temperatures of 60-75° C are attained.  | Bidlingmaier (1979), Tabasaran (1980), Bidlingmaier and Bickel (1979), Spennes and Britsch (1977) |

(cont.)

Table A-5 (cont.)

| Raw material                                       | Process                           | Description  | Reference  |
|--|-----------------------------------|--|--|
| Dewatered sewage sludge and recycled compost       | Windrow                           | The sewage sludge is mixed with recycled compost at a ratio of 3:2 and deposited as a windrow, which is turned by a composter for 4 weeks. This is followed by 30 days of maturation.  | Gunn (1980)  |
| Sewage sludge (dewatered) and recycled compost     | Roediger Ferment-technik          | The sewage sludge is mixed with recycled compost and put in a vertical reactor. The retention time is 4-6 days, after which the compost is put in a dryer for a further 4-6 days; it is then pelleted and stored for sale. Temperatures of over 65° C are attained in the reactor. | Widmer and Konstandt (1978), Bidlingmaier (1979), Bidlingmaier and Bickel (1978), Tabasaran et al. (1981), Bidlingmaier and Tabasaran (1980) |
| Dewatered sewage sludge and recycled compost       | Forced aeration through fermenter | The sewage sludge and recycled compost are mixed and ground and fed into the fermenters, where the mixture is aerated and turned. The retention time is 10 days and temperatures of up to 75° C are attained. The compost is then graded and bagged.                               |  |
| Raw or digested sewage sludge and recycled compost | Vertical reactor (pilot plant)    | The dewatered sludge is mixed with recycled compost and fed into a vertical reactor consisting of two levels. Retention time is 7-9 days, during which temperatures of 65-70° C are reached and maintained.  | Maebashi (1980)  |

(cont.)

Table A-5 (cont.)

| Raw material  | Process          | Description  | Reference    |
|---|------------------|--|--------------|
| Raw sludge and recycled compost                     |                  | The dewatered sludge (60 percent moisture) is mixed with finished compost three parts to two and the mixture is laid as a windrow over a bed of straw on a concrete floor having an aeration-and-drainage system. A Cobey composter is used to mix the materials. The retention time is 4 weeks, followed by 30 days of curing. Temperatures reach 76° C during this time. |              |
| Digested or conditioned sludge and recycled compost | Pellets in piles | The sludge is dewatered and passed through a mincer to make pellets. These are piled for up to 8 weeks after mixing with recycled compost.   | Spohn (1978) |

ANNEX B  
PATHOGEN SURVIVAL

Table B-1. Survival of Bacterial Pathogens during Composting

| Pathogen                          | Raw Material Type  | Temper-ature (°C) | Time                        | Survival % | Source                        |
|-----------------------------------|--|-------------------|-----------------------------|------------|-------------------------------|
| <u>Bacillus anthracis</u>         | Refuse/sludge in reactor   | 40-43             | 3 days<br>7 days<br>15 days | 0<br>0     | Miersch and Strauch (1978)    |
| <u>B. anthracis</u>               | Refuse/sludge in windrow   | 65                | 2 weeks                     | 0          | Miersch and Strauch (1978)    |
| <u>B. anthracis</u>               | Refuse/sludge in reactor   | 58<br>74          | 12 days<br>12 days          | 0<br>0     | Miersch and Strauch (1978)    |
| <u>Escherichia coli</u>           |  | 55                | -                           | 0.01       | Wiley (1962)                  |
| <u>E. coli</u>                    | Dewatered raw sludge and wood chips in windrow                       | 50-70             | 14 days                     | 1          | Burge and Cramer (1974)       |
| <u>E. coli</u>                    | Refuse and sludge in drum  | 55<br>55          | 2 days<br>7 days            | 0<br>0     | Krogstad and Gudding (1975)   |
| <u>E. coli</u>                    | Night soil and 29<br>rubbish in 40<br>pile, aerobic<br>and anaerobic | 29<br>40          | -<br>-                      | 0.01<br>0  | McGarry and Stainforth (1978) |
| <u>E. coli</u>                    | Raw sludge, digested sludge  | 50-70<br>40-60    | 3 days<br>14 days           | (low)<br>0 | Burge et al. (1978)           |
| <u>Mycobacterium tuberculosis</u> | Refuse   | 65                | 14 days                     | 0          | Morgan and MacDonald (1969)   |

(cont.)

Table B-1 (cont.)

| Pathogen                           | Raw Material Type   | Temper-<br>ature (°C) | Time                        | Survival %  | Source                            |
|------------------------------------|---|-----------------------|-----------------------------|-------------|-----------------------------------|
| <u>Salmonellae</u>                 | Sludge windrow  | 60                    | 8 days                      | 0           | Faust and Romano (1978)           |
| <u>Salmonellae</u>                 | Activated and primary sludge windrow  |                       | 1-5 weeks                   | high        | Wesner (1978)                     |
| <u>Salmonella</u>                  | Refuse compost 55 (DANO)  |                       | 3 days<br>17 hours          | 0           | Golueke and Gotaas (1954)         |
| <u>Salmonella</u><br>spp.          | Refuse and sludge in windrows   | 55-70                 | 50 days                     | 0           | Knoll (1959), quoted Wiley (1962) |
| <u>Salmonella</u><br>spp.          | Sewage sludge and wood chips  | 50-70                 | 14 days                     | 0           | Burge and Cramer (1974)           |
| <u>Salmonella</u><br>spp.          | Refuse and sludge windrow   |                       | 7-21 days                   | 0           | Gaby (1975)                       |
| <u>Salmonella</u><br>spp.          | Sludge windrow  |                       | 10 days                     | 0           | Epstein et al. (1976)             |
| <u>Salmonella</u><br><u>dublin</u> | Refuse and sludge in windrow  | 65                    | 2 weeks                     | 0           | Miersch and Strauch (1978)        |
| <u>S. dublin</u>                   | Refuse and sludge in reactor,<br>48 percent H <sub>2</sub> O, 15 square centimeters | 40-43                 | 3 days<br>7 days<br>15 days | 0<br>0<br>0 | Miersch and Strauch (1978)        |
| <u>S. newport</u>                  | Sewage sludge   | 60-70                 | 15 hours                    | 0           | Wiley and Westerberg (1969)       |
| <u>S. paratyphi</u>                | Refuse and sludge in windrows   | 50                    | 2 days                      | 0           | Knoll (1958)                      |

(cont.)

Table B-1 (cont.)

| Pathogen               | Raw Material Type   | Temperature (°C) | Time                        | Survival %  | Source                              |
|------------------------|---|------------------|-----------------------------|-------------|-------------------------------------|
| <u>S. paratyphi</u>    | Garbage   | 30-65            | 68 hours                    | 0           | Barth and Brauss (1967)             |
| <u>S. paratyphi</u>    | Feces and garbage windrow   | 68               | 14 days                     | 0           | Savage, Chase, and MacMillan (1973) |
| <u>S. seftenburg</u>   | Refuse and sludge in reactor, 48° C to H <sub>2</sub> O, 15 centimeters | 40-43            | 3 days<br>7 days<br>15 days | 0<br>0<br>0 | Miersch and Strauch (1978)          |
| <u>S. seftenburg</u>   | Refuse and sludge in windrow  | 65               | 2 weeks                     | 0           | Miersch and Strauch (1978)          |
| <u>S. typhi</u>        | Garbage   | 30-65            | 68 hours                    | 0           | Barth and Brauss (1967)             |
| <u>S. typhi</u>        | Feces and garbage windrow   | 55               | 40 days                     | 0           | Savage et al. (1972)                |
| <u>S. typhi</u>        | Night soil and garbage  | 50<br>55         | 1 month<br>5 days           | 0<br>0      | Chinese Academy of Sciences (1975)  |
| <u>S. typhi-murium</u> | Refuse and sludge   | 65<br>55         | 2 days<br>4 days            | 0<br>0      | Krogstad and Gudding (1975)         |
| <u>Shigellae</u>       | Refuse compost DANO   | 55               | 3 days<br>17 hours          | 0           | Golueke et al. (1954)               |
| <u>Sh. sonnei</u>      | Garbage   | 60<br>55         | 1-3 days<br>3-7 days        | 0<br>0      | Baetgen (1962)                      |
| <u>Sh. dysenteriae</u> | Night soil  |                  | 5 days                      | 0           | Feachem et al. (1980)               |

- not stated.

Table B-2. Survival of Viral Pathogens during Composting

| Pathogen                      | Raw Material Type  | Temper-ature (°C) | Time                | Survival % | Source                           |
|-------------------------------|--|-------------------|---------------------|------------|----------------------------------|
| Bacterio-phage                | Sewage sludge and grass, sewage sludge and refuse                      | 40                | 6 days              | 0          | Krige (1964)                     |
|                               |  | 38-60             | 14 days             | 0          |                                  |
|                               |  |                   | 6 days              | 0          |                                  |
| Bacterio-phage f <sub>2</sub> | Sewage sludge and wood chips, sewage sludge and wood chips turned once | 50-70             | 2 weeks             | 1          | Burge and Cramer (1974)          |
|                               |  | 50-70             | 2 weeks             | 10         |                                  |
|                               | " "  | 50-70             | 2 weeks and 70 days | 0          |                                  |
|                               | " "  | mesophili-c       | 1 month             | 1          |                                  |
| Bacterio-phage f <sub>2</sub> | Raw sludge and wood chips, digested sludge and wood chips              | 50-70             | 50 days             | 0          | Kawata, Cramer, and Burge (1977) |
|                               |  | 40-60             | 70 days             | 0          |                                  |
| Coliphage f <sub>2</sub>      | Sludge and wood chips  | 50                | 13 days             | 0          | Burge et al. (1978)              |
|                               |  |                   | 21 days             | 0.001      |                                  |
| Poliovirus                    | Sludge   | 35-58             | 7 days              | 0          | Krige (1964)                     |
| Poliovirus 1                  | Sewage sludge  | 60-70             | 3 days              | 0          | Wiley and Westerberg (1969)      |
| Poliovirus 1                  | Refuse and sludge  | -                 | 8 days              | 0          |                                  |
| Poliovirus type 2 (inserted)  | Sludge and refuse mix  | -                 | 3-7 days            | 0          | Gaby (1975)                      |

- not stated.

Table B-3. Survival of Protozoal Pathogens during Composting

| Pathogen                     | Raw Material Type          | Temper-<br>ature (°C) | Time             | Survival % | Source       |
|------------------------------|----------------------------|-----------------------|------------------|------------|--------------|
| Protozoan cysts              | Vegetable matter and feces | 55-60                 | 3 weeks          | 0          | Scott (1952) |
| <u>Entamoeba histolytica</u> | Refuse and sludge          | 49<br>55              | 8 days<br>7 days | 0<br>0     | Gaby (1975)  |

Table B-4. Survival of Helminthic Pathogens during Composting

| Pathogen                           | Raw Material Type                    | Temper-ature (°C)       | Time                                    | Survival %          | Source                             |
|------------------------------------|--------------------------------------|-------------------------|---|---------------------|------------------------------------|
| Helminthic ova                     | Refuse/sludge                        | -                       | 7 days                                  | 0                   | Gaby (1975)                        |
| Helminthic ova                     | Refuse/sludge                        | 40                      | 28 days                                 | 6-0                 | McGarry and Stainforth (1978)      |
| <u>Ascaris lumbricoides</u> ova    | Night soil and garbage               | 65                      | 1 month                                 | 5                   | Stone (1949)                       |
| <u>Ascaris lumbricoides</u> ova    | Feces and vegetable matter, ash soil | 65                      | 5 days<br>12 days<br>22 days<br>67 days | 15<br>4<br>0.3<br>0 | Scott (1952)                       |
| <u>Ascaris lumbricoides</u> ova    | Sludge                               | 55-70                   | 2 months                                | 15-0                | Murray (1960)                      |
| <u>Ascaris lumbricoides</u> ova    | Sludge                               | 60-76                   | 1 hour                                  | 0                   | Wiley and Westerberg (1969)        |
| <u>Ascaris lumbricoides</u> ova    | Garbage and night soil               | 5-64                    | 105 days                                | 1-0                 | Chinese Academy of Sciences (1975) |
| Hookworm ova<br><u>N.americana</u> | Night soil                           | 35-55<br>35-65<br>35-60 | 24 hours<br>24 hours<br>24 hours        | 0<br>0<br>0         | Nicholls and Gunawardena (1939)    |

- not stated.

REFERENCES

Adams, R. 1971. Composting tree bark with sewage. Compost Science 12(3): 30-32.

Alestalo, A., and Koistinen, O. 1975. On the possibilities of composting bark and where this compost can be used. ISWA Information Bulletin 17:13-17.

Angle, J. S., Wolf, D. C., and Hall, J. R. III. 1981. Turfgrass growth aided by sludge compost. Biocycle 22(6):40-43.

Arditti E. 1973. Use of municipal garbage compost in Israel. Research and observation, 1959-1970. ISWA Information Bulletin 11-12:70-78.

Baetgen, D. 1962. Die Kompostierung und das Absterben pathogener Bakterien der TPE und Ruhrgruppe. Städtehygiene 13(5):81-85.

Barth, H., and Brauss, F. W. 1967. Untersuchungen zur Hygiene der Schnellkompostierung nach dem Multibacto-Verfahren. Verhalten von Salmonellen beim Rotervorgang Städtehygiene, 4:79-85.

Bidlingmaier, W. 1979. Aerob-Thermophile Klärschlammbehandlung. Fortbildungs-zentrum Gesundheits und Umweltschutz Berlin, e.V. Kurzfassungen der Referate II Seminar 15-16 März.

Bidlingmaier, W., and Bickel, F. 1980. Klärschlammkompostierung. Wiener Mitterlungen Behandlung und besertigung von Kommunalen und industriellen Schlämmen Band 34:El-9.

Bidlingmaier, W., and Tabassran, O. 1980. Schlammkompostierung. Korrespondenz Abwasser 27(2):133-36.

Blum, D., and Feachem, R. G. 1985. Health aspects of night soil and sludge use in agriculture and aquaculture; Part III an epidemiological perspective. IRCWD Report, No. 5.

Breer, \_\_\_. 1980. Die Hygienisierung von Klärschlamm mit Lilfe verschiedener Behandlungserahrer Wasser Energie Luft 72(12):41-44.

Breidenbach, A. W. 1971. Composting of Municipal Solid Wastes in the United States. U.S. Environmental Protection Agency Report SW47R, chapters 3, 4.

Brinsko, G. A. 1974. Sludge disposal by incineration of ALCOSAN. In Proceedings of the National Conference on Municipal Sludge Management, pp. 157-62. Rockville, Md.: Information Transfer, Inc.

Bucher, R. 1974. Einsatz von klärschlamm müll und müll-klärschlamm komposten. Der Deutsche Weinbau.

Bundesrepublik 1979. Preliminary instruction leaflet, "Quality criteria and recommendations for application of compost from domestic refuse/sewage sludge."

Burge, W. D., and Cramer, W. N. 1974. Destruction of pathogens by composting sewage sludge. Progress report Joint Project. M.E.S. and Water Resources Management Administration, Washington, D.C.

Burge, W. D., Cramer, W. N., and Epstein, E. 1976. Pathogens in sewage sludge and sludge compost. Proc. A.S.C.E. San. Eng. Dir. Dec. paper no. 76-2559.

Burge, W. D., Marsh, P. B., and Millner, P. D. 1977. Occurrence of pathogens and microbial allergens in the sewage sludge composting environment. National Conference on Composting of Municipal Residues and Sludges, August 23-25, pp. 128-35.

Burge, W. D., Cramer, W. N., and Epstein, E. 1978. Destruction of Pathogens in Sewage Sludge by Composting (reprint). Transactions of the ASAE 21(3):510-14.

Burge, W. D., and Millner, P. D. 1980. Health aspects of composting: Primary and secondary pathogens. In G. Bilton, B. L. Damron, G. T. Edds, and J. M. Davidson (eds.), Sludge-Health Risks of Land Application, pp. 245-64. Ann Arbor, Mich.: Ann Arbor Science Publishers.

Burge, W. D., Colacicco D., and Cramer, W. N. 1981. Criteria for achieving pathogen destruction during composting. J. Water Pollution Control Federation 53(12):1683-90.

Camp Dresser and McKee, Inc. 1975. Alternative sludge disposal systems for the District of Columbia Water Pollution Control Plant of Blue Plains. Washington, D.C.: Department of Environmental Services.

Carroll, T. E., Maase, D. L., Geneco, J. M., and Ifead, C. N. 1975. Review of landspreading liquid municipal sewage sludge. EPA-676/2-75-049. Washington, D.C.: Environmental Protection Agency, Office of Research and Development.

Chinese Academy of Sciences, Dept. of Environmental Health, Peking. 1975. Chinese Medical Journal 1(6):407-12.

Chrometzka, P. 1972. Über den vorteil ausgerifter Müllklärschlammkomposte gegenüber nicht ausgeriften. ANS Mitteilungen no. 29 Wasser & Abwasser, vol. 1.

Colacicco, D., Derr, D., and Kasper, V. 1977. Major cost factors in composting sewage sludge in aerated piles. Beltsville, Md.

Cooney, D. G., and Emerson, R. 1964. Thermophilic fungi. An account of their biology, activities and classification. San Francisco: W. H. Freeman and Company.

Cooper, R. C., and Golueke, C. G. 1979. Survival of enteric bacteria and viruses in compost and its leachate. Compost Science/Land Utilization 20(2):29-35.

Dalmat, D. J., Parr, J. F., Von Lignau, A., and Laguerre, P. A. 1982. Biocycle 23(6):43-46.

Dallaire, G. 1978. Aerated-pile composting: A promising new alternative for disposing of sewage sludge. Civil Engineering ASCE (September).

de Bertoldi, M., Citernesi, U., and Griselli, M. 1980. Bulking agents in sludge composting. Compost, Science/Land Utilization 21(1):32-35.

de Bertoldi, M., Vallini, G., Pera, A., and Zucconi, F. 1982. Comparison of 3 windrow compost systems. Biocycle 23(2):45-50.

Diaz, L. F., and Golueke, C. G. 1985. Solid Waste Management in Developing Countries. Biocycle 26(5):46-52.

Epstein E., Willson, G. B., Burge W. D., Mullen D. C., and Enkin, N. K. 1976. A forced aeration system for composting wastewater sludge. Journal of Water Pollution Control Federation 48(4):688-94.

Ernst von A. A. 1972. Müllklärschlamm kompost-Herstellung und Anwendung. Der StädteTag 9:511-12.

Faust, J., and Romano, L. S. 1978. Composting sewage sludge by means of forced aeration at Windsor, Ontario. Utilization and Disposal no. 6. Ontario Ministry of Environmental Sludge.

Farkasdi, G. 1968. Wirkung der Vorrote im Etagenturm auf die Mikroflora und den Stoffabbau. University of Giessen Institut für handwirtschaftliche Mikrobiologie der Justus Liebig, pp. 75-85.

Feachem, R. G., Bradley, D. J., Garelick, H., and Mara, D. D. 1980. Health Aspects of Excreta and Sullage Management: A State of the Art Review. World Bank Studies in Water Supply and Sanitation, Appropriate Technology for Water Supply and Sanitation, vol. 3.

Feachem, R. G., Bradley, D. J., Garelick, H., and Mara, D. D. 1983. Sanitation and Disease. New York: J. Wiley and Sons.

Ferrero, G. 1978. The bio-tunnel for composting solid urban waste and sewage sludge. Inquinamento 20(7/8):83, 85-95.

Finstein, M. S., Cirello, J., Suler, D. J., Morris, M. L., and Strom, P. F. 1980. Microbial ecosystems responsible for anaerobic digestion and composting. Journal of Water Pollution Control Federation 52(II):2675-85.

Gaby, W. L. 1975. Evaluation of health hazards associated with solid waste/sewage sludge mixture. EPA 670/2-75023. Cincinnati, Ohio.

Glathe, H., and Farkasdi, G. 1966. Bedeutung verschiedener faktoren für die Kompostierung. In Kumpf, E. H. N., Maas, K., and Straum, H. (eds.), Müll Handbuch Erich Schmidt Verlag, pp. 1-23.

Golueke, C. G., and Gotaas, H. B. 1954. Public Health aspects of waste disposal by composting. Amer. J. Public Health 44:339-48.

Golueke, C. G. 1972. Composting a Study of the Process and Its Principles. Emmaus, Pa.: Rodale Press.

Golueke, C. G., Lafrenz, D., Chaser, B., and Diaz, L. F. 1980. Composting combined refuse and sewage sludge. Compost Science/Land Utilization 21(5):42-48.

Golueke, C. G. 1983. Epidemiological Aspects of Sludge Handling and Management. Biocycle 24(4):50-58.

Gotaas, H. B. 1956. Composting: Sanitary disposal and reclamation of organic wastes. WHO Monograph series 31. Geneva: World Health Organization.

Gunn, G. A. 1980. Virginia compost project develops new approaches. Compost Science/Land Utilization 21(5):28-31.

Grote, H., and Model, J. 1978. Lippe-Kompost aus Lemgo. Müll und Abfall (6):185-90.

Hand, C. W., Gershman, H. W., and Navarro, P. 1977. Markets Study for Composted Sewage Sludge in the Metropolitan Washington Area. A case study. Natl. Conf. on Composting of Municipal Residues and Sludges sponsored by: Information Transfer Inc. Hazardous Control Research Institute, Washington, D.C.

Hart, S. A. 1967. Composting (solid waste management), European activity and American potential. A report to the U.S. Public Health Service office of solid wastes 43 pp.

Hart, P. D., Russell, E., Jr., and Remington, J. C. 1969. The compromised host and infection. II. Deep fungal infections. J. Infect. Diseases 120:169-91.

Hasuk, A. 1979. Einjährige Qualitätsuntersuchungen von Müll und Müllklärschlammkomposten in vier Kompostierungsanlagen. Müll und Abfall II(10):275-78.

Haug, R. T. 1980. Compost Engineering: Principles and Practice. Ann Arbor, Mich.: Ann Arbor Science Publishers.

Hayes, Denis. 1978. Repairs, Reuse, Recycling--First Steps Toward a Sustainable Society. Worldwatch Paper no. 23. Washington, D.C.: Worldwatch Institute.

Heaman, J. D. 1977. Composting - An approach to using sewage waste. Compost Science 18(1):28-29.

Helfer, K. 1975. Die Müll und Klärschlammverwertung des gemeinde verbandes der region Biel (Schewiz). Forum Umwelthygiene 17:343-95.

Helfer, K. 1977. Betriebserfahrungen mit der kompostierung nach dem system brikollare. ISWA Informationsblatt 23:22-24.

Hirschheydt, A. von. 1975. Zur Müllkompostierung in Frankreich. Müll und Abfall 7:196-204.

Hileman, L. H. 1982. Fortified Compost Product shows promise as fertilizer. Biocycle 23(1):43-44.

Hornick, S. B., Murray, J. J., Chaney, R. L., Sikora, L. J., Parr, J. F., Burge, W. D., Willson, G. B., and Tester, C. F. 1979. Use of sewage sludge compost for soil improvement and plant growth. USDA, SEA, Agric. Reviews and Manuals - ARM-NE-6, pp. 11.

Hovsenius, G. 1975. Composting and use of compost in Sweden. J. Water Pollut. Control Fed. 147(4):741-47.

Hughes, E. G. 1977. Reviewing an English composting plant. Compost Science 18(2):18-21.

Hughes, E. G. 1986. Solid Waste Composting in Egypt. Biocycle 27(2):26-27.

Ingerle K. von. 1978. Erfahrungen mit der gemeinsam Verrottung von Müll und Klärschlamm in d'sterreich. Müll und. Abfall 10(1):26-28.

Ingerle K. 1980. Gemeinsame ablagerung von Klärschlamm und Hausmüll. Wiener Mitteilungen Behandlung und beseitigung von Kommunalen und Industriellen Schlämmen, Band 34:1-15.

Jäger, B. 1974. Investitions und Betriebskosten von Kompostwerken Müll und Abfall 32 Lfg VI (5610). In Erich Schmidt Verlag Kumpf, F. H., Mass, K., and Straumm, H. (eds.), Mull Handbuch, pp. 1-17.

Jäger, B. 1977. Stand der Kennstrusse und erfahrungen mit dem Aufbereitungs und Kompostierungsverfahren System Willisch. Müll und Abfall 9(2):44, 46.

Jäger, B., and von Jäger, J. 1978. Geruchsbekämpfung in Kompostwerken am Beispiel Heidelberg. Müll und Abfall 10(2):48-54.

Japan Sewage Works Agency. 1980. Agricultural use of sewage sludge. Report of research work 1:215-50.

Kane, B. E., and Mullins, J. T. 1973a. Thermophilic fungi in municipal waste compost system. Mycologia 65:1087-1100.

Kane, B. E., and Mullins, J. T. 1973b. Thermophilic fungi and the compost environment in a high-rate municipal composting system. Compost Science 14(6):6-7.

Kawata, K., Cramer, W. W., and Burge, W. D. 1977. Composting destroys pathogens in sewage solids. Water and Sewage Works 124(4):76-79.

Kim, B. H., and Bae, M. 1981. Night Soil Composting. Proceedings of the Regional Workshop on Rural Development Technology, Seoul, Korea.

Klausing, O. 1975. Biologische Grundlagen der Stroh-Klärschlamm - Kompostierung nach dem Bio-mist Verfahren. Hessische Landesanstalt für Umwelt Wiesbaden.

Knoll, H. 1980. Die effektivität von Klärschlamm-aufbereitungsverfahren im hindblick auf die forderungen der Hygiene zur Vewertung der produkte. Osterreichische Abwasser-Rundschau (5):111-16.

Kohler, H., and Hardmeier, H. U. 1980. Grenzwerte für Müll und Müll Klärschlamm kompost. Stellungnahme der KBA Beringen KT Schaffhausen Schweiz.

Krige, P. R. 1964. A survey of the pathogenic organisms and helminth ova in composts and sewage sludge. J. and Proceedings Inst. Sewage Purification 3:215-20.

Krogstad, O., and Gudding, R. 1975. The survival of some pathogenic microrganisms during reactor composting. Acta Agr. Scandinavica (Sweden) 25:281-84.

Kuchta, H. D. 1967. Kompostierung von Müll und Klärschlamm nach dem dano-biostabilisator-verfahren. Aufbereitungs - Technik 5:253-56.

Kurzweil, H. E. 1980. Composting of sewage sludge. Osterreichische Abwasser-Rundschau (5):122-25 (in German).

Lacey, J. 1974. Thermophilic actinomycetes associated with farmer's lung. In R. de Haller and F. Suter (eds.), Aspergillosis and Farmers Lung in Man and Animal, pp. 155-163. Bern, Switzerland: Hans Huber.

Leonhardt, H. W. 1979. Verrottung von ballen aus mullklärschlamm. Müll und Abfall 11(7):214-18.

Leonhardt, H. W. 1981. Modell-fleisschemen für kompostwerke. Müll und Abfall 13(7):194-204.

Mach, R. 1978. Anlagen und Systeme zur Kompostierung von Abwasserschlämmen in der Bundesrepublik Deutschland stand - Tendenzen. Müll und Abfall 10(1):1-9.

Maebashi, R. 1980. Composting of sewage sludge by mechanical facility (Minamitama). Japan Sewage Works Bureau, pp. 1-11.

Marsh, P. B., Millner, P. D., and Kia, J. M. 1979. A guide to recent literature on aspergillosis as caused by Aspergillus fumigatus. U.S. Dept. of Agriculture publication ARM-NE-58EA. Washington, D.C.

McGarry, M. G., and Stainforth, J. 1978. Compost, fertilizer and biogas production from human and farm wastes in the People's Republic of China. IDRC TS8e Ottawa.

Miersch, K., and Strauch, D. 1978. Hygienische Überprüfung der Kompostierung von Siedlungsabfällen in stationären Rottezellen mit Belüftung. Müll und Abfall 10(4):115-21.

Millner, P. D. 1982. Thermophilic and thermotolerant actinomycetes in Sewage Sludge Compost. Devel. Ind. Microbiology 23:61-78.

Millner, P. D., Bassett, D. A., and Marsh, P. B. 1980. Dispersal of Aspergillus fumigatus from self-heating compost piles subjected to mechanical agitation in open air. Appl. and Environ. Microbiol. 39:1000-1009.

Millner, P. D., Marsh, P. B., Snowden, R. B., and Parr, J. F. 1977. Occurrence of Aspergillus fumigatus during composting of sewage sludge. Appl. and Environ. Microbiol. 34(6):765-72.

Moilliet, von G. 1981. Feuchtkompostierung von Klärschlamm - das bewährte alternative-Verfahren bei problematischem flüssigaustrag, chap. 16, pp. 1-8. Kolloquium Klärschlamm behandeln. Luzern, Switzerland.

Morgan, M. T., and Macdonald, F. W. 1969. Tests show MB Tuberculosis doesn't survive composting. J. Environ. Health 32:101-8.

Mühlacker (1980). Bericht zur Kompostierung. Klaranlage Lomersheim Margenthaler Nussbaum in Bitzfeld.

Murray, H. M. 1960. Incidence of Ascaris ova in Pretoria sludge and their reduction by storage (Maturation) in large heaps. Journal and Proceedings of the Institute for Sewage Purification (3):337-42.

Nicholls, L., and Gunawardara, S. A. 1939. The destruction of helminth ova in nightsoil by composting. Ceylon J. Science 5(1):1-9.

Nordsiek, D. 1976. Müll-Klarschlamm-Kompostierung. Nach Dem Brikollare Verfahren. Forum Umwelt Hygiene 27(8):275-79.

Oger, L. 1981. Le compostage aerobie de boues de stations depuration. Le procede B.A.V. Eau et Industrie Dec. no. 60, pp. 35-40.

Olver, W. M. 1979. The life and times of Aspergillus fumigatus. Compost Sci. Land/Utilization 20(1):36-39.

Olver, W. M. 1980. Cold weather sludge composting works in Maine. Compost Science/Land Utilization 21(5):20-22.

Oosthoek, J. 1981. Das Kompostwerk in Wijster. Müll und Abfall 13(7):185-88.

Parr, J. F., Epstein, E., and Willson, G. B. 1978. Composting sewage sludge for land application. Agriculture and Environment 14:123-37.

Pagliai M., Guada, G., LaMarca M., Ginchetti, L., and Lucamank, G. 1981. Effects of Sewage sludges and composts on soil porosity and aggregation. Journal Environ. Quality 10(4):556-61.

Patterson, J. C., and Rodgers, S. 1979. Static Pile Composting - A Waste Treatment Alternative. Parks - Park Techniques 4(1):16-19.

Pereira-Neto, J. T., Stentiford, E. I., Mara, D. D. 1986. Pathogen survival in a refuse/sludge forced aeration compost system. Institution of Chemical Engineers, Effluent Treatment and Disposal and The Annual Research Meeting, University of Bradford 96:373-391.

Pereira-Neto, J. T., Stentiford, E. I., Mara, D. D. 1986. Comparison of windrows and aerated static piles for refuse/sludge composting. International Symposium on Compost, Production Quality and Use. Udine, Italy, 11 pp.

Poincelot, R. P. 1974. A scientific examination of the principles and practice of composting. Compost Sci. 15(3):24-31.

Polprasert, C., and Muttamara, S. 1980. Composting night soil and water hyacinth in the tropics. Compost Science/Land Utilization 21(2):25-27.

Polprasert, C., Edwards, P., Pacharaprakiti, C., Rajput, V. S., and Suthirawuts. 1982. Recycling rural and urban night soil in Thailand. IDRC final report AIT Research Report no. 143 Bangkok.

Rabbani, K. R., Jindal, R., and Kubota, H. 1983. Composting of Domestic Refuse. Environmental Sanitation Reviews, No. 10/11.

Resources Management Associates, Inc. 1975. The land containment project in Montgomery County, Maryland. Report prepared for the Maryland Environmental Service.

Rohde, G. 1972. Pasteurisierung des Klärschlammes oder Kompostierung von Klärschlamm und Müll vor der Anwendung zu Düngungszwecken. Wasser Abwasser (5):129-31.

Sander von H. 1967. Verfahren und probleme der Kompostierung von Müll und Abwasserfaulschlamm für die Verwendung im Landbau. Zeitschrift für Kulturtechnik und Flurbereinigung 6(6):345-53.

Sasser, J. N. 1971. An introduction to the plant nematode problem affecting world crops and a survey of current control methods. Pflanzenchuts-Nachrichten Bayer 24(1):3-47.

Savage, J., Chase, T., and MacMillan, T. D. 1973. Population changes in enteric bacteria and other microorganisms during aerobic thermophilic windrow composting. Appl. Microbiol. 26:969-74.

Savage, G. M., Golueke, C. G. Major Cost Elements in Co-Composting. 1986. Biocycle 27(1):33-35.

Schneider, von P. 1981. Das Triga-verfahren zur Klärschlamm-kompostierung. Kolloquium Klärschlamm behandeln 29-30 Jan. in Horw.bei Luzern, Switzerland.

Schuchardt, F., and Baader, W. 1979. Kompostierung von brikettiertem Klärschlamm. Müll und Abfall II(8):205-14.

Schwabe, von O. H. 1973. Müll und Klärschlammbehandlungsanlage in Flensburg. der Städtetag (5):302-5.

Schwanhäuser, H. von. 1978. Erfahrungen mit dem Schlammverrotlungssystem Dambach Schnorr in Rastäft W. Germany. Müll und Abfall 10(1):22-25.

Scott, J. C. 1952. Health and Agriculture in China: A Fundamental Approach to Some of the Problems of World Hunger. London: Faber and Faber.

Shuval, H. I., Gunnerson, C. G., and Julius, De Anne. 1981. Night-soil Composting. Appropriate Technology for Water Supply and Sanitation Series, vol. 10, Washington, D.C.: World Bank.

Sikora, L. J., Willson, G. B., Colacicco, D., and Parr, J. F. 1981. Materials balance in aerated static pile composting. Journal of the Water Pollution Control Federation 53(12):1701-7.

Smith, R., and Eilers, R. G. 1975. Computer evaluation of sludge handling and disposal cost, pp. 30-59. In Proceedings of the National Conference on Municipal Sludge Management and Disposal. Rockville, Md.: Information Transfer, Inc.

Spennes, G., and Britsch, Th. 1977. Klärschlamm kompostierung ohne Zusätze Kommunalwirtschaft (9):320-25.

Spohn, E. 1978. Neue einfache verfahren der abfallverwertung. Compost Science/Land Utilization 19(3):26-27.

Sridhar, M. K. C., Ewerikhare, E. O., Bammeke, A. O., Omishakin, M. A. 1985. Composting in a Nigerian Community. Biocycle 26(3):50, 52-54.

Stentiford, E. I., Mara, D. D., Taylor, P. L., Leton, T. G. 1983. Forced Aeration Co-Composting of Domestic Refuse and Sewage Sludge, Proceedings of the International Conference on Composting of Solid Wastes and Slurries. University of Leeds, England 58-72.

Stentiford, E. I., Pereira-Neto, T. J., Taylor, P. L., Mara, D. D., Lopez-Real, J., Witter, E. 1985. Sanitisation potential of composting for sewage sludge and refuse in a static pile system in Advances in Water Engineering. Ed. T. H. Y. Tebbutt. Elsevier Applied Science Pub. 269-277.

Stentiford, E. I., Taylor, P. I., Leton, T. G., Mara, D. D. 1985. Forced Aeration Composting of Domestic Refuse and Sewage Sludge. J. Inst. Water Pollution Control 84(1), pp. 23-32.

Stern, G. 1975. Processing, economics, and sale of heat dried sludge. In Proceedings of the National Conference on Municipal Sludge Management and Disposal, pp. 235-44. Rockville, Md.: Information Transfer, Inc.

Sterritt, \_\_\_, and Lester, J. M. 1980. The value of sewage sludge to agriculture and effects of the agricultural use of sludges contaminated with toxic elements: A review. The Science of the Total Environment 16:55-90.

Stone, R. 1949. The Shnoyang, China, Night Soil Fertilizer Reclamation Plant. Sewage Works Journal 21(6):992-1001.

Strauch, D., Berg, T., and Fleischle, W. 1980. Microbiological studies for disinfection of sewage sludge. III. Experiments on the composting of straw and digested sludge. GWF-Wasser/Abwasser 121(6):298-301.

Sunawira, U. 1968. A system of composting in West Java Indonesia. Compost Science 9(2):22.

Tabasaran, O. 1976. Tests on the composting of domestic refuse and wastewater sludge. Wasser-Abwasser Gewasser 20:1-35.

Tabasaran, O. 1980. Aerobic stabilization of sludge by composting on straw. Ingegneria Ambientale 9(9):111-16.

Tabasaran, O., and Lausterer, W. 1979. Composting of raw domestic sewage sludge in clumps together with straw. Abwassertechnik 30(1):17-21.

Tabasaran, O., Bidlingmaier, W., and Bickel, F. 1981. Abwasserschlammbehandlung in Bioreaktoren. Kolloquim Klarschlamm behandeln 29-30 Jan.in Horw bei Luzern, Switzerland.

Tansey, M. R. 1971. Isolation of thermophilic fungi from self heated industrial wood chip piles. Mycologia 63:537-47.

Tester, C. F., Parr, J. F., and Paolini, \_\_\_. 1980. Effect of screening on compost properties. Proceedings of Natl. Conference on municipal and industrial sludge composting, Nov. 14-16, Maryland.

Tietjen, C. 1975. The potential of composting in developing countries. Compost Science 16(4):6-7.

Tokyo Metropolis Labour Economy Office. 1979. Agricultural utilization of Minamitama sewage and urban refuse compost research outline.

Toyohashi City, Japan. N.d. Urban and ural environmental combination system (reprint).

U.S. Environmental Protection Agency (USEPA). 1974. Process design manual for sludge treatment and disposal. EPA technology transfer. EPA 625/1-74-006. Washington, D.C.

Van Note, R. H., Herbert, P. V., Patei, R. M., Chupek, C., and Feldman, L. 1975. A guide to the selection of cost effective wastewater treatment systems. U.S. E.P.A. 430/9-75-002. Washington, D.C.

Weber, H. 1983. Experiences in building of compost plants in developing countries.

Wesner, G. M. 1978. Sewage sludge composting. In Sludge Treatment and Disposal. Sludge Disposal. Vol. 12. U.S. EPA 625/4-70-012. Washington, D.C.

Widmer, O., and Konstandt, H. G. 1978. Klärschlammkompostierung ohne zuschlagstoffe Müll und Klärschlammverwertung Erfahrungen und Tendenzen, 18 Oct. 1978 in Konstanz am Bodensee, Switzerland.

Wiley, B. B., and Westerberg, S. C. 1969. Survival of human pathogens in composted sewage. Applied Microbiology 18:994-1001.

Wiley, J. S. 1962. Pathogen survival in composting municipal wastes. Journal of the Water Pollution Control Federation 34:80-90.

Willetts, S. R. 1979. Advanced Composting - The Austrian Way. Environ. Pollut. Management 9(2):36, 38-39.

Willson, G. B., Parr, J. F., Epstein, E., Marsh, P. B., Chaney, R. L., Colacicco, D., Burge, W. D., Sikora, L. J., Tester, C. F., and Hornick, S. 1980. Manual for composting sewage sludge by the Beltsville aerated pile method. U.S. EPA 600/8-80-022 May 1980. Washington, D.C.

Wolf, H. W. 1974. Composting sludge in Germany. Compost Science 15(6):31.

Wyatt, J. M., and White, P. C. 1975. Sludge processing, transportation, and disposal/resource recovery: A Planning perspective. U.S. Environmental Protection Agency, Water Planning Division, WPO 12-75-01 p. 186. Washington, D.C.

## Distributors of World Bank Publications

Algeria: Office des Publications Universitaires, 1, place centrale de Ben-Aknoun, Algiers

Argentina: Carlos Hirsch, SRL, Galeria Guemes, Florida 163, 4th Floor-Ofc. 433/463, 1333 Buenos Aires

Australia, Papua New Guinea, Fiji, Solomon Islands, Vanuatu: Info-Line, Overseas Document Delivery, Box 506, GPO, Sydney, NSW 2001

Austria: Gerold and Co., A-1011 Wien, Graben 31, Austria

Bahrain: Middle East Marketing Research Bureau, Branch Office: Bahrain Research and Consultancy Associates W.L.L., P.O. Box 2750, Manama Town 317

Bangladesh: Micro Industries Development Assistance Society (MIDAS), G.P.O. Box 800, Dhaka

Belgium: Publications des Nations Unies, Av. du Roi 202, 1060 Brussels

Brazil: Publicacoes Tecnicas Internacionais Ltda., Rua Peixoto Gomide, 209, 01409 Sao Paulo, SP

Burma: See Singapore

Canada: Le Diffuseur, C.P. 85, 1501 rue Ampere, Boucherville, Quebec J4B 5E6

Chile: Editorial Renacimiento, Miraflores 354, Santiago

Colombia: Enlace Ltda., Aptdo. Aereo 34270, Bogota D.E.

Costa Rica: Libreria Trejos, Calle 11-13, Av. Fernandez Guell, San Jose

Cyprus: MEMRA Information Services, Head Office, P.O. Box 2096, Nicosia

Denmark: SamfundsLitteratur, Rosenørns Alle 11, DK-1970 Frederiksberg C.

Dominican Republic: Editora Taller, C. por A., Isabel la Católica a Esq. Restauracion, Apdo. postal 2190, Santo Domingo

Egypt, Arab Republic of: Al Ahram, Galaa Street, Cairo

Fiji: See Australia

Finland: Akateeminen Kirjakauppa, P.O. Box 128, SF-00101, Helsinki 10

France: World Bank Publications, 66, avenue d'Iéna, 75116 Paris

Germany, Federal Republic of: UNO-Verlag, D-5300 Bonn 1, Simrockstrasse 23

Greece: MEMRA Information Services, Branch Office, 24, Ippodamou Street, Athens-11635

Hong Kong, Macao: Asia 2000 Ltd., 6 Fl., 146 Prince Edward Road, W, Kowloon

Hungary: Kultura, P.O. Box 149, 1389 Budapest 62

India: New Delhi: (for single titles) UMS Publishers' Distributors Ltd., Post Box 7013, 3 Ansari Road, New Delhi 110002; (for subscription series) Universal Subscription Agency Pvt. Ltd. (Pending), 18-19 Community Centre Saket, New Delhi 110 017

UMS Branch Office: 10 First Main Road, Gandhi Nagar, Bangalore 560009; Apeejay Chambers, P.O. Box 736, 3 Wallace Street, Bombay 400001; 8/1-B, Chawringhee Lane, Calcutta 700016; 7/188, 1(CA), Swarup Nagar, Kampu 200002; Sriangan Road, Nungambakkam, Madras 600034

Indonesia: Pt. Indira Limited, Jl. Sam Ratulangi 17, Jakarta Pusat, PO Box 181

Ireland: TDC Publishers, 12 North Frederick Street, Dublin 1

Israel: Jerusalem Post, Jerusalem Post Building, P.O. Box 81, Romema Jerusalem 91000

Italy: Licos, Libreria Commissionaria, Sansoni S.P.A., Via Lamarmora 45, Casella Postale 552, 50121 Florence

Ivory Coast: Centre d'Édition et de Diffusion Africaines (CEDA), 04 B.P. 541, Abidjan 04 Plateau

Japan: Eastern Book Service (EBS), 37-3, Hongo 3-Chome, Bunkyo-ku 113, Tokyo

Jordan, MEMRA Information Services, Branch Office, P.O. Box 3143, Jabal, Amman

Kenya: Africa Book Service (E.A.) Ltd., P.O. Box 45245, Nairobi

Korea, Republic of: Pan Korea Book Corporation, 134, 1-Ka, Shinmun-RO, Jongro-Ku, P.O. Box 101, Kwanghamun, Seoul

Kuwait, MEMRA Information Services, Branch Office, P.O. Box 5465, Kuwait

Macao: See Hong Kong

Malaysia: University of Malaya, Cooperative Bookshop, Limited, P.O. Box 1127, Jalan Pantai Baru, Kuala Lumpur 59200

Maldives: See Sri Lanka

Mexico: INFOTEC, San Fernando No. 37, Col. Torillo Guadalupe, Tlalpan

Morocco: Societe d'Etudes Marketing Marocaine, Branch Office, 2, rue Moliere, Casablanca

Netherlands: Medical Books Europe, BV (MBE), Noorderkwal 38, 7241 BL Lochem

New Zealand: R. Hill and Son Ltd., Private Bag, New Market, Auckland

Nigeria: University Press Limited, Three Crowns Building Jericho, Private Mail Bag 5095, Ibadan

Northern Ireland: See United Kingdom

Norway: For single titles: Tanum-Karl Johan, A.S., Books Box 1177 Sentrum, 0107, Oslo 1

Pakistan: Mirza Book Agency, 63, Shahrah-e-Quaid-e-Azam, P.O. Box No. 729, Lahore 3

Panama: Libreria Cultural Panamena, S.A. (LCP), Via Espana 16, Panama Zone 1

Papua New Guinea: See Australia

Peru: Editorial Desarrollo SA, Apartado 3824, Ica 242, OE. 106, Lima 1

Philippines: National Book Store, P.O. Box 1934, Manila

Portugal: Livraria Portugal, Rua Do Carmo 70-74, 1200 Lisbon

Saudi Arabia: Jarir Book Store, P.O. Box 3196, Riyadh—11471

Singapore, Taiwan, Burma: Information Publications, Private, Ltd., 02-06 First Floor, Pei-Fu Industrial Bldg., 24 New Industrial Road, Singapore 1953

Solomon Islands: See Australia

South Africa: For single titles: Oxford University Press, Southern Africa, Academic Division, P.O. Box 1141, Cape Town 8000. For subscription series: International Subscription Serv., P.O. Box 41093, Craighall, Johannesburg

Spain: Mundiprensa Libros, S.A., Castello 37, 28001 Madrid

Sci Lanka, Maldives: Lake House Bookshop, P.O. Box 244, 100, Sir Chittampalam A. Gardiner Mawatha, Colombo 2

Sweden: For single titles: ABCE Fritzes Kungl. Hovbokhandel, Regeringsgatan 12, Box 16356, S-103 27 Stockholm. For subscription orders: Wennergren-Williams AB, Box 30004, S-104 25 Stockholm

Switzerland: Librairie Payot, 6 Rue Grenus, Case postal 101, CH 1211 Geneva 11

Taiwan, China: See Singapore

Tanzania: Oxford University Press, P. O. Box 5299, Dar es Salaam

Thailand: Central Department Store, 306 Silom Road, Bangkok

Trinidad & Tobago: Systematics Studies Unit, 55 Eastern Main Road, Curepe, Trinidad

Tunisia: Societe Tunisienne de Diffusion, 5 Avenue de Carthage, Tunis

Turkey: Haset Kitabevi A.S., 469, İstiklal Caddesi, Beyoglu-Istanbul

Uganda: Shipping: Uganda Bookshop, P.O. Box 7145, Kampala

United Arab Emirates: Middle East Marketing Research Bureau, Branch Office, P. O. Box 6097, Sharjah

United Kingdom and Northern Ireland: Microinfo Ltd., P.O. Box 3, Alton, Hampshire GU 34 2PG

Venezuela: See Australia

Venezuela: Libreria del Este, Aptdo. 60.337, Caracas 1060-A

Western Samoa: Wesley Bookshop, P.O. Box 207, Apia

Yugoslavia: Jugoslovenska Knjiga, YU-11000 Belgrade/Trg Republike, 8th Floor

Zimbabwe: Textbook Sales Pvt. Ltd., Box 3799, Harare

WORLD BANK TECHNICAL PAPERS (continued)

No. 33. Guidelines for Calculating Financial and Economic Rates of Return for DFC Projects  
(also in French, 33F, and Spanish, 33S)

No. 34. Energy Efficiency in the Pulp and Paper Industry with Emphasis on Developing Countries

No. 35. Potential for Energy Efficiency in the Fertilizer Industry

No. 36. Aquaculture: A Component of Low Cost Sanitation Technology

No. 37. Municipal Waste Processing in Europe: A Status Report on Selected Materials and Energy Recovery Projects

No. 38. Bulk Shipping and Terminal Logistics

No. 39. Cocoa Production: Present Constraints and Priorities for Research

No. 40. Irrigation Design and Management: Experience in Thailand

No. 41. Fuel Peat in Developing Countries

No. 42. Administrative and Operational Procedures for Programs for Sites and Services and Area Upgrading

No. 43. Farming Systems Research: A Review

No. 44. Animal Health Services in Sub-Saharan Africa: Alternative Approaches

No. 45. The International Road Roughness Experiment: Establishing Correlation and a Calibration Standard for Measurements

No. 46. Guidelines for Conducting and Calibrating Road Roughness Measurements

No. 47. Guidelines for Evaluating the Management Information Systems of Industrial Enterprises

No. 48. Handpumps Testing and Development: Proceedings of a Workshop in China

No. 49. Anaerobic Digestion: Principles and Practices for Biogas Systems

No. 50. Investment and Finance in Agricultural Service Cooperatives

No. 51. Wastewater Irrigation: Health Effects and Technical Solutions

No. 52. Urban Transit Systems: Guidelines for Examining Options

No. 53. Monitoring and Evaluating Urban Development Programs: A Handbook for Program Managers and Researchers

No. 54. A Manager's Guide to "Monitoring and Evaluating Urban Development Programs"

No. 55. Techniques for Assessing Industrial Hazards: A Manual

No. 56. Action-Planning Workshops for Development Management: Guidelines



## **The World Bank**

**Headquarters**  
1818 H Street, N.W.  
Washington, D.C. 20433, U.S.A.  
Telephone: (202) 477-1234  
Telex: WUI 64145 WORLDBANK  
RCA 248423 WORLDBK  
Cable Address: INTBAFRAD  
WASHINGTONONDC

**European Office**  
66, avenue d'Iéna  
75116 Paris, France  
Telephone: (1) 47.23.54.21  
Telex: 842-620628

**Tokyo Office**  
Kokusai Building  
1-1 Marunouchi 3-chome  
Chiyoda-ku, Tokyo 100, Japan  
Telephone: (03) 214-5001  
Telex: 781-26838

## **UNDP**

**New York**  
United Nations Development Programme  
1 United Nations Plaza  
New York, New York 10017  
Telephone: (212) 754-1234  
Telex: 125980 (domestic)  
232-422 (overseas)  
Cable Address: UNDEVPRO  
NEW YORK

**Geneva Office**  
Palais des Nations  
CH-1211 Geneva 10  
Switzerland  
Telephone: 98-84-00  
DBH Telephone: DDH98-58-50  
Telex: (UNDP) 28.96.20 or (UN) 28.96.96  
Cable Address: UNDEVPRO  
GENEVA (SWITZERLAND)

**Tokyo Office**  
Shin Aoyama Building  
Room 2255  
1-1, Minami-Aoyama 1-Chome  
Minato-Ku  
Tokyo 107, Japan  
Telephone: 03-475-1619/20  
Telex: J28 334  
AB TKOPI J28 334  
Cable Address: UNDEVPRO  
TOKYO (JAPAN)